

Town of Hardwick

Unified Development Bylaws

Amended on September 5, 2024

The 2024 Bylaw update and amendment was created with Heather Carrington, CCDS, LLC and funded by the Bylaw Modernization Grant Program, which is administered by the Vermont Department of Housing and Community Development.

| | |
|---|-----------|
| <u>Article 1. Authority & Purpose</u> | <u>7</u> |
| <u>Section 1.1 Enactment</u> | <u>7</u> |
| <u>Section 1.2 Purpose</u> | <u>7</u> |
| <u>Section 1.3 Application & Interpretation</u> | <u>8</u> |
| <u>Section 1.4 Adoption & Effective Date</u> | <u>8</u> |
| <u>Section 1.5 Severability</u> | <u>8</u> |
| <u>Article 2. Zoning Districts</u> | <u>9</u> |
| <u>Section 2.1 Establishment of Zoning Districts & Map</u> | <u>9</u> |
| <u>Section 2.2 Zoning District Boundary Interpretation</u> | <u>9</u> |
| <u>Section 2.3 Application of District Standards</u> | <u>10</u> |
| <u>Article 3. General Regulations</u> | <u>25</u> |
| <u>Section 3.1 Applicability</u> | <u>25</u> |
| <u>Section 3.2 Damaged Structures</u> | <u>25</u> |
| <u>Section 3.3 Access & Frontage Requirements</u> | <u>25</u> |
| <u>Section 3.4 Conversions & Changes of Use</u> | <u>26</u> |
| <u>Section 3.5 Equal Treatment of Housing</u> | <u>26</u> |
| <u>Section 3.6 Existing Small Lots</u> | <u>27</u> |
| <u>Section 3.7 Height Requirements</u> | <u>27</u> |
| <u>Section 3.8 Lot & Yard Requirements</u> | <u>28</u> |
| <u>Section 3.9 Nonconforming Structures & Nonconforming Uses</u> | <u>29</u> |
| <u>Section 3.10 Discontinued Uses</u> | <u>30</u> |
| <u>Section 3.11 Performance Standards</u> | <u>30</u> |
| <u>Section 3.12 Protection of Water Resources</u> | <u>31</u> |
| <u>Section 3.13 Parking & Loading Requirements</u> | <u>33</u> |
| <u>Section 3.14 Sign Regulations</u> | <u>34</u> |
| <u>Section 3.15 Steep Slopes & Erosion Control</u> | <u>39</u> |
| <u>Section 3.16 Storage of Hazardous Materials</u> | <u>39</u> |
| <u>Article 4. Specific Use Standards</u> | <u>40</u> |
| <u>Section 4.1 Applicability</u> | <u>40</u> |
| <u>Section 4.2 Accessory Dwelling</u> | <u>40</u> |
| <u>Section 4.3 Adaptive Reuse of an Historic Structure</u> | <u>40</u> |
| <u>Section 4.4 Recreational Vehicles [Temporary Shelter]</u> | <u>42</u> |
| <u>Section 4.5 Campground</u> | <u>43</u> |
| <u>Section 4.6 Day Care Facility [Home Child Care, Day Care]</u> | <u>44</u> |
| <u>Section 4.7 Residential Care and Group Homes</u> | <u>44</u> |

| | | |
|----------------------------|---|------------------|
| <u>Section 4.8</u> | <u>Extraction of Earth Resources</u> | <u>44</u> |
| <u>Section 4.9</u> | <u>Home Businesses [Home Occupation, Home Industry].....</u> | <u>45</u> |
| <u>Section 4.10</u> | <u>Light Industry</u> | <u>47</u> |
| <u>Section 4.11</u> | <u>Agricultural and Forest Processing:</u> | <u>47</u> |
| <u>Section 4.12</u> | <u>Mixed Use.....</u> | <u>48</u> |
| <u>Section 4.13</u> | <u>Mobile Home Park.....</u> | <u>48</u> |
| <u>Section 4.14</u> | <u>Motor Vehicle Service & Gas Stations.....</u> | <u>49</u> |
| <u>Section 4.15</u> | <u>Protected Public Uses</u> | <u>50</u> |
| <u>Section 4.16</u> | <u>Salvage Yard.....</u> | <u>50</u> |
| <u>Section 4.17</u> | <u>Telecommunications Facility</u> | <u>51</u> |
| <u>Section 4.18</u> | <u>Temporary Structure or Use</u> | <u>57</u> |
| <u>Section 4.19</u> | <u>Private Family Cemeteries.....</u> | <u>58</u> |
| <u>Article 5.</u> | <u>Development Review.....</u> | <u>60</u> |
| <u>Section 5.1</u> | <u>Site Plan Review.....</u> | <u>60</u> |
| <u>Section 5.2</u> | <u>Conditional Use Review</u> | <u>60</u> |
| <u>Section 5.3</u> | <u>Flood Hazard Review</u> | <u>65</u> |
| <u>Section 5.4</u> | <u>River Corridor Protection</u> | <u>70</u> |
| <u>Section 5.5</u> | <u>Planned Unit Development.....</u> | <u>74</u> |
| <u>Section 5.6</u> | <u>Review Procedures.....</u> | <u>77</u> |
| <u>Article 6.</u> | <u>Subdivision Review</u> | <u>78</u> |
| <u>Section 6.1</u> | <u>Applicability</u> | <u>78</u> |
| <u>Section 6.2</u> | <u>Minor Subdivision Review</u> | <u>79</u> |
| <u>Section 6.3</u> | <u>Major Subdivision Review</u> | <u>81</u> |
| <u>Section 6.4</u> | <u>Application of Subdivision Standards</u> | <u>83</u> |
| <u>Section 6.5</u> | <u>General Standards [applicable to all Major Subdivision].....</u> | <u>83</u> |
| <u>Section 6.6</u> | <u>Transportation Facilities & Infrastructure</u> | <u>86</u> |
| <u>Section 6.7</u> | <u>Facilities & Utilities.....</u> | <u>88</u> |
| <u>Section 6.8</u> | <u>Legal Requirements</u> | <u>89</u> |
| <u>Article 7.</u> | <u>Administration & Enforcement</u> | <u>90</u> |
| <u>Section 7.1</u> | <u>Permit & Application Requirements</u> | <u>90</u> |
| <u>Section 7.2</u> | <u>Exemptions</u> | <u>91</u> |
| <u>Section 7.3</u> | <u>Appeals</u> | <u>93</u> |
| <u>Section 7.4</u> | <u>Variances</u> | <u>94</u> |
| <u>Section 7.5</u> | <u>Violations & Enforcement.....</u> | <u>95</u> |
| <u>Section 7.6</u> | <u>Municipal Administrative Requirements.....</u> | <u>96</u> |

| | |
|--|----|
| Article 8. Definitions | 98 |
| Section 8.1 Terms & Use..... | 98 |
| Section 8.2 Definitions..... | 98 |
| Article 1. Authority & Purpose..... | 5 |
| Section 1.1 Enactment | 5 |
| Section 1.2 Purpose | 5 |
| Section 1.3 Application & Interpretation | 6 |
| Section 1.4 Adoption & Effective Date..... | 6 |
| Section 1.5 Severability | 6 |
| Article 2. Zoning Districts | 7 |
| Section 2.1 Establishment of Zoning Districts & Map..... | 7 |
| Section 2.2 Zoning District Boundary Interpretation | 7 |
| Section 2.3 Application of District Standards | 8 |
| Article 3. General Regulations..... | 22 |
| Section 3.1 Applicability | 22 |
| Section 3.2 Damaged Structures..... | 22 |
| Section 3.3 Access & Frontage Requirements | 22 |
| Section 3.4 Conversions & Changes of Use..... | 23 |
| Section 3.5 Equal Treatment of Housing..... | 23 |
| Section 3.6 Existing Small Lots | 24 |
| Section 3.7 Height Requirements | 24 |
| Section 3.8 Lot & Yard Requirements | 25 |
| Section 3.9 Nonconforming Structures & Nonconforming Uses..... | 26 |
| Section 3.10 Discontinued Uses | 27 |
| Section 3.11 Performance Standards | 27 |
| Section 3.12 Protection of Water Resources | 28 |
| Section 3.13 Parking & Loading Requirements | 30 |
| Section 3.14 Sign Regulations..... | 31 |
| Section 3.15 Steep Slopes & Erosion Control..... | 36 |
| Section 3.16 Storage of Hazardous Materials | 36 |
| Article 4. Specific Use Standards | 37 |
| Section 4.1 Applicability | 37 |
| Section 4.2 Accessory Dwelling..... | 37 |
| Section 4.3 Adaptive Reuse of an Historic Structure | 37 |
| Section 4.4 Recreational Vehicles [Temporary Shelter] | 39 |

| | |
|---|-----|
| Formatted: Default Paragraph Font, Check spelling and grammar | ... |
| Formatted | ... |
| Formatted: Default Paragraph Font, Check spelling and grammar | ... |
| Formatted | ... |
| Formatted | ... |
| Formatted | ... |
| Formatted: Default Paragraph Font, Check spelling and grammar | ... |
| Formatted | ... |
| Formatted: Default Paragraph Font, Check spelling and grammar | ... |
| Formatted | ... |

| | | | |
|--------------|---|----|---|
| Section 4.5 | Campground | 40 | Formatted |
| Section 4.6 | Day Care Facility [Home Child Care, Day Care] | 41 | Formatted |
| Section 4.7 | Residential Care and Group Homes | 41 | Formatted |
| Section 4.8 | Extraction of Earth Resources | 41 | Formatted |
| Section 4.9 | Home Businesses [Home Occupation, Home Industry] | 42 | Formatted |
| Section 4.10 | Light Industry | 44 | Formatted |
| Section 4.11 | Agricultural and Forest Processing: | 44 | Formatted |
| Section 4.12 | Mixed Use | 45 | Formatted |
| Section 4.13 | Mobile Home Park | 45 | Formatted |
| Section 4.14 | Motor Vehicle Service & Gas Stations | 46 | Formatted |
| Section 4.15 | Protected Public Uses | 47 | Formatted |
| Section 4.16 | Salvage Yard | 47 | Formatted |
| Section 4.17 | Telecommunications Facility | 48 | Formatted |
| Section 4.18 | Temporary Structure or Use | 54 | Formatted |
| Article 5 | Development Review | 56 | Formatted: Default Paragraph Font, Check spelling and grammar |
| Section 5.1 | Site Plan Review | 56 | Formatted |
| Section 5.2 | Conditional Use Review | 56 | Formatted |
| Section 5.3 | Flood Hazard Review | 61 | Formatted |
| Section 5.4 | River Corridor Protection | 66 | Formatted |
| Section 5.5 | Planned Unit Development | 69 | |
| Section 5.6 | Review Procedures | 72 | |
| Article 6 | Subdivision Review | 73 | Formatted: Default Paragraph Font, Check spelling and grammar |
| Section 6.1 | Applicability | 73 | |
| Section 6.2 | Minor Subdivision Review | 74 | Formatted |
| Section 6.3 | Major Subdivision Review | 76 | Formatted |
| Section 6.4 | Application of Subdivision Standards | 78 | Formatted |
| Section 6.5 | General Standards [applicable to all Major Subdivision] | 78 | Formatted |
| Section 6.6 | Transportation Facilities & Infrastructure | 81 | Formatted |
| Section 6.7 | Facilities & Utilities | 83 | Formatted |
| Section 6.8 | Legal Requirements | 84 | Formatted |
| Article 7 | Administration & Enforcement | 85 | Formatted: Default Paragraph Font, Check spelling and grammar |
| Section 7.1 | Permit & Application Requirements | 85 | Formatted |
| Section 7.2 | Exemptions | 86 | Formatted |
| Section 7.3 | Appeals | 88 | Formatted |
| Section 7.4 | Variances | 89 | Formatted |

~~Section 7.5~~ ~~Violations & Enforcement~~ 90
~~Section 7.6~~ ~~Municipal Administrative Requirements~~ 91
~~Article 8. Definitions~~ 93
~~Section 8.1~~ ~~Terms & Use~~ 93
~~Section 8.2 Definitions~~ 93

Formatted: Default Paragraph Font,
Check spelling and grammar

ARTICLE 1. AUTHORITY & PURPOSE

Section 1.1 Enactment

- (A) Unified Development Bylaws for the Town of Hardwick are hereby established in accordance with 24 V.S.A. Chapter 117, hereinafter referred to as “the Act”. The following text and maps which constitute these regulations shall be known and cited as the “Town of Hardwick Unified Development Bylaws” and shall hereinafter referred to as “the Bylaws” in this document.
- (B) In accordance with 10 V.S.A. Chapter 32 and V.S.A Chapter 117, Sections 4424, 4411, and 4414, these bylaws hereby incorporate regulations for areas at risk of flood damage in the Town of Hardwick, Vermont.

Land Development: A permit is required before commencing **any** form of land development, which includes construction, reconstruction, demolition, establish, change or extension of a use or structure; land subdivision, excavation, or any other activity not specifically exempted in accordance with Section 7.2 of these bylaws. See Article 8 for definition of “Land Development.”

Land Subdivision: The division of a parcel into two or more parcels, for the purposes of immediate or future sale, conveyance, or development. The term “subdivision” includes resubdivisions, amended subdivisions, lot line (boundary) adjustments, and the division of land held in common among several owners.

Section 1.2 Purpose

- (A) The purposes of the Unified Development Bylaws are to:
- encourage the appropriate and efficient use of all lands in the Town of Hardwick in a manner which promotes and protects public health, safety and the general welfare of the community;
 - facilitate the adequate and efficient provision of public facilities and services;
 - implement the Hardwick Town Plan as most recently amended;
 - integrate all administrative and regulatory provisions of zoning, subdivision, flood hazard, and telecommunication regulations as authorized by the Act into a single Bylaw;
 - further the goals and purposes established in the Act [§4302];
 - avoid and minimize the loss of life and property, the disruption of commerce, the impairment of the tax base, and the extraordinary public expenditures and demands on public services that result from flooding;
 - ensure that the selection, design, creation, and use of development is reasonably safe and accomplished in a manner that is consistent with public wellbeing, does not impair floodplain services,
 - manage the flood hazard area designated pursuant to 10 V.S.A. Chapter 32 § 753, the municipal hazard mitigation plan; and make the Town of Hardwick, its citizens, and businesses eligible for federal flood insurance, federal disaster recovery funds, and hazard mitigation funds as may be available; and
 - protect the individual property rights of landowners to the extent consistent with the other purposes of these Bylaws as stated above.

Section 1.3 Application & Interpretation

- (A) The application of these Bylaws is subject to all provisions of the Act. No land development or land subdivision shall commence within the Town of Hardwick except in conformance with the requirements of these Bylaws. Any land development or land subdivision not specifically authorized under these Bylaws, or otherwise exempted under Section 6.1 and/or Section 7.2, is prohibited.
- (B) All uses or structures lawfully in existence as of the effective date of these Bylaws are allowed to continue indefinitely. Changes, alterations or expansions to pre-existing structures or uses shall be subject to all applicable requirements of these Bylaws, including provisions applying to nonconforming uses and/or nonconforming structures under Section 3.9.
- (C) These Bylaws are not intended to repeal, annul or in any way to impair any permit previously adopted or issued, nor shall they in any way impair or remove the necessity of compliance with any other local, state, or federal laws or regulations. Where these Bylaws impose a greater restriction upon the use of a structure or land than is required by any other statute, ordinance, rule, regulation, permit, easement, or agreement, the provisions of these Bylaws shall control.
- (D) In the event of changes to the Act which nullify or supersede a specific provision of these bylaws, the requirements of the Act, as most recently amended, shall control.

Section 1.4 Adoption & Effective Date

- (A) These Bylaws shall take effect 21 days after the date of its adoption by the Hardwick Select ~~B~~board. Upon the effective date of these Bylaws, the zoning Bylaws previously in effect (“Hardwick Unified Development Bylaws,” effective November 24, 2005, 2008, [September 5, 2024](#)) are deemed repealed.
- (B) These Bylaws may be amended or repealed in accordance with the requirements and procedures established in the Act [§§ 4441, 4442].

Section 1.5 Severability

The provisions of these Bylaws are severable. The invalidity of any provision or application of these Bylaws shall not invalidate any other part.

ARTICLE 2. ZONING DISTRICTS

Section 2.1 Establishment of Zoning Districts & Map

(A) The Town of Hardwick is hereby divided into the following zoning districts as described in the accompanying tables (Tables 2.1 - 2.108) and shown on the official zoning map and associated overlays:

- Central Business (CB) District
- ~~Village Center (VC) District~~
- Village Neighborhood (VN) District
- Highway Mixed-Use (HM) District
- Compact Residential (CR) District
- Industrial (I) District
- Rural Residential (RR) District
- Forest Reserve (FR) District
- Flood Hazard Overlay (FHO) District
- River Corridor Overlay (RCO) District
- ~~_____~~

(B) The location and boundaries of each zoning district are depicted on the official “Town of Hardwick Zoning Map” and on the most current flood insurance studies and maps published by the Department of Homeland Security, Federal Emergency Management Agency, National Flood Insurance Program maps, which are adopted by reference and declared to be part of these bylaws. The official zoning map may only be altered by amendment to these bylaws in accordance with Section 1.4 and the Act [§§4441, 4442].

(C) The official zoning map and overlays shall be located in the Hardwick Town Office, and shall be identified by the signatures of the Select Board, as attested to by the Town Clerk. These maps shall be the final authority as to the zoning status of any lands or waters in the town.

Section 2.2 Zoning District Boundary Interpretation

(A) Where uncertainty exists as to the location of district boundaries shown on the official zoning map and overlays, the following rules shall apply:

- (1) Boundaries indicated as following roads, transportation or utility rights-of-way shall be interpreted to follow the centerlines of such features.
- (2) Boundaries indicated as following rivers or streams shall be interpreted to follow the channel centerline and shall move with the centerline of such features.
- (3) Boundaries indicated as following shorelines shall be interpreted as the normal mean water level. In the event of change in the shoreline the boundary shall move with the shoreline.
- (4) Boundaries indicated as following lot lines shall be interpreted to follow the delineated property boundary.

Formatted: Indent: Left: 0.25", No bullets or numbering

- (5) Boundaries indicated as following contour lines shall be interpreted to follow a constant, specified elevation as measured from mean sea level or other accepted reference datum.
 - (6) Boundaries indicated as following compass headings shall be interpreted to follow such headings.
 - (7) Boundaries indicated as parallel or perpendicular to, or extensions of the above features, shall be so interpreted on the ground.
 - (8) Distances not specifically indicated shall be determined by the scale on the official zoning map.
- (B) The abandonment or relocation of a right-of-way or roadway, or the change in a line or feature which references a district boundary line, after the effective date of these bylaws, shall not affect the location of the district boundary line except with regard to shorelines, streams and rivers as specified above.
 - (C) Where available, base flood elevations and floodway limits provided by the National Flood Insurance Program and in the Flood Insurance Study and accompanying maps shall be used to administer and enforce these regulations. In Special Flood Hazard Areas where base flood elevations and/or floodway limits *have not* been provided by the National Flood Insurance Program in the Flood Insurance Study and accompanying maps, it is the applicant's responsibility to develop the necessary data. Where available, the applicant shall use data provided by FEMA, or State, or Federal agencies.
 - (D) When the Zoning Administrator cannot definitely determine the location of a district boundary, the Development Review Board and/or appropriate state or federal official may be consulted prior to issuing a determination. A determination by the Zoning Administrator regarding the location of a district boundary may be appealed to the Development Review Board under Section 7.3. If the applicant appeals the determination of the Flood Hazard Overlay boundary made by the Zoning Administrator, a Letter of Map Amendment from FEMA shall constitute proof.
 - (E) Where a district boundary divides a lot in single ownership as of the effective date of these bylaws, or any amendment thereto, the Development Review Board may permit, subject to conditional use review under Section 5.2, the extension of district standards for either portion of the lot up to 30 feet beyond the district line into the remaining portion of the lot.
 - (F) Where a lot is divided by a town boundary, the standards of these bylaws shall be applied to that portion of the lot located in the Town of Hardwick in the same manner as if the entire lot were located in this town.

Section 2.3 Application of District Standards

- (A) All uses and structures, unless specifically exempted under Section 7.2, must comply with all prescribed standards for the district in which they are located, as set forth in Tables 2.1-2.810 and as defined in Section 8.2, unless otherwise specified in these bylaws. The standards for each district shall apply uniformly to each class of use or structure, unless otherwise specified. Nonconforming uses and noncomplying structures in lawful existence as of the effective date of these bylaws shall be regulated in accordance with Section 3.9.

- (B) Overlay district standards shall be applied concurrently with the standards for underlying zoning districts. Where overlay districts impose more restrictive standards on the use of land or a structure, the standards of the overlay district shall apply.
- (C) Uses for each district are classified as - **“permitted uses”** to be reviewed by the Zoning Administrator in accordance with Section 7.1, or as **“conditional uses”** to be reviewed by the Development Review Board in accordance with Section 5.2. Both permitted and conditional uses are subject to applicable district requirements and general standards set forth in Article 3. Variances from the provisions of these bylaws may be considered only on appeal to the Development Review Board, in accordance with Sections 7.3 and 7.4.
- (D) Within specified zoning districts, the lot size and/or density requirements may vary depending on the availability of municipal sewer and/or water. For this purpose, the following lot classifications are established:
 - Class 1 – Served by both municipal water and sewer.
 - Class 2 – Served by either municipal water OR sewer, but not both.
 - Class 3 – Not served by municipal water or sewer.

TABLE 2.1 CENTRAL BUSINESS DISTRICT (CB)

(A) Purpose. The purpose of the Central Business District is to support a compact mix of commercial, professional, civic and residential uses in Hardwick’s traditional downtown in a manner that maintains and enhances the area’s historic character and economic vitality.

(B) Permitted Uses:

1. Accessory Dwelling [see Section 4.2]
2. Accessory Structure/Use (to a permitted use)
3. Accessory Structure less than or equal to 500 sq. ft. (to a conditional use)
4. Group Home [see Section 4.7]
5. Home Child Care [see Section 4.6]
6. Home Occupation [see Section 4.9]
7. Dwelling/Single Family Dwelling/Single Unit
8. Dwelling/Two Family Dwelling/Two Unit
9. Dwelling/Multi-Family Dwelling/Multi-Unit

(C) Conditional Uses:

1. Accessory Structure/Use (to a conditional use)
2. Adaptive Reuse [see Section 4.3]
3. Bank/Financial Institution
4. Bed & Breakfast
5. Community Center
6. Cultural Facility
7. Day Care Center [see Section 4.6]
8. Funeral Home
9. Gasoline Station [see section 4.14]
10. Greenhouse/Nursery
11. Health Clinic
12. Home Industry [see Section 4.9]
13. Hotel/Motel
14. Hospital
15. Industry, Light [see Section 4.10]
16. Mixed Use [see Section 4.12]
17. Motor Vehicle Sales
18. Motor Vehicle Service [see section 4.14]
19. Office
20. Residential Care Facility
21. Personal Service
22. Place of Worship
23. Private Club
24. Public Facility [see Section 4.15]
25. Recreation [Indoor]
26. Recreation [Outdoor]
27. Restaurant
28. Retail Sales
29. School
30. Telecommunications Facility [see Section 4.17]
31. Warehouse/Storage

(D) Dimensional Standards (unless otherwise specified for a particular use):

| | |
|---|-------------------|
| Minimum Lot Size | 5,000 square feet |
| Minimum Frontage | 25 feet |
| Minimum Setback/Front (Starting 25 feet from the road centerline) | 0 feet |
| Minimum Setback/Side | 5 feet |
| Minimum Setback/Side with signed agreement with neighboring property owner and provision of fire-walls. | 0 feet |
| Minimum Setback/Rear | 15 feet |
| Minimum Setback/Side and Rear for Accessory Structure | 5 feet |
| Maximum Height | 35 feet |

TABLE 2.2 VILLAGE CENTER DISTRICT (VC)

(A) Purpose. The purpose of the Village Center District is to support a central mixed use area in East Hardwick. The Village Center District is intended to provide a place of civic pride and a focal point for development in the community. The Village Center District enables a variety of housing opportunities with a mix of small-scale commercial in a pedestrian-friendly setting.

(B) Permitted Uses:

1. Accessory Dwelling [see Section 4.2]
2. Accessory Structure/Use (to a permitted use)
3. Accessory Structure less than or equal to 500 sq. ft. (to a conditional use)
4. Agriculture
5. Dwelling/Single Unit
6. Dwelling/Two Unit
7. Dwelling/Multi-Unit
8. Forestry
9. Group Home [see Section 4.7]
10. Home Child Care [see Section 4.6]
11. Home Occupation [see Section 4.9]
12. Private Family Cemetery [see Section 4.19]

(C) Conditional Uses:

1. Accessory Structure more than 500 sq. ft. (to a conditional use)
2. Adaptive Reuse [see Section 4.3]
3. Agricultural and Forest Processing [See Section 4.11]
4. Bank/Financial Institution
5. Bed & Breakfast
6. Community Center
7. Cultural Facility
8. Day Care Center [see Section 4.6]
9. Funeral Home
10. Greenhouse/Nursery
11. Health Clinic
12. Home Industry [see Section 4.9]
13. Hotel/Motel
14. Mixed Use [see Section 4.12]
15. Office
16. Residential Care Facility
17. Personal Service
18. Place of Worship
19. Private Club
20. Public Facility [see Section 4.15]
21. Recreation [Indoor]
22. Recreation [Outdoor]
23. Restaurant
24. Retail Sales
25. School
26. Telecommunications Facility [see Section 4.17]
27. Veterinary Clinic
28. Warehouse/Storage

(D) Dimensional Standards (unless otherwise specified for a particular use):

| | |
|--|--------------------------|
| <u>Minimum Lot Size</u> | <u>5,000 square feet</u> |
| <u>Minimum Frontage</u> | <u>25 feet</u> |
| <u>Minimum Setback/Front (Starting 25 feet from the road centerline)</u> | <u>0 feet</u> |
| <u>Minimum Setback/Side</u> | <u>10 feet</u> |
| <u>Minimum Setback/Side with signed agreement with neighboring property owner and provision of fire-walls.</u> | <u>0 feet</u> |
| <u>Minimum Setback/Rear</u> | <u>10 feet</u> |
| <u>Minimum Setback/Side and Rear for Accessory Structure</u> | <u>5 feet</u> |
| <u>Maximum Height</u> | <u>35 feet</u> |

Formatted: Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0" + Indent at: 0.25"

Formatted: Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"

Formatted: Indent: Left: 0", Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"

TABLE 2.2-3 VILLAGE NEIGHBORHOOD [VN] DISTRICT

(A) Purpose. The purpose of the Village Neighborhood District is to provide for high density residential development and appropriate non-residential uses in existing neighborhoods located close to Hardwick’s traditional downtown in a manner that maintains historic settlement patterns and streetscapes.

(B) Permitted Uses:

1. Accessory Dwelling [see Section 4.2]
2. Accessory Structure/Use (to a permitted use)
3. Accessory Structure less than or equal to 500 sq. ft. (to a conditional use)
4. Agriculture
5. ~~Dwelling/Single Family Dwelling/Single Unit~~
6. ~~Dwelling/Two Family Dwelling/Two Unit~~
7. ~~Dwelling/Multi Family Dwelling/Multi Unit~~
8. Forestry
9. Group Home [see Section 4.7]
10. Home Child Care
11. Home Occupation [see Section 4.9]
- ~~11-12. Private Family Cemetery [see Section 4.19]~~

(C) Conditional Uses:

1. Accessory Structure/Use (to a conditional use)
2. Adaptive Reuse [see Section 4.3]
3. Agricultural and Forest Processing [see Section 4.11]
4. Bank/Financial Institution
5. Bed & Breakfast
6. Cemetery
7. Community Center
8. Cultural Facility
9. Day Care Center [see Section 4.6]
10. Funeral Home
11. Greenhouse/Nursery
12. Health Clinic
13. Home Industry [see Section 4.9]
14. Hospital
15. Hotel/Motel
16. Mixed Use [see Section 4.12]
17. Natural Burial Ground
18. Office
19. Residential Care Facility
20. Personal Service
21. Place of Worship
22. Private Club
22. Public Facility
23. Recreation [Indoor]
24. Recreation [Outdoor]
25. School
26. Telecommunications Facility [see Section 4.17]

(D) Dimensional Standards (unless otherwise specified for a particular use):

| | |
|---|-------------------------|
| Minimum Lot Size | 5,000 square feet |
| Minimum Lot Area per Unit – Class 1 | 1 per 1,000 square feet |
| Minimum Lot Area per Unit – Class 2 | 1 per 3,500 square feet |
| Minimum Lot Area per Unit – Class 3 | 1 per 3,500 square feet |
| Minimum Frontage | 50 feet |
| Minimum Setback/Front (Starting 25 feet from the road centerline) | 10 feet |
| Minimum Setback/Side | 10 feet |
| Minimum Setback/Rear | 15 feet |
| Minimum Setback/Side and Rear for Accessory Structure | 5 feet |
| Maximum Height | 35 feet |

TABLE 2.3-4 HIGHWAY MIXED-USE [HM] DISTRICT

(A) Purpose. The purpose of the Highway Mixed-Use District is to allow automobile-oriented businesses and other compatible uses along major travel corridors contiguous to the historic village centers, while maintaining safe and efficient traffic flow.

Permitted Uses:

1. Accessory Dwelling [see Section 4.2]
2. Accessory Structure/Use (to a permitted use)
3. Accessory Structure less than or equal to 500 sq. ft. (to a conditional use)
4. Agriculture
- ~~5. Dwelling/Single Family Dwelling/Single Unit~~
- ~~6. Dwelling/Two Family Dwelling/Two Unit~~
- ~~7. Dwelling/Multi Family Dwelling/Multi-Unit~~
- ~~8-7. Forestry~~
- ~~9-8. Group Home [8 or fewer residents]~~
- ~~10-9. Home Child Care [see Section 4.6]~~
- ~~10. Home Occupation [see Section 4.9]~~
11. Private Family Cemetery [see Section 4.19]

(C) Conditional Uses:

12. Accessory Structure/Use (to a conditional use)
13. Agricultural and Forest Processing [see Section 4.11]
14. Bank/Financial Institution
15. Bed & Breakfast
16. Cemetery
17. Community Center
- ~~17-18. Contractor Yards~~
- ~~18-19. Cultural Facility~~
- ~~19-20. Day Care Center [see Section 4.6]~~
- ~~20-21. Extraction of Earth Resources~~
- ~~21-22. Funeral Home~~
- ~~22-23. Gasoline Station [see section 4.14]~~
- ~~23-24. Greenhouse/Nursery~~
- ~~24-25. Health Clinic~~
- ~~25-26. Home Industry [see Section 4.9]~~
- ~~26-27. Hotel/Motel~~
- ~~27-28. Industry [Light]~~
- ~~28-29. Mixed Use [see Section 4.12]~~
- ~~29-30. Mobile Home Park [see section 4.13]~~
- ~~30-31. Motor Vehicle Sales~~
- ~~31-32. Motor Vehicle Service [see section 4.13]~~
- ~~32-33. Natural Burial Ground~~
- ~~33-34. Office~~
- ~~34-35. Residential Care Facility~~
- ~~35-36. Personal Service~~
- ~~36-37. Place of Worship~~
- ~~37. Private Club~~
38. Public Facility
39. Recreation [Indoor]
40. Recreation [Outdoor]
41. Restaurant
42. Retail Sales
43. Sawmill
44. School
45. Telecommunications Facility [see Sec. 4.17]
- ~~45-46. Transfer Stations~~
- ~~46-47. Veterinary Clinic~~
- ~~47-48. Warehouse/Storage~~

Formatted: Font: Bold

(D) Dimensional Standards (unless otherwise specified for a particular use):

| | |
|---|--------------------------|
| Minimum Lot Size | 5,000 square feet |
| Minimum Lot Area per Unit – Class 1 | 1 per 1,250 square feet |
| Minimum Lot Area per Unit – Class 2 & 3 | 1 per 10,000 square feet |
| Minimum Frontage | 65 feet |
| Minimum Setback/Front (Starting 25 feet from the road centerline) | 20 feet |

| | |
|---|---------|
| Minimum Setback/Side | 20 feet |
| Minimum Setback/Rear | 20 feet |
| Minimum Setback/Side and Rear for Accessory Structure | 20 feet |
| Maximum Height | 35 feet |

TABLE 2.54 COMPACT RESIDENTIAL [CR] DISTRICT

(A) Purpose. The purpose of the Compact Residential District is to provide for moderate to high density residential development, and appropriate non-residential uses, in predominately built-up areas within and surrounding the town’s traditional village centers.

(B) Permitted Uses:

1. Accessory Dwelling [see Section 4.2]
2. Accessory Structure/Use (to a permitted use)
3. Accessory Structure less than or equal to 500 sq. ft. (to a conditional use)
4. Agriculture
5. ~~Dwelling/Single Family Dwelling/Single Unit~~
6. ~~Dwelling/Two Family Dwelling/Two Unit~~
7. ~~Dwelling/Multi Family Dwelling/Multi-Unit~~
8. Forestry
9. Group Home [see Section 4.7]
10. Home Child Care [see Section 4.6]
11. Home Occupation [see Section 4.9]
- ~~11-12. Private Family Cemetery [see Section 4.19]~~

(C) Conditional Uses:

1. Accessory Structure/Use (to a conditional use)
2. Adaptive Reuse [see Section 4.3]
3. Agricultural and Forest Processing [see Section 4.11]
4. Bank/Financial Institution
5. Bed & Breakfast
6. Campground
7. Cemetery
8. Community Center
9. Cultural Facility
10. Day Care Center [see Section 4.6]
11. Extraction of Earth Resources [see Sec. 4.8]
12. Funeral Home
13. Greenhouse/Nursery
14. Health Clinic
15. Home Industry
16. Mixed Use [see Section 4.12]
17. Mobile Home Park [see Section 4.13]
18. Natural Burial Ground
19. Office
20. Residential Care Facility
21. Personal Service
22. Place of Worship
23. Private Club
24. Public Facility [see Section 4.15]
25. Recreation [Indoor]
26. Recreation [Outdoor]
27. Restaurant
28. School
29. Telecommunications Facility [see Sec. 4.17]
30. Veterinary Clinic
31. Warehouse/Storage

(D) Dimensional Standards (unless otherwise specified for a particular use):

| | |
|---|--------------------|
| Minimum Lot Size – Class 1 | 5,000 square feet |
| Minimum Lot Size – Class 2 | 10,000 square feet |
| Minimum Lot Size – Class 3 | 30,000 square feet |
| Minimum Frontage – Class 1 | 50 feet |
| Minimum Frontage – Class 2 | 50 feet |
| Minimum Frontage – Class 3 | 50 feet |
| Minimum Setback/Front (Starting 25 feet from the road centerline) | 15 feet |
| Minimum Setback/Side | 20 feet |
| Minimum Setback/Rear | 20 feet |
| Minimum Setback/Side and Rear for Accessory Structure | 10 feet |
| Maximum Height | 35 feet |

TABLE 2.65 INDUSTRIAL [I] DISTRICT

(A) Purpose. The purpose of the Industrial District is to encourage a variety of industrial, manufacturing and appropriate commercial uses, while protecting such uses from incompatible residential uses, in locations served by municipal water and sewer and good highway access.

(A) Permitted Uses:

1. Accessory Structure less than or equal to 500 sq. ft. (to a conditional use)
2. Additions to existing Conditional Use less than or equal to 500 sq. ft.

(B) Conditional Uses:

1. Accessory Structure/Use (to a conditional use)
2. Agricultural and Forest Processing [see Section 4.11]
3. Caretakers Apartment [see Section 4.2]
4. Contractor's Yard
5. Day Care Center [see Section 4.6]
6. Extraction of Earth Resources [see Section 4.8]
7. Hazardous Waste Facility [see Section 4.15]
8. Industry [Light] [see Section 4.10]
9. Industry [Heavy]
10. Motor Vehicle Service [see Section 4.14]
11. Public Facility [see Section 4.15]
12. Salvage Yard [see Section 4.16]
13. Sawmill
14. Telecommunications Facility [see Section 4.17]
15. Transfer Station [see Section 4.15]
16. Warehouse/Storage

(C) Dimensional Standards (unless otherwise specified for a particular use):

| | |
|---|--------------------|
| Minimum Lot Size | 20,000 square feet |
| Minimum Frontage | 100 feet |
| Minimum Setback/Front (Starting 25 feet from the road centerline) | 20 feet |
| Minimum Setback/Side | 20 feet |
| Minimum Setback/Rear | 20 feet |
| Minimum Setback/District Boundary | 20 feet |
| Maximum Height | 35 feet |

TABLE 2.76 RURAL RESIDENTIAL [RR] DISTRICT

(A) Purpose. The purpose of Rural Residential District is to promote agriculture, forestry and low to moderate density residential development in areas well served by public roads but lacking municipal water and sewer. To ensure the protection of environmental resources and maintain open space, the clustering of new development is strongly encouraged.

(B) Permitted Uses:

1. Accessory Dwelling [see Section 4.2]
2. Accessory Structure/Use (to a permitted use)
3. Accessory Structure less than or equal to 500 sq. ft. (to a conditional use)
4. Agriculture
5. Dwelling/Single Family Dwelling/Single Unit
6. Dwelling/Two Family Dwelling/Two Unit
7. Forestry
8. Group Home [see Section 4.7]
9. Home Child Care [see Section 4.6]
10. Home Occupation [see Section 4.9]
- ~~10,11.~~ Private Family Cemetery [see Section 4.19]
- ~~11-12.~~ Seasonal Camp

(C) Conditional Uses:

1. Accessory Structure/Use (to a conditional use)
2. Adaptive Reuse [see Section 4.3]
3. Agricultural and Forest Processing [see Section 4.11]
4. Bed & Breakfast
5. Campground
6. Cemetery
7. Contractors Yard
8. Cultural Facility
9. Day Care Center [see Section 4.6]
10. Dwelling/Multi Family Dwelling/Multi-Unit
11. Extraction of Earth Resources [see Sec. 4.8]
12. Greenhouse/Nursery
13. Health Clinic
14. Home Industry [see Section 4.9]
15. Kennel
16. Landfill [see Section 4.15]
17. Mixed Use [see Section 4.12]
18. Mobile Home Park [see Section 4.13]
19. Natural Burial Ground
20. Residential Care Facility
21. Place of Worship [see Section 4.15]
22. Public Facility [see Section 4.15]
23. Recreation [Outdoor]
24. Restaurant
25. Retreat Center
26. Sawmill
27. School [see Section 4.16]
28. Transfer Station [see Section 4.15]
29. Telecommunications Facility [see Section 4.17]
30. Veterinary Clinic
31. Warehouse/Storage

(D) Dimensional Standards (unless otherwise specified for a particular use):

| | |
|---|---------------|
| Minimum Lot Size | 3 acres |
| Minimum Area per Unit | 2 per 3 acres |
| Minimum Frontage | 200 feet |
| Minimum Setback/Front (Starting 25 feet from the road centerline) | 35 feet |
| Minimum Setback/Side | 50 feet |
| Minimum Setback/Rear | 50 feet |
| Minimum Setback/Side & Rear for Accessory Structure | 20 feet |
| Maximum Height | 35 feet |

TABLE 2.87 FOREST RESERVE [FR] DISTRICT

(A) Purpose. The purpose of the Forest Reserve is to protect significant forest resources and limit development to low densities in areas with steep slopes, shallow soils, unique or fragile resources, significant wildlife habitat, and poor access to town roads and community facilities and services.

(B) Permitted Uses:

1. Accessory Dwelling [see Section 4.2]
2. Accessory Structure/Use (to a permitted use)
3. Accessory Structure less than or equal to 500 sq. ft. (to a conditional use)
4. Agriculture
5. ~~Dwelling/Single Family Dwelling/Single Unit~~
6. ~~Dwelling/Two Family Dwelling/Two Unit~~
7. ~~Seasonal Camp~~
- 8-7. Forestry
- 9-8. Group Home [see Section 4.7]
- 10-9. Home Child Care [see Section 4.6]
10. Home Occupation [see Section 4.9]
11. Private Family Cemetery [see Section 4.19]
- 11-12. Seasonal Camp

(C) Conditional Uses:

1. Accessory Structure/Use (to a conditional use)
2. Agricultural and Forest Processing [see Section 4.11]
3. Bed & Breakfast
4. Campground
5. Extraction of Earth Resources [see Section 4.8]
6. Greenhouse/Nursery
7. Health Clinic
8. Kennel
9. Natural Burial Ground
10. Public Facility [see Section 4.15]
11. Recreation [Outdoor]
12. Retreat
13. Telecommunications Facility [see Section 4.17]

(D) Dimensional Standards (unless otherwise specified for a particular use):

| | |
|---|----------------|
| Minimum Lot Size | 25 acres |
| Minimum Area per Unit | 2 per 25 acres |
| Minimum Frontage | 300 feet |
| Minimum Setback/Front (Starting 25 feet from the road centerline) | 50 feet |
| Minimum Setback/Side | 50 feet |
| Minimum Setback/Rear | 50 feet |
| Minimum Setback/Side & Rear for Accessory Structures | 20 feet |
| Maximum Height | 35 feet |

TABLE 2.98 FLOOD HAZARD AREA OVERLAY (FHO) DISTRICT

(A) Purposes. ~~(A) Purposes.~~ The purposes of the Flood Hazard and River Corridor Overlay Districts are as follows: 1) to protect health, safety, and welfare of the public, minimize and prevent the loss of life and property, the disruption of commerce, the impairment of the tax base, and the extraordinary public expenditures and demands on public services that result from flooding-related inundation and erosion hazards; 2) to ensure that selection, design, creation, and use of development in our community protects floodplain and river corridor functions, and avoids and reduces damage from flooding and erosion; 3) to manage all flood hazard areas pursuant to 24 VSA §4382 and 10 VSA §751, §753, and the local hazard mitigation plan and 4) to make the Town of Hardwick, its citizens, and businesses and farms eligible for federal flood insurance, federal disaster recovery funds, and hazard mitigation funds, as may be available.

~~The purposes of the Flood Hazard Area Overlay are to 1) avoid and minimize the loss of life and property, the disruption of commerce, the impairment of the tax base, and the extraordinary public expenditures and demands on public services that result from flooding; 2) ensure that the selection, design, creation, and use of development is reasonably safe and accomplished in a manner that is consistent with public wellbeing, does not impair floodplain services, and 3) manage the flood hazard area designated pursuant to 10 V.S.A. Chapter 32 5-753, the municipal hazard mitigation plan; and make the Town of Hardwick, its citizens, and businesses eligible for federal flood insurance, federal disaster recovery funds, and hazard mitigation funds as may be available.~~

| (B) Permitted Uses | (C) Conditional Use | (D) Prohibited Uses | (E) Exempted |
|---|---|---|---|
| 1. Accessory structures not greater than 500 square feet and outside of the Floodway | 1. Accessory structures larger than 500 square feet, outside of the Floodway | 1. All new residential or non-residential structures, including small Accessory Structures, in the Floodway | 1. Agriculture** 2. Forestry** 3. Interior improvements or repairs to existing buildings that cost less than 500 dollars. |
| 2. Bridges and culverts | 2. All other new structures, (including Accessory Dwelling Units) outside of the Floodway | 2. Caretaker’s apartments | 4. Maintenance of roads, bridges, or stormwater drainage. |
| 3. Building utilities | 3. Fill to elevate new and existing structures or for primary access | 3. Cemetery | 5. Open space |
| 4. Channel Management | 4. Grading, excavation or the creation of a pond | 4. Critical facilities | 6. Removal of a structure (in whole or in part), so long as the ground elevations under and adjacent to the removed structure remain unchanged |
| 5. Footbridges | 5. Non-substantial improvements to existing structures (outside of Floodway) | 5. Fill for any purpose other than elevating structures or primary access | 7. Routine maintenance of an existing building |
| 6. New or replacement storage tanks for existing structures | 6. Parking, at grade (in Floodway) | 6. Natural Burial Ground | 8. Stream bank stabilization and abutment work that do not reduce the cross-sectional flow area of the river or stream channel and have coverage under a Stream Alteration Permit, if required. |
| 7. Non-substantial improvements to existing structures (outside of Floodway) | 7. Public utilities | 7. Private Family Cemetery | 9. Subdivision of land that does not involve or authorize development. |
| 8. Parking, at grade (outside of Floodway) | 8. Road improvements | 8. Salvage Yards | |
| 9. Recreational vehicles (parking of) outside of the Floodway | 9. Substantial improvements to existing structures | 9. Storage Facility | |
| 10. Replacement of water supply or septic systems | 10. River and floodplain restoration projects in the Floodway, including dam | | |
| 11. River and floodplain restoration projects, outside of the Floodway, including dam removal, that restore natural & | | | |

beneficial floodplain functions and include written information from the ANR Regional Floodplain Manager that the project is designed to meet the applicable standards in this bylaw

removal that restore natural & beneficial floodplain functions and include written information from the ANR Regional Floodplain Manager that the project is designed to meet the applicable standards of this bylaw.

**Forestry activities conducted in accordance with the Vermont Department of Forests and Parks Acceptable Management Practices; and agriculture activities conducted in accordance with the Vermont Agency of Agriculture Food & Markets Required Agricultural Practices

(F) Dimensional Standards (unless otherwise specified for a particular use):

As required for the underlying zoning district. Subject to conditional use approval by the Development Review Board, a waiver may be granted to dimensional standards in the underlying district in order to locate development outside of flood hazard prone areas. Such a waiver shall represent the minimum deviation from dimensional standards in order to locate development away from flood prone areas and shall not encroach into public and private rights of way or required replacement fields or separation distances to accommodate on-site potable water and waste water systems.

(G) Development Standards [See section 5.3]


TABLE 2.10 RIVER CORRIDOR OVERLAY DISTRICT

(A) Purposes. The purposes of the Flood Hazard and River Corridor Overlay Districts are as follows: 1) to protect health, safety, and welfare of the public, minimize and prevent the loss of life and property, the disruption of commerce, the impairment of the tax base, and the extraordinary public expenditures and demands on public services that result from flooding-related inundation and erosion hazards; 2) to ensure that selection, design, creation, and use of development in our community protects floodplain and river corridor functions, and avoids and reduces damage from flooding and erosion; 3) to manage all flood hazard areas pursuant to 24 VSA §4382 and 10 VSA §751, §753, and the local hazard mitigation plan and 4) to make the Town of Hardwick, its citizens, and businesses and farms eligible for federal flood insurance, federal disaster recovery funds, and hazard mitigation funds, as may be available.

| (B) Permitted Uses | (C) Conditional Use | (D) Prohibited Uses | (E) Exempted |
|---|--|--|---|
| <ol style="list-style-type: none"> 1. <u>Accessory structures not greater than 500 square feet</u> 2. <u>Improvements to Existing Structures that will change the footprint of the structure</u> 3. <u>Building utilities</u> 4. <u>Parking, at grade</u> 5. <u>Recreational vehicles (parking of)</u> 6. <u>Replacement of water supply or septic systems</u> 7. <u>Attached deck or patio to an existing structure that is 200 square feet or less and is located no less than 100 feet from the top of the bank</u> 8. <u>Unimproved trails</u> 9. <u>River or floodplain restoration projects that do not involve fill, structures, utilities, or other improvements and which have written confirmation from the ANR Regional Floodplain Manager that the project is designed to meet or exceed the applicable standards in this bylaw.</u> | <ol style="list-style-type: none"> 1. <u>Accessory structures larger than 500 square feet</u> 2. <u>All other new structures, (including Accessory Dwelling Units)</u> 3. <u>Storage (See Definition)</u> 4. <u>Grading, excavation or the creation of a pond</u> 5. <u>Road improvements</u> | <ol style="list-style-type: none"> 1. <u>Cemetery</u> 2. <u>Critical facilities</u> 3. <u>Fill for any purpose other than elevating structures or primary access</u> 4. <u>Natural Burial Ground</u> 5. <u>Private Family Cemetery</u> 6. <u>Salvage Yards</u> 7. <u>Storage Facility</u> | <ol style="list-style-type: none"> 1. <u>Agriculture**</u> 2. <u>Forestry**</u> 3. <u>Any changes to a structure that will not change the footprint of the structure.</u> 4. <u>Maintenance of existing sidewalks, roads, bridges, parking areas, culverts, or stormwater drainage.</u> 5. <u>Channel Stabilization and Management</u> 6. <u>Open space</u> 7. <u>Removal of a structure (in whole or in part), so long as the ground elevations under and adjacent to the removed structure remain unchanged</u> 8. <u>Functionally dependent uses that must be placed in or cross over rivers and streams that are not located in a flood hazard area and that have coverage under a Stream Alteration Permit, if required.</u> 9. <u>Subdivision of land that does not involve or authorize development.</u> 10. <u>Planting projects which do not include any construction or grading.</u> 11. <u>Public utilities</u> 12. <u>Telecommunications facilities</u> |

- Formatted:** Font: Bold
- Formatted:** Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"
- Formatted:** Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"
- Formatted:** Indent: Left: -0.01", Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"
- Formatted:** Indent: Left: -0.01", Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"
- Formatted:** Indent: Left: 0.24", No bullets or numbering
- Formatted:** Font: +Body (Calibri), 10 pt

|



ARTICLE 3. GENERAL REGULATIONS

Section 3.1 Applicability

The following general standards, including provisions required under the Act [§4412, §4413], apply to all uses and structures as specified within the Town of Hardwick.

Section 3.2 Damaged Structures

- (A) No zoning permit is required for the stabilization of damaged structures located outside of the Flood Hazard Overlay District to prevent hazards to public health or safety, or to adjoining properties, structures or uses (e.g., fire, collapse, squatting); nor for the timely repair or reconstruction of damaged structures to the extent of their prior condition and use, provided such stabilization, repair or reconstruction occurs within 12 months of the date the structure is damaged. Reconstruction that results in changes in density, dimension or use under applicable provisions of these regulations shall require a zoning permit issued in accordance with Section 7.1.
- (B) If an owner has not stabilized, repaired or reconstructed a structure that has been demolished, destroyed, or substantially damaged within 12 months of the date of damage or demolition, and the structure is determined by the Town Health Officer to present a hazard to public health and safety, the owner shall remove all materials from the site, restore the site to a normal grade, and establish ground cover sufficient to prevent erosion.
- (C) The repair or reconstruction of damaged structures located in the Flood Hazard Overlay District shall be subject to the provisions of Section 5.3 of these Bylaws.

Section 3.3 Access & Frontage Requirements

- (A) No land development may be permitted on lots which do not have either frontage on a public or private road or public waters or, with the approval of the Development Review Board, access to such a road or waters by a permanent easement, right-of-way or fee-simple ownership at least 50 feet in width and fully located outside of the Flood Hazard Overlay District. In granting approval under this Section, the Development Review Board shall consider the intended use and shall ensure the proposed access does not pose a hazard to traffic and pedestrian safety.
- (B) The approval of access to a non-frontage lot shall be done in Site Plan Review as provided in Section 5.1 unless the proposed development is subject to other development review processes such as Conditional Use Review, Planned Unit Development, or Subdivision Review. In that case, the review and approval of access shall be incorporated into the appropriate development review process.
- (B) Access onto public roads is subject to the approval of the Hardwick Select Board, and for state highways, the Vermont Agency of Transportation. As a condition of access approval, compliance with all municipal land use regulations is required. Access permits must be obtained prior to the issuance of a zoning permit.
- (C) With the exception of parcels in agricultural or forestry use, no lot created after the effective date of these bylaws shall be served by more than one (1) access or driveway unless otherwise approved under conditional use review in accordance with Section 5.2. The consolidation of existing accesses and/or shared access between adjoining lots is encouraged and may be required as a condition of such approval. Access widths shall be

limited to that approved, and not extend along the length of road frontage.

- (D) No driveway intersection with a public road shall be located within seventy-five (75) feet of a street line intersection.

Section 3.4 Conversions & Changes of Use

- (A) Conversions or changes in the use of land, existing buildings, or other structures are subject to the following:
 - (1) The proposed use shall be subject to all the requirements of these Bylaws pertaining to such use, including but not limited to any district, general or specific requirements, as well as all other municipal regulations currently in effect.
 - (2) An accessory structure such as a garage or barn may be converted to a principal use allowed within the district in which it is located only if the structure is located on a separate lot which conforms to lot size, setback, parking and other requirements applicable to the proposed use, independent of the principal use or structure on the lot (see Section 3.8). Such a conversion requires a zoning permit issued by the Zoning Administrator in accordance with Section 7.1.
 - (3) A conversion or change of use from one permitted use to another permitted use which involves the creation of new floor space or outdoor storage space, requires additional on-site parking, or has different minimum lot size or dimensional requirements, will require a zoning permit issued by the Zoning Administrator under Section 7.1.
 - (4) A conversion or change from a permitted use to a conditional use, or from a conditional use to a different conditional use, shall be approved by the Development Review Board subject to conditional use review under Section 5.2. Such a change of use shall constitute the discontinuance of a previously approved conditional use unless the Board specifically authorizes the continuation of the prior use as part of its approval under Section 5.2. A landowner may not reconvene the discontinued use without Board approval.
 - (5) A conversion or change of use involving a non-conforming use and/or Nonconforming structure is also subject to review under Section 3.9.

Section 3.5 Equal Treatment of Housing

- (A) No provision of these regulations shall have the effect of excluding mobile homes, modular housing or other forms of prefabricated housing from the Town of Hardwick except under the same terms and conditions as conventional housing is excluded. A mobile home shall be considered single ~~unit family~~ dwelling, and must meet the zoning requirements for such dwelling, except when located in an approved mobile home park (see Section 4.13) or sales establishment, or allowed as a temporary structure (see Section 4.18).
- (B) No provision of these regulations shall be construed to prevent the establishment of a mobile home park pursuant to state statute [10 V.S.A., Chapter 153] and local standards within designated zoning districts (see Article 2).
- (C) No provision of these regulations shall have the effect of excluding for review one dwelling unit constructed within or attached to a primary owner-occupied single ~~unit family~~ residence located in a district in which single ~~unit family~~ residences are a permitted or conditional use, if the accessory unit meets statutory requirements

[§4412(1)] and is located outside of flood hazard areas as defined in Section 5.3. Accessory dwellings are provided for under these regulations in accordance with the requirements of the Act (see Section 4.2).

Section 3.6 Existing Small Lots

- (A) Any lot in individual and non-affiliated ownership from surrounding properties legally in existence on the effective date of these regulations may be developed for the purposes permitted in the district in which it is located, if such lot is at least 5,000 square feet in area with a minimum width or depth of forty (40) feet. Development of the existing lot shall be subject to all other applicable requirements.
- (B) Within all zoning districts, except the Flood Hazard Area Overlay District, an existing small lot that comes under common ownership with one or more contiguous lots after July 1, 2004, shall not require a merger and the nonconforming lot may remain a separate, individual lot. Within the Flood Hazard Area Overlay District, an existing small lot (wholly or partially in the Flood Hazard Area Overlay District) that comes under common ownership with one or more contiguous lots after July 1, 2004, shall be deemed merged with the contiguous lot unless all of the following apply:
 - (1) the lots are conveyed in their pre-existing, nonconforming configuration; and
 - (2) on the effective date of any bylaw, each lot was developed with a water supply and wastewater disposal system; and
 - (3) at the time of transfer, each water supply and wastewater system is functioning in an acceptable manner; and,
 - (4) the deeds of conveyance create appropriate easements on both lots for replacement of one or more wastewater systems, potable water systems, or both, in case there is a failed system or failed supply as defined in 10 V.S.A. chapter 64.

Section 3.7 Height Requirements

- (A) The maximum height of structures in all districts shall not exceed the district maximum, except as permitted under Subsection (B), or for the following which are specifically exempted from the height requirements of these bylaws:
 - (1) agricultural structures in accordance with the Act [§4413(D)];
 - (2) steeples, spires, belfries, bell and clock towers;
 - (3) accessory structures associated with residential use which are less than fifty (50) feet in height above the lowest grade at ground level at the base of the structure, including antenna structures, wind turbines with blades less than 20 feet in diameter, or rooftop solar collectors less than 10 feet high, any of which are mounted on complying structures.
 - (4) In any area served by municipal sewer and water infrastructure that allows residential development, any affordable housing development, as defined in 24 V.S.A. § 4303, including mixed use development, shall be permitted to exceed density limitations for residential developments by an additional 40 percent, which shall include exceeding maximum height limitations by one floor, provided that the structure complies with the Vermont Fire and Building Safety Code [per Sec. 2. 24 V.S.A. § 4412(13)].

- (B) The Development Review Board may permit structures in excess of the district standard subject to conditional use review under Section 5.2, upon finding that:
 - (1) the structure does not constitute a hazard to public safety, or to adjoining properties;
 - (2) that portion of the structure above the district maximum height shall remain unoccupied except for normal maintenance;
 - (3) the structure is not to be used for advertising purposes;
 - (4) lighting, if deemed necessary by the Board in accordance with state and federal regulations, shall be restricted to the minimum required for security and safe operation; and,
 - (5) the proposed building height and scale are consistent with the character of the immediate surroundings.
- (C) Notwithstanding these requirements, or the district maximum height standards, telecommunications facilities shall meet the standards set forth in Section 4.15, including those standards which relate to maximum height.

Section 3.8 Lot & Yard Requirements

- (A) Only a single principal use or structure may be located on a single lot, unless permitted within the specific district as:
 - (1) an accessory use to a principal use (e.g., a home occupation, home child care);
 - (2) a mixed use (see Section 4.12);
 - (3) agricultural and forestry uses;
 - (4) the adaptive reuse of a historic structure in accordance with Section 4.3; or
 - (5) as otherwise approved by the Development Review Board as part of a Planned Unit Development (PUD) in accordance with Section 5-45.5.
- (B) Notwithstanding subsection 3.8(A), above, the Zoning Administrator may permit two single ~~unit family~~ dwellings on a single parcel under Section 7.1 provided:
 - (1) the parcel meets all applicable lot size, density and dimensional standards for the district in which the parcel is located;
 - (2) the dwellings are set back from one another a minimum of twice the side yard setback distance for the district in which they are located; and
 - (3) the Zoning Administrator determines that if the parcel were subdivided into two parcels each would meet all requirements for a conforming use and complying structure under these bylaws.
- (C) An accessory structure or use must conform to all lot setback, coverage and other dimensional requirements for the district in which it is located, unless otherwise exempted under Section 7.2.
- (D) No lot shall be so reduced in area that it cannot conform to area, setback, frontage, coverage and other dimensional requirements as prescribed in these regulations, except as approved by the Development Review Board for PUDs in accordance with Section 5-45.5.

- (E) Any interior lot which does not have frontage on a public or private road or public waters shall meet minimum setback requirements equal to the front yard setback distance for the district in which it is located from all adjacent property boundaries.
- (F) Any yard adjoining a street shall be considered a front yard. A corner lot shall be considered to have only front and side yards.

Section 3.9 Nonconforming Structures & Nonconforming Uses

- (A) **Nonconforming Structures.** Any pre-existing structure or part thereof which does not conform to the provisions of these regulations concerning density, setbacks, height, lot size or other dimensional standard, or which does not meet other applicable requirements of these regulations, shall be deemed a Nonconforming structure. Nonconforming structures may be allowed to continue indefinitely, but shall be subject to the following provisions. A Nonconforming structure:
 - (1) may undergo normal repair and maintenance provided that such action does not increase the degree of nonconformity (see definition of degree of nonconformity in Article 8.2);
 - (2) may be restored or reconstructed after damage from any cause, in accordance with Section 3.2, provided the structure is located outside of the Flood Hazard Overlay District, and provided that the reconstruction does not increase the degree of nonconformity which existed prior to the damage;
 - (3) may be structurally enlarged, expanded or moved, upon approval of the Zoning Administrator, provided the enlargement, expansion or relocation does not increase the degree of nonconformity;
 - (4) may, subject to conditional use review under Section 5.2, undergo alteration or expansion which would increase the degree of nonconformity solely for the purpose of meeting mandated state or federal environmental, safety, health or energy regulations (e.g., handicap access ramp in accordance with ADA standards).
- (B) **Nonconforming Uses.** Any use of land or a structure which does not conform to the uses allowed for the zoning district in which it is located shall be deemed a nonconforming use. Nonconforming uses may be continued indefinitely, but shall be subject to the following provisions. A nonconforming use:
 - (1) shall not be re-established or continued following abandonment or discontinuance resulting from structural damage from any cause, unless the nonconforming use is carried on uninterrupted in the undamaged part of the structure, or the use is reinstated within one year of such damage; or if the use is in a structure deemed eligible for Adaptive reuse in accordance with Section 4.3;
 - (2) shall not be re-established if such use has been changed to, or replaced by, a conforming use, or if such use has been discontinued for a period of 12 months, regardless of the intent to re-establish such prior use;
 - (3) shall not be changed to another non-conforming use without the approval of the Development Review Board in accordance with Section 5.2, and then only to a use which, in the opinion of the Board, is of the same or a more restricted nature;
 - (4) shall not be moved, enlarged, or increased by any means whatsoever, except with the approval of the Development Review Board subject to conditional use review

under Section 5.2. In no case shall a nonconforming use be moved to a different lot within the same district in which it is located.

Section 3.10 Discontinued Uses

- (A) A use shall be considered discontinued when the owner or lessee has relinquished the property or has ceased to use the property without any intention of transferring rights to the property to another owner or lessee, or without any intention of resuming use of the property for a consecutive period of five years.
- (B) Notwithstanding (A) above, the owner or lessee of a discontinued use may apply for a one-year extension from the Zoning Administrator, provided the extension request is made prior to the two-year date.

Section 3.11 Performance Standards

- (A) The following performance standards must be met and maintained for all Conditional Uses and Home Occupation uses in all districts, except for agriculture and forestry, as measured at the property line. In determining ongoing compliance, the burden of proof shall fall on the applicant, property owner, and/or all successors and assigns; in the case of appeals to the Zoning Administrator alleging a violation of one or more of the following standards, the burden of proof shall rest with the appellant. No Conditional Uses or Home Occupation uses, under normal conditions, shall cause, create or result in:
 - (1) **regularly occurring noise**, which:
 - i. represents a significant increase in noise levels in the vicinity of the use so as to be incompatible with the surrounding area; or
 - ii. in excess of 65 decibels, or 70 decibels within the Industrial District.
 - (2) **releases of heat, cold, moisture, mist, fog** or condensation which are detrimental to neighboring properties and uses, or the public health, safety, and welfare;
 - (3) **any electromagnetic disturbances or electronic transmissions or signals** which will repeatedly and substantially interfere with the reception of radio, television, or other electronic signals, or which are otherwise detrimental to public health, safety and welfare (except from telecommunications facilities which are specifically licensed and regulated through the Federal Communications Commission);
 - (4) **glare, lumen, light or reflection** which constitutes a nuisance to other property owners or tenants, which impairs the vision of motor vehicle operators, or which is otherwise detrimental to public health safety and welfare;
 - (5) **liquid or solid waste or refuse** in excess of available capacities for proper disposal which cannot be disposed of by available existing methods without undue burden to municipal or public disposal facilities; which pollute surface or ground waters; or which is otherwise detrimental to public health, safety and welfare;
 - (6) **undue fire, safety, explosive, radioactive emission or other hazard** which endangers the public, public facilities, or neighboring properties; or which results in a significantly increased burden on municipal facilities and services.
 - (7) **clearly apparent vibration** which, when transmitted through the ground, is discernible at property lines without the aid of instruments; or

- (8) **smoke, dust, noxious gases, or other forms of air pollution** which constitute a nuisance or threat to neighboring landowners, businesses or residents; which endanger or adversely affect public health, safety or welfare; which cause damage to property or vegetation; or which are offensive and uncharacteristic of the affected area;
- (C) Agricultural operations shall at minimum observe Required Agricultural Practices (RAPs) as defined and administered by the Vermont Department of Agriculture (see Section 8.2).
- (D) Forestry operations shall at minimum observe Acceptable Management Practices (AMPs) as defined and administered by the Vermont Department of Forests, Parks and Recreation (see Section 8.2). Such AMPs include *Acceptable Management Practices for Maintaining Water Quality on Logging Jobs in Vermont*.

Section 3.12 Protection of Water Resources

- (A) **Surface Waters.** To prevent soil erosion and sedimentation of surface waters, maintain water quality and protect wildlife habitat, the following standards shall apply to all perennial streams and rivers:
 - (1) All septic systems shall meet all applicable state standards and regulations;
 - (2) All structures shall be setback a minimum of 75 feet from all streams, rivers and public lakes, although the Development Review Board may, in accordance with conditional use review under Section 5.2, approve the placement of a structure within the 75 feet setback providing it meets the following standards:
 - a) the structure is located within the Central Business District or the Village Neighborhood District;
 - b) the building placement will better reflect the historic settlement pattern and character of the surrounding area;
 - c) reasonable provision is made for the protection of water quality such as, but not limited to, the planting of shade trees adjacent to stream banks, the establishment of vegetated buffer areas along stream banks, and/or stormwater management provisions to collect and disperse stormwater away from the stream or river;
 - d) the structure, if located in a flood hazard area, shall meet the development standards of Section 5.3 of these bylaws.
 - (3) An undisturbed, vegetated buffer strip shall be maintained for a minimum of 25 feet from all streams, rivers and lakes. The 25 feet buffer strip shall be measured from the top of the stream bank. No development, excavation, filling, clearing or grading shall occur within the buffer strip, with the exception of clearing and associated site development necessary to accommodate the following:
 - a) road, driveway and utility crossings;
 - b) stream bank stabilization and restoration projects, in accordance with applicable state and federal regulations;
 - c) bicycle and pedestrian paths and trails;
 - d) recreation facilities, including structures, and improved lake or pond accesses;

- e) landscaping associated with a residential use;
 - f) agriculture in accordance with Required Agricultural Practices (RAPs) as defined by the Commissioner of Agriculture, Food and Markets, and forestry in accordance with *Acceptable Management Practices (AMPs) For Maintaining Water Quality on Logging Jobs in Vermont*, published by the Vermont Department of Forests, Parks and Recreation; or
 - g) any use exempted in subsection (2), above.
- (4) The expansion or enlargement of any structure in existence prior to the effective date these bylaws and not in compliance with this Section is permitted with approval of the Development Review Board pursuant to Section 5.2 regarding Nonconforming structures.
- (5) No alteration of the natural course of any perennial stream shall be allowed unless a stream alteration permit has been issued by the Vermont Department of Environmental Conservation in accordance with 10 VSA Chapter 41. Such alterations within the Flood Hazard Area Overlay District are subject to state agency and municipal referral requirements under Section 7.1.
- (B) **Source Protection Areas.** In order to protect community water supplies, the following potential sources of contamination are specifically prohibited within designated Source Protection Areas, unless it is demonstrated to the satisfaction of the Development Review Board under conditional use review (Section 5.2) that no potential for contamination of a water supply exists:
- a) gasoline and motor vehicle service and repair facilities;
 - b) machine and body shops;
 - c) car washes;
 - d) the outdoor storage of road salt and other de-icing chemicals;
 - e) public or community wastewater treatment facilities;
 - f) fuel storage except for agricultural or residential use;
 - g) underground storage tanks;
 - h) solid waste disposal facilities and sanitary landfills;
 - i) dry cleaning, furniture stripping, metal plating, and photographic processing activities;
 - j) junk and salvage yards;
 - k) extraction and quarrying activities;
 - l) cemeteries;
 - m) lawn and garden stores;
 - n) power plants and substations; and/or
 - o) any other use which involves the generation, use, storage, treatment, transportation or disposal of potential contaminants greater than normal household use.

- (C) An application for development within delineated Source Protection Areas which is subject to conditional use review shall also be forwarded for review by the local fire or water district having jurisdiction prior to the issuance of a permit. Development within a source protection area shall be managed in accordance with the adopted source protection plan for that area. Conditions may be attached as appropriate, in consultation with the local district and/or state.

Section 3.13 Parking & Loading Requirements

- (A) Off-street parking spaces shall be provided in accordance with this section when any use is established or enlarged unless otherwise approved by the Development Review Board or waived under subsection 5.2.
- (1) In the Central Business (CB) and Village Center (VN) Districts, off-street parking will be required only for employees, on the basis of one space per two (2) employees per shift, and for dwelling or lodging units as provided for in Table 3.1, or as otherwise allowed by the Development Review Board in accordance with a parking plan submitted by the applicant and approved in accordance with Section 5.2. In all other districts, off-street parking shall be required to accommodate business-owned vehicles and the vehicles of all owners, occupants, employees, customers or other persons expected to be on the premises in accordance with Table 3.1.
 - (2) All required parking spaces shall have a minimum width of nine (9) feet, and a minimum length of eighteen (18) feet, excluding access and maneuvering room.
 - (3) In addition to the requirements listed in Table 3.1, meeting standards to address the needs of people with disabilities (e.g., Americans with Disabilities Act) may also be required by state or federal agencies.
 - (4) Non-residential parking areas shall be located to the side or rear of buildings unless otherwise approved under site plan or conditional use review and shall be screened from adjoining residential properties.

| Table 3.1 Minimum Off-Street Parking Requirements | |
|--|---|
| Use | Parking Spaces |
| Dwelling Unit/ Single or Two <u>Units-Family</u> | 1 per unit |
| Dwelling Unit/ Accessory | 1 per unit |
| Dwelling Unit/ Multi- <u>UnitsFamily</u> | 1 per unit |
| Home Occupation/Home-Based Business | 2 per unit, and 1 per additional employee |
| Bed & Breakfast | 2 per unit, and 1 per guest room |
| Lodging Facility (Inn, Motel, Boarding House) | 1 per lodging unit, and 1 per employee on largest shift |
| Office/Personal Service | 1 per 300 sq. ft. of gross floor area |
| Retail | 1 per 300 sq. ft. of gross floor area |
| Restaurant/Bar | 1 per 3 seats, and one per employee on largest shift |
| Public Assembly (Church, Theater, etc.) | 1 per 4 seats |
| Warehouse/Manufacturing/Industry | 1 per 2 employees on the largest shift |
| Other | As determined under site plan or conditional use review |

- (B) **Loading and Service Areas.** In all zoning districts other than the Central Business and

Village Center Districts, off-street loading space shall be provided for commercial, industrial or institutional uses which will receive shipments in vehicles too large for a standard parking space. Space provided shall be specifically for off-street loading and shall be large enough to fully accommodate the maximum number of such vehicles expected to be on the premises at any one time. Service areas also may be required for development subject to site plan or conditional use review to accommodate emergency vehicles, waste collection and disposal areas, transit service, or other purposes as may be necessitated by the proposed use. All loading and service areas shall be clearly marked and located in such a manner that parked vehicles will not block or obstruct access or sight visibility at intersections.

- (C) **Waivers.** On-site parking, loading, and/or service area requirements may be reduced or waived by the Development Review Board under conditional use review based upon a determination under one or more of the following provisions that, due to circumstances unique to the development, the strict application of these standards is unnecessary:
- (1) suitably landscaped vacant land is set aside and maintained as open space for future conversion to parking, loading or services area in the event that the amount of space initially permitted is deemed inadequate to meet demonstrated need; or
 - (2) shared use of parking, loading and/or service areas on the same or contiguous lots by two or more establishments is proposed; or
 - (3) adequate off-site public parking exists within reasonable walking distance of the establishment;
 - (4) sufficient off-site parking has been procured (e.g., through lease agreements) in a private or municipal parking lot; or
 - (5) the proposal is specifically for the development of elderly housing.

Section 3.14 Sign Regulations

- (A) **Applicability.** A zoning permit shall be required prior to the erection, construction or replacement of any outdoor sign, except for signs which are specifically exempted from these provisions, or specifically prohibited as listed under Table 3.2, or the replacement of any sign communicating a change in ownership, management or brand associated with any sign that meets all applicable standards of this section [See subsection (12)].
- (B) **General Standards.** All signs, other than those specified in subsection (A) of Table 3.2, shall require a zoning permit issued by the Zoning Administrator in accordance with the following requirements pertaining to all signs:
- (1) No outdoor advertising signs shall be permitted in any district except for the purposes of identifying an existing on-premise use in those districts where such uses are permitted.
 - (2) There shall be only one free-standing except as allowed for gasoline pricing signs in accordance with Section 4.14.
 - (3) In addition to (2) above, a principal business or service shall be allowed one hanging wall mounted sign per building face except as allowed for gasoline pricing signs in accordance with Section 4.14. Collectively the total sign area per building face shall not exceed 50% of the surface of the building face.

- (4) The Development Review Board may approve a roof-mounted sign as a conditional use in accordance with Section 5.2.
- (5) No sign located within the Central Business District, ~~and~~ Village Neighborhood District, ~~and the Village Center District~~ shall have a sign area that exceeds 16 square feet. The Development Review Board may, however, approve a sign of up to 25 square feet as a conditional use in accordance with Section 5.2.
- (6) No sign located within the Highway Mixed Use District or the Industrial District shall have a sign area that exceeds 32 square feet.

| Table 3.2 Exempted & Prohibited Signs | |
|--|--|
| (A) | <p>Exempt Signs. No zoning permit shall be required for the following types of signs, which are exempt from these regulations:</p> <ul style="list-style-type: none"> (1) Signs erected by the state or town on public roads. (2) Non-advertising signs placed for directional, safety or public service purposes which do not exceed 4 square feet in area. (3) Signs offering real estate for sale, not to exceed 4 square feet and placed in accordance with subsection (B)(8). (4) One residential sign per dwelling unit identifying the occupant, not to exceed 2 square feet in area; and residential flags or banners intended solely for ornamental or non-advertising purposes. (5) Signs relating to trespassing and hunting, each not to exceed 2 square feet in area. (6) Temporary auction, yard, or garage sale signs not to exceed 2 in number or 6 square feet in total area, which shall be removed immediately following the event or sale. (7) Temporary election signs to be posted and removed in accordance with state law. (8) Temporary signs or banners advertising public or community events, to be displayed in designated locations on town property with the prior permission of the Select Board, which shall be removed immediately following the event. (9) Signs or bulletin boards incidental to places of worship, schools, libraries or public facilities, not to exceed one per establishment, 16 square feet in total area, or 6 feet in height above ground level. (10) Unlit signs associated with farm operations, not to exceed one per establishment or 16 square feet in area. (11) Unlit wall-mounted or freestanding signs advertising a home occupation, home industry or home child care facility, not to exceed one per residential dwelling or 4 square feet in area. (12) On-premise historic or landmark signs, not to exceed one in number or 6 square feet in area. (13) Wall murals intended solely for artistic, non-advertising purposes. (14) Up to one flag displaying messages such as "open" and/or "sale." (15) Window signs and wall graphics affixed directly to the face of a wall or window within the Central Business (CB) and Highway Mixed-use (HM) Districts. (16) One temporary construction sign, not to exceed 16 square feet in total area or 10 feet in height, providing such sign is promptly removed immediately following completion of construction. |
| (B) | <p>Prohibited Signs. The following signs are prohibited in all districts:</p> <ul style="list-style-type: none"> (1) Signs which impair highway safety. (2) Signs which are flashing, oscillating, revolving or made of reflective material, unless necessary for public safety or welfare. (3) Permanent signs which project over public rights-of-way or property lines, except in instances in which a building abuts a public sidewalk. (4) Signs located on motor vehicles which are used primarily as a support or foundation. (5) Off-premises signs, except for those which conform to state laws and meet Section 314(C). |

- (7) No sign in the Compact Residential District, Rural Residential District or the Forest

Reserve District shall have a sign area that exceeds 9 square feet.

- (8) No sign, including mounted or freestanding supporting structures, shall exceed 16 feet in height. The Development Review Board may, however, approve a sign of up to 20 feet in height as a conditional use in accordance with Section 5.2.
- (9) No sign shall be closer than 10 feet to the nearest part of the traveled portion of any road, except within the Central Business District.
- (10) No sign shall be placed at any road intersection in a manner to obstruct the line of sight from such intersection.
- (11) Signs shall be illuminated so as not to produce undue glare, hazards, or distractions. A constant, shielded light source may be used for indirect lighting, provided that the light fixture is mounted on the top or side of the sign, is directed onto the sign surface, and does not adversely affect neighboring properties, rights-of-way, or vehicular traffic. The light source shall not be visible from adjacent properties or roads.
- (12) Signs shall not be constructed to include blinking lights, moving parts, or any device capable of emitting noise unless specifically approved by the Development Review Board as a conditional use in accordance with section 5.2.
- (13) All signs shall be maintained in a secure and safe condition. Nothing in these regulations shall prevent normal sign maintenance and repair, including the replacement of broken parts. If the Zoning Administrator is of the opinion that a sign is not secure, safe, or in a good state of repair, a written warning and/or notice of violation under Section 7.5 may be issued with a request that any defect in the sign immediately is corrected.
- (14) No nonconforming sign may be replaced, expanded, or the message altered to advertise a different owner, management or brand, unless such altered sign is brought into conformance with these standards.
- (15) Supporting structures of freestanding signs shall be balanced and proportionate with the sign area and shall consist of posts that are no larger than 8" x 8" unless approved by the Development Review Board in accordance with Section 5.2.
- (C) **Off-Premise Signage.** Notwithstanding Section (B), off-premise signage may be established in accordance with Title 10 §494 and with the written consent of the property owner in which the sign is located. Specifically, the following forms of off-premises signage are allowed in the Town of Hardwick:
 - (1) Directional signs, subject to approval by the Development Review Board, as well as regulations adopted by the Federal Highway Administration, with a total sign face area not to exceed six square feet providing directions to places of business offering for sale agricultural products harvested or produced on the premises where the sale is taking place, or to farmers' markets that are members of the Vermont Farms' Market Association selling Vermont agricultural products.
 - (2) Murals, subject to approval by the Select Board, that relate exclusively to a downtown designated under 24 V.S.A. chapter 76A, whether located within or outside the designated downtown itself, provided that all of the following apply:
 - i. The mural is hand painted, and is painted directly on the outside surface of a

structure that has been in existence on the site for at least the preceding 25 years;

- ii. It is located no more than three miles from the designated downtown; and
- iii. Any words used in the mural pertain only to the direction or distance to, and the name of, the designated downtown.

(3) Alternative municipal information and guidance signs to assist persons in reaching destinations that are transportation centers, geographic districts, historic monuments, and significant or unique educational, recreational, or cultural landmarks, including farmers' markets that are members of the Vermont Farmers' Market Association selling Vermont agricultural products, provided that such destinations are not private, for-profit businesses. Such signage shall be one of the following:

- i. Signage of a uniform nature, with a sign face that does not exceed 12 square feet, a height that does not exceed 12 feet, and of a design that is created in accordance with 10 V.S.A. §494(15).
- ii. Signage of a uniform nature, with a sign face that does not exceed 12 square feet, a height that does not exceed 12 feet, and of a designed that is approved in accordance with 10 V.S.A. §494(17).

(D) Calculation of sign area. (See Illustrations 3.1 and 3.2)

- (1) The width of the sign area shall include all sign faces, lettering, designs, or symbols, together with the background, whether open or enclosed, upon which they are displayed, including any supporting framework incidental to the display itself, except for legs and knobs of supporting posts for freestanding signs.
- (2) The height of the sign area shall be measured to the highest point of the supporting structure, or the height of the sign face, whichever is greater.
- (3) Advertising relating to a specific product or products sold on the premises, or the utilization of corporate symbols, logos, or similar features, shall be included in the aggregate sign area.
- (4) Where a sign consists of multiple sign faces, or individual letters or symbols, the area shall be considered to be the smallest rectangle encompassing all the letters and symbols and any supporting frame.
- (5) In computing the area of a double-faced sign, only one side shall be considered if the faces are identical. Notwithstanding the above, if the interior angle formed by the two faces of the double-faced sign is greater than forty-five (45) degrees, then both sides of such sign shall be considered in calculating the sign area.
- (6) The maximum allowable area of a sign shall include all permanent sign faces attached, painted, or applied to a building façade. If an establishment has walls fronting on two (2) or more streets, the sign area for each street shall be computed separately.

Illustration 3.1: How to measure a free-standing sign





Illustration 3.2: How to measure a wall-mounted sign



Section 3.15 Steep Slopes & Erosion Control

- (A) Development shall not take place on slope gradients in excess of 25% with the exception of limited site improvements necessary to facilitate development on contiguous land less than 25% gradient.
- (B) Required agricultural practices and forestry, as defined in Article 7, are exempted from this Section

Section 3.16 Storage of Hazardous Materials

- (A) The storage of any highly flammable or hazardous liquid or gas in tanks above ground with unit capacity greater than 550 gallons shall be prohibited, unless such tanks up to and including 10,000 gallon capacity are placed not less than 80 feet from all property lines, and unless all such tanks of more than 10,000 gallon capacity are placed not less than 200 feet from all property lines. All storage tanks shall comply with all applicable state and federal regulations. All storage tanks in the Flood Hazard Overlay District shall comply with standards of Section 5.3.
- (B) All tanks (containing flammable liquids) located above-ground and having a capacity greater than 550 gallons shall be properly retained with dikes having a capacity not less than 1.5 times the capacity of the tanks surrounded.

ARTICLE 4. SPECIFIC USE STANDARDS

Section 4.1 Applicability

- (A) The following standards apply to specified uses in all zoning districts in which such uses are allowed. Specified uses may be subject to conditional use review in accordance with Section 5.2. If there is a conflict between a standard in this section and a standard in another section of these bylaws, the more restrictive standard shall apply.

Section 4.2 Accessory Dwelling

- (A) A dwelling unit may be allowed as an accessory to another principal use, subject to the following provisions:
- (1) One attached or detached dwelling unit that is an accessory to a single ~~unit~~family dwelling on an owner-occupied lot, located outside of the flood hazard areas defined in Section 5.3, shall be allowed as a permitted use. Such accessory dwelling shall not exceed 900 square feet or 30% of the total existing living area of the principal dwelling, whichever is greater, and shall meet other applicable requirements under subsections (3) and (4), below.
 - (2) One caretaker's apartment which is accessory to a nonresidential use may be approved as an accessory to another use by the Development Review Board in accordance with Section 5.2. A caretaker's apartment shall be located within the Industrial District, be occupied by the owner or an employee of the principal use, and shall not exceed 900 square feet.
 - (3) All accessory dwellings shall:
 - i. meet setback requirements for accessory structures for the district in which they are located; for nonconforming structures, the degree of nonconformance shall not be increased by the addition of an accessory apartment or dwelling;
 - ii. have adequate potable water and wastewater systems in accordance with applicable municipal and state regulations; and
 - iii. be provided with off-street parking for the residents of the dwelling in accordance with Section 3.13.
 - (4) Any zoning permit issued for an accessory dwelling shall clearly state that the dwelling is permitted only as an accessory to the principal use of the property and shall be retained in common ownership. An accessory dwelling to a single- ~~unit~~family dwelling may be subdivided and/or converted for conveyance or use as a principal dwelling only if it is found to meet all current municipal regulations applying to a two ~~unit~~family dwelling, or to two single ~~family~~ unit dwellings if detached, including all density and dimensional requirements for the district in which it is located. All applicable municipal permits and approvals shall be required prior to conversion to, or conveyance as, a principal dwelling.

Section 4.3 Adaptive Reuse of an Historic Structure

- (A) Adaptive reuse is designed to provide for the continued viability of historic structures that have outlived their original agricultural, civic or industrial function, while retaining their historic character, by allowing additional uses within the current dimensions of such structures, including nonconforming structures, subject to conditional use review under Section 5.2 and the following provisions.

- (B) Structures eligible for adaptive reuse in the Rural Residential (RR) District and Forest Reserve (FR) District are limited to historic buildings which:
 - (1) have historical or architectural significance to the town, as determined by the Development Review Board from application information, listing on federal or state historic site registers or surveys, and/or evidence presented in hearing; and
 - (2) are no less than 50 years old.
- (C) Structures determined to be eligible for adaptive reuse in the Rural Residential (RR) District and Forest Reserve (FR) District may be considered for one or more of the following uses subject to conditional use approval under Section 5.2:
 - (1) any use allowed within the district in which the structure is located;
 - (2) multi-~~unit~~~~family~~ dwelling (maximum of 4 dwelling units);
 - (3) storage facility;
 - (4) the processing and/or sale of agricultural or forest products (e.g., farm produce store, food cooperative, woodworking or furniture shop);
 - (5) cultural facility (e.g., museum, theater, performance space); and
 - (6) retail sales, limited to antiques, arts and crafts.
 - (7) any use which legally occupied the structure as a pre-existing nonconforming use, even if the use is considered discontinued as per Section 3.10
- (D) Structures eligible for adaptive reuses in the Central Business (CB) District, Village Neighborhood (VN) District and/or Compact Residential (CR) District are limited to non-residential structures which:
 - (1) have historical or architectural significance to the town, as determined by the Development Review Board from application information, listing on federal or state historic site registers or surveys, and/or evidence presented in hearing;
 - (2) are no less than 50 years old and are listed, or eligible for listing, on the Vermont Historic Sites and Structures Survey for the Town of Hardwick; and
 - (3) have a minimum floor area of 800 square feet.
- (E) Structures determined eligible for adaptive reuse in the Central Business (CB) District, Village Neighborhood (VN) District and/or Compact Residential (CR) District may be put to one or more of the following uses:
 - (1) any use allowed within the district in which the structure is located;
 - (2) restaurant
 - (3) retail store
 - (4) cultural facility
 - (5) indoor recreation; and
 - (6) storage facility
- (F) Structures determined eligible for adaptive reuse in the Central Business (CB) District, Village Neighborhood (VN) District, Village Center (VC) District and/or Compact

Residential (CR) District may be granted the following modifications to standards contained within these bylaws, subject to conditional use approval under Section 5.2:

- (1) The Development Review Board may waive one or more parking requirements set forth in Section 3.10, provided the Board determines that the proposed use meets the standards set forth in Section 5.2 and that the waiver will not result in or cause unsafe conditions for motorists or pedestrians, and will not adversely impact surrounding properties.
 - (2) The Development Review Board may waive one or more dimensional standards, including residential density standards, set forth in Article 2, provided the proposed use meets the standards set forth in Section 5.2, and that the waiver will not result in or cause unsafe conditions for motorists or pedestrians, and will not adversely impact surrounding properties.
- (G) It also shall be demonstrated to the satisfaction of the Development Review Board for any adaptive reuse of an historic structure, regardless of the district within which it is located, that:
- (1) adequate water supply, septic system, and off-street parking capacity exist to accommodate the proposed use; and
 - (2) any proposed exterior renovations shall maintain the historic and architectural character of the structure, including those characteristics which resulted in the Board's determination that the structure is of historical or architectural significance to the town.

Section 4.4 Recreational Vehicles [Temporary Shelter]

- (A) A recreational vehicle (e.g., camper, travel trailer) or other temporary shelter (e.g., tent, teepee, yurt) may be located, stored or parked on public or private property in accordance with the following requirements:
- (1) Recreational vehicles may be parked in approved campgrounds (see Section 4.5), sales establishments and, for a specified period, on construction sites for use as a temporary structure in accordance with subsection (C).
 - (2) A recreational vehicle may be stored on the lot of a single or two ~~family-unit~~ dwelling and/or on an undeveloped parcel, provided that it is not located within required setbacks for the district in which it is located; is not occupied for dwelling purposes for more than 90 days within any one year period; and is not connected to the residential water or wastewater system.
 - (3) Notwithstanding subsections (1)-(2) above, a recreational vehicle parked in a flood hazard area as defined in Section 5.3 of these bylaws for more than 180 days must be licensed and ready for highway use.
- (B) Any camper or temporary shelter that is used for dwelling purposes for more than 90 days within any one year period, or is sited so as not to be readily moveable, shall be deemed a dwelling and be subject to all zoning regulations applicable to accessory or single ~~unit family~~ dwellings.
- (C) The Zoning Administrator may issue a zoning permit to allow a temporary shelter, including a mobile home, to be occupied for dwelling purposes for not greater than one year to allow a property owner to reside on a parcel while constructing or rehabilitating a

permanent dwelling. Such a temporary shelter shall be removed from the premises within one year of the issuance of the permit, unless the applicant obtains a one year extension, with the approval of the Development Review Board, in accordance with Section 5.2. No structure other than the permitted temporary shelter may be occupied as a dwelling on a single parcel for the period in which the temporary structure is occupied.

- (D) Any wastewater or sewage generated by a camper shall be disposed of off-site in accordance with all applicable state and federal regulations.

Section 4.5 Campground

- (A) A new or expanded recreational vehicle campground, improved seasonal campground, or primitive campground may be permitted in designated zoning districts subject to conditional use review under Section 5.2, applicable requirements under Section 7.1, and the following provisions:
 - (1) The parcel of land for a campground shall be no less than five acres in area or the minimum lot area for the district in which it is located, whichever is greater.
 - (2) All campgrounds shall meet minimum setback requirements for the districts in which they are located. A minimum 75 foot setback shall be required from any residential property. No building, camp site, parking or service area shall be located in setback areas.
 - (3) Landscaping and/or fencing along property boundaries shall be required as appropriate for screening, security, and privacy.
 - (4) Campgrounds shall provide lavatory, shower, and toilet facilities sufficient to serve all camp sites. Water and wastewater disposal systems must be designed and installed in accordance with applicable municipal and state regulations.
 - (5) A campground shall provide sufficient access and parking for each camp site. Each camp site shall be at least 2,000 square feet in area.
 - (6) The campground shall operate for a period not to exceed six months (180 days) during any calendar year, unless otherwise approved by the Development Review Board. Recreational vehicles may be stored on the property only if they are registered for highway use.
 - (7) Adequate provision for the safe, sanitary disposal of trash and recyclables shall be provided on site.
 - (8) Outdoor fires shall not result in a nuisance or threat to neighboring landowners, businesses or residents, nor endanger or adversely affect public health, safety or welfare.
- (B) For substantially undeveloped, primitive camping areas (e.g., tenting areas, backcountry shelters) located on public or private lands, the Development Review Board may waive any or all of the requirements under subsection (A) if it is demonstrated to the Board's satisfaction that access, total lot area, camp site area, and setback distances are sufficient to:
 - (1) support the proposed level of use, and
 - (2) avoid any adverse impacts to water quality, natural areas, and adjoining properties and uses.

Section 4.6 Day Care Facility [Home Child Care, Day Care]

- (A) A state registered or licensed child care home serving six or fewer children on a full-time basis and up to four additional children on a part time basis, which is conducted within a single ~~unit family~~ dwelling by a resident of that dwelling, shall be considered a permitted use of the single ~~unit family~~ residence. No zoning permit is required for home child care providing it meets the requirements of this section.
- (B) The home day care shall be permitted one unlit wall-mounted or freestanding sign not to exceed 4 square feet in area.
- (C) Nonresidential day care facilities, and those facilities operated from a dwelling which serve greater than six children full-time and four part-time children, may be permitted in designated zoning districts as a conditional use subject to review under Section 5.2.

Section 4.7 Residential Care and Group Homes

- (A) In accordance with the Act [§4412(1)(G)], a residential care home or group home to be operated under state licensing or registration, serving not more than eight persons who have a handicap or disability as defined in 9 V.S.A. § 4501 shall be considered to constitute a permitted single ~~unit family~~ residential use of property,

Section 4.8 Extraction of Earth Resources

- (A) The extraction or removal of topsoil, sand, gravel, rock, minerals or other similar earth resource for may be allowed in designated districts subject to conditional use review under Section 5.2. In addition to the conditional use standards set forth in Section 5.2, for commercial extraction operations which are likely to impact surrounding properties due to the scale, intensity and timing of the extraction, the presence of fragile natural features (e.g., steep slopes, riparian land), and/or the relative density of nearby land uses, the Development Review Board may also require erosion control and site reclamation plans showing:
 - (1) existing grades, drainage patterns and depths to bedrock and the seasonal high water table;
 - (2) the extent and magnitude of the proposed operation, including proposed phasing;
 - (3) finished grades at the conclusion of the operation; and
 - (4) a detailed plan for the restoration of the site, including final grading and revegetation.
- (B) In granting approval, the Development Review Board may impose conditions with regard to any of the following factors:
 - (1) depth of excavation or quarrying;
 - (2) slopes created by removal;
 - (3) effects on surface drainage on and off-site;
 - (4) storage of equipment and stockpiling of materials on-site;
 - (5) hours of operation for blasting, trucking, and processing operations;
 - (6) effects on adjacent properties due to noise, dust, or vibration;
 - (7) effects on traffic and road conditions, including potential physical damage to public

highways;

- (8) creation of nuisances or safety hazards;
- (9) temporary and permanent erosion control, including project phasing to limit exposed area;
- (10) effect on ground and surface water quality, and drinking water supplies;
- (11) effect on natural, cultural, historic, or scenic resources on-site or in the vicinity of the project;
- (12) effect on agricultural land; and
- (13) public health, safety and general welfare.

(C) In accordance with the Act [§4412(12), §4464(B)(6)] a performance bond, escrow account, or other surety acceptable to the Select Board may be required to ensure reclamation of the land upon completion of the excavation, to include any re-grading, reseeded, reforestation or other reclamation activities that may be required. This provision specifically does not apply to mining or quarrying operations; however upon failure of the permit holder, or their successors or assigns, to complete site reclamation as required, the town may take legal action as appropriate to ensure site reclamation and cost recovery.

(D) This section shall not apply to non-commercial uses associated with normal agricultural and/or forestry operations; public (municipal and state) road maintenance and construction; the operation of a cemetery, or the removal of earth resources for a use that is incidental to another duly permitted construction activity located on the same parcel from which the materials were extracted.

Section 4.9 Home Businesses [Home Occupation, Home Industry]

- (A) **Home Occupations.** No provision of these regulations may infringe upon the right of any resident to use a minor portion of a dwelling for an occupation which is customary in residential areas and which does not have an undue adverse effect upon the character of the surrounding neighborhood or area. No zoning permit is required for a home occupation. All home occupations shall comply with the following standards:
- (1) The home occupation shall be carried on by residents of the dwelling.
 - (2) The home occupation shall not occupy a gross floor area greater than 30% of the combined gross floor area of the principal dwelling and accessory structure.
 - (3) Exterior storage or displays, other than that characteristic of a residential use, is prohibited.
 - (4) The home occupation shall meet all performance standards set forth in Section 3.11.
 - (5) No traffic shall be generated in substantially greater volumes than would normally be expected from a residential use.
 - (6) The home occupation shall be permitted one unlit wall-mounted or freestanding sign not to exceed 4 square feet in area.
 - (7) The outdoor storage of materials that are not customary of a residential use is prohibited.

(8) On-site wholesale or retail sales shall be limited to products produced or services provided on the premises, which will be available to the public by appointment only.

(B) **Home Industry.** Home industry, as distinguished from “home occupation” under Subsection (A), may be allowed as an accessory to a single ~~unit family~~ dwelling in designated zoning districts subject to conditional use review under Section 5.2, and the following provisions:

- (1) The home industry shall be conducted by residents of the dwelling, and up to three full-time nonresident employees (or full-time equivalent part-time nonresident employees).
- (2) The home industry shall be carried out within the principal dwelling or an accessory structure.
- (3) Exterior storage areas for materials and equipment associated with the home industry may be approved by the Development Review Board provided that such areas are clearly designated and are adequately screened from public view and neighboring properties. Designated storage areas shall meet the setbacks for the district in which the use is located, although the Board may require greater setbacks to avoid impacts on neighboring properties. The storage of hazardous materials anywhere on the premises is prohibited, with the exception of materials customary and characteristic of residential uses (e.g., heating oil).
- (4) The home industry shall not have an undue adverse effect upon the character of the neighborhood, or result in a change in the outward appearance of the dwelling or the accessory structure.
- (5) The home industry shall not generate traffic, including delivery traffic, in excess of volumes characteristic of other uses allowed in the district in which the home industry is located.
- (6) Off-street parking shall be provided for resident, employee, customer and delivery vehicles, as well as all commercial vehicles or equipment associated with the home industry.
- (7) Adequate provisions shall be made for water, wastewater and the disposal of solid waste, in accordance with applicable municipal and state regulations.
- (8) Home industries shall meet all performance standards set forth in Section 3.11.
- (9) The home industry shall be permitted one unlit wall-mounted or freestanding sign not to exceed 4 square feet in area.
- (10) On-site wholesale or retail sales shall be limited to products produced or services provided on the premises.

(C) The zoning permit issued for a home industry shall clearly state that the home based business is permitted only as an accessory to the principal residential use of the property, and as such shall be retained in common ownership. A home occupation or home industry may be subdivided and/or converted for conveyance as a separate, principal use only if it is found to meet all current municipal regulations applying to such use, including all density and dimensional requirements for the district in which it is located. All applicable municipal permits and approvals shall be required prior to subdivision,

conversion, or conveyance of a home business as a principal use.

Section 4.10 Light Industry

- (A) Light industry (as distinguished from home industry under Section 4.9 may be permitted in designated zoning districts subject to conditional use review under Section 5.2. Within the Central Business (CB) District and Highway Mixed-Use (HMU) District, light industry also shall meet the following provisions:
- (1) All industrial activities, and the maintenance and repair of vehicles and equipment, shall be conducted within an enclosed building or buildings.
 - (2) The Development Review Board may limit the outdoor storage of materials, vehicles and heavy equipment shall be limited to a designated area, and may require that such area be screened year-round from the road and from neighboring properties.
 - (3) Any area designated for the outdoor storage of materials shall be located outside of flood hazard areas and set back a minimum of 100 feet from road rights-of-way, surface waters, wetlands and adjacent properties. All other setback and dimensional standards for the district in which the light industry is located shall apply. The Development Review Board may however, as a condition of approval, require greater setbacks based on specific site conditions to protect water quality and neighboring properties.
 - (4) Industrial uses shall comply with all performance standards under Section 3.11; additional conditions, including conditions on the hours of operation, may be imposed as appropriate to protect public health, safety, and welfare, municipal facilities and services, and other public investments.
 - (5) The on-site storage of hazardous materials shall require the specific approval of the Development Review Board. In approving such storage the Board shall require the submission of a hazard mitigation plan, prepared by the applicant, to ensure the protection of ground and surface waters and public safety in the event of a spill or release.
 - (6) Sufficient landscaping and screening shall be provided along parcel boundaries and within the project site to protect adjacent properties from objectionable visual impacts. At a minimum, a landscaped buffer a minimum of 30 feet deep shall be located along all boundaries adjoining a residential property.
- (B) The standards set forth in subsection (A), above, shall not apply to lands within the Industrial District.

Section 4.11 Agricultural and Forest Processing:

- (A) Agricultural and Forest Processing may be permitted in designated zoning districts subject to conditional use review under Section 5.2 and the following provisions:
- (1) The processing facility shall be of a size and scale appropriate for the neighborhood in which it is proposed.
 - (2) Where a processing facility uses or generates hazardous materials, the applicant shall demonstrate compliance with applicable state or federal regulations.
 - (3) Wholesale sales of processed products are allowed as a part of any approval. Retail

sales may be allowed as a part of conditional use approval. Sales of products in addition to those processed on the site will be limited to those clearly incidental, secondary and ancillary to those processed products or as declared and approved as a part of the conditional use permit.

Section 4.12 Mixed Use

- (A) In designated zoning districts, more than one principal use may be allowed within a single building, or on a single lot, subject to the following provisions:
- (1) Each of the proposed uses is allowed as a permitted or conditional use within the zoning district in which the mixed use is located.
 - (2) The uses in combination meet all applicable standards for the district in which the mixed use is proposed, including minimum lot, frontage and setback requirements; or the mixed use is part of a planned unit development (PUD) reviewed in accordance with Section 5.54.
 - (3) The mixed use shall meet all applicable general regulations under Article 3, including but not limited to sign and parking requirements.

Section 4.13 Mobile Home Park

- (A) Mobile home parks may be permitted in designated districts subject to conditional use review in accordance with Section 5.2 and the following provisions:
- (1) Proposed parks shall comply with all applicable state regulations, including regulations relating to water supply and wastewater disposal.
 - (2) The parcel of land for a mobile home park shall have a minimum area of no less than five acres, or the minimum lot area for the district in which it is located, whichever is greater.
 - (3) Each mobile home shall be located on a dedicated site of not less than 5,000 square feet in area.
 - (4) Mobile home parks shall meet minimum setback requirements along their perimeter for the district in which they are located. Setback areas shall not be included in the calculation of recreation land or open space under Subsection (9).
 - (5) Each mobile home shall be set back a minimum of 10 feet from adjoining mobile home sites.
 - (6) All roads within a mobile home park shall comply with Section 6.6, and adequate walkways shall be provided.
 - (7) Parking shall be provided in accordance with Section 3.130.
 - (8) ~~(8)~~ A minimum of 20% of the total land area in any mobile home park shall be set aside for common recreational use or open space.
- (B) The mobile home park owner, or designated operator, as a condition of ~~Board of Adjustment Development Review Board~~ approval, shall:
- (1) maintain all park buildings, roads, parking areas, paths, utilities, infrastructure, landscaping, open space and common areas in good condition, and shall provide for

Formatted: Indent: Left: 0", First line: 0"

the regular collection and removal of recyclables, waste and garbage; and

- (2) remove snow from all park roads and service areas.

Failure to meet these operation and maintenance requirements shall constitute a violation of permit conditions and these regulations, subject to enforcement action under Section 7.5.

- (C) Changes or alterations to park area, design, layout or common facilities are subject to conditional use review in accordance with the above provisions. The owner of a mobile home within an approved mobile home park may apply for a zoning permit under Section 7.1 for a deck or accessory structure which meets site setback requirements under Subsection (A), without additional approval by the Development Review Board under Section 5.2. The replacement of a permitted mobile home within an approved mobile home park shall require a zoning permit issued by the Zoning Administrator in accordance with Section 7.1 to ensure ongoing compliance with all conditions of conditional use approval.

Section 4.14 Motor Vehicle Service & Gas Stations

- (A) Motor vehicle service stations and gas stations may be allowed in designated districts subject to conditional use review under Section 5.2 and the following requirements:
 - (1) No vehicle may be parked, stored or displayed within the setback areas for the district in which the business is located.
 - (2) There shall be no more than two (2) curb cuts providing access to and from adjoining roads. On corner or through lots, one or both accesses may be limited to the secondary road. The width of a curb cut shall not exceed 35 feet.
 - (3) The service and/or repair of motor vehicles shall be conducted within an enclosed structure.
 - (4) All buildings, equipment, service, parking and storage areas shall be set back at least 150 feet from streams, surface waters and wetlands. The setback area shall be maintained as a vegetated buffer. The required setback may be increased as appropriate to protect water quality, based on local site and drainage conditions.
 - (5) Gasoline pumps shall be located not less than 15 feet from any road right-of-way. All pumps, lubricating and other service equipment shall be located at least 35 feet from side and rear lot lines.
 - (6) Gasoline service stations, in addition to the signs allowed under Section 3.14, may have one pricing sign which does not exceed 12 square feet in area and/or pump-top pricing signs, each not to exceed 2 square feet in area.
 - (7) Gas station canopies shall be limited to the minimum area required for adequate pump and apron coverage, and the minimum ceiling height necessary to meet applicable state and federal safety requirements. Canopy design, including materials and roof pitch, shall be compatible with surrounding buildings.
 - (8) Light fixtures mounted on station canopies shall either be recessed so that the lens cover is flush with the bottom surface (ceiling) of the canopy; or for indirect lighting, mounted and shielded or skirted so that direct illumination is focused exclusively on the underside of the canopy. Lights shall not be mounted on the top or sides (fascia) of canopies, nor shall canopies be internally illuminated.

- (9) Gasoline stations which include retail sales unrelated to motor vehicle service, maintenance or repair (e.g., food, convenience items) shall be reviewed as a mixed use, and as such be required to meet all zoning provisions pertaining to retail uses for the district in which they are located, including but not limited to additional sign, lot size and/or parking requirements.

Section 4.15 Protected Public Uses

- (A) In accordance with the Act [§4413(a)], reasonable provision has been made for the following uses within designated districts, shown in Table 4.1 which may be regulated only with respect to size, height, building bulk, yards, courts, setbacks, density of buildings, off-street parking, loading facilities, traffic, noise, lighting, landscaping and screening requirements and only to the extent that regulations do not have the effect of interfering with the intended functional use.

| TABLE 4.1: PROTECTED PUBLIC USES | |
|---|--------------------------------|
| Facility | Specified District(s) |
| Public and private hospitals. | CB, VN, CR, <u>VC</u> |
| Regional solid waste management facilities certified by the State [10 V.S.A., Chapter 159]. | RR (see Landfill) |
| Hazardous waste management facilities for which a notice of intent to construct has been received under state law [10 V.S.A., §6606a]. | I |
| State or community owned and operated institutions and facilities [see Public Facility]. | All Districts |
| Public and private schools and other educational institutions certified by the Vermont Department of Education , <u>Vermont Agency of Educatio</u> | CB, VN, HMU, CR, RR, <u>VC</u> |
| Churches, convents and parish houses [see Place of Worship] | CB, VN, HMU, CR, RR, <u>VC</u> |
| Emergency Shelters | CB, VN, HMU, CR, <u>VC</u> |
| <u>Hotels and motels converted to permanently affordable housing developments.</u> | <u>CB, VN, HMU, CR, VC</u> |

- (B) With the exception of State-owned and operated institutions and facilities, the uses identified in Table 4.1 shall be subject to compliance with the National Flood Insurance Program, the development standards of Section 5.3, and all other provisions of these bylaws pertaining to development in the Town of Hardwick’s flood hazard overlay. These regulations, however, shall not have the effect of interfering with the intended functional use.

Section 4.16 Salvage Yard

- (A) New or expanded salvage yards may be permitted within designated zoning districts subject to conditional use review under Section 5.2 and the following requirements:
 - (1) Salvage yards shall meet all setback standards for the district in which the yard is located, and shall be set back at least 75 feet from surface waters and wetlands. Required setbacks may be increased as appropriate based on specific site conditions, and to protect water quality and neighboring properties.
 - (2) Yards shall be screened year-round from public view and from adjoining residential properties. Additional landscaping, fencing or other forms of screening may be required as appropriate. No vehicles associated with the business, or any other

waste, scrap, parts or materials shall be stacked, piled or stored higher than the fence or screen.

- (3) Salvage yards shall be secured as necessary to protect public health, safety, and welfare, and neighboring properties. Exterior lighting shall be the minimum required for security and safe operation.
 - (4) Conditions and limitations may be imposed with regard to traffic generated, hours of operation, and the on-site storage of hazardous materials in order to protect neighboring properties, public infrastructure including roads, and the character of the area in which the yard is located.
 - (5) All salvage yards shall be licensed in accordance with State of Vermont regulations pertaining to salvage yards, and shall be responsible for all upkeep and maintenance of fences, screening, and other required site improvements, and the proper storage of salvaged and hazardous materials, as required under municipal and state regulations, and associated conditions of approval.
 - (6) The on-site storage of materials shall not adversely affect surface, ground or drinking water supplies.
- (B) In addition to application requirements under Section 5.2, the applicant for a new or expanded salvage yard shall submit a description of existing and proposed operations, including storage areas, all equipment to be used on-site, and a site development plan that includes the following information:
- (1) the extent in area of existing and/or proposed salvage yard operations, including all storage and processing areas, and distances from property boundaries, public streets, wetlands, surface waters and public and private wells on-site and in the vicinity;
 - (2) site contours that show existing and proposed grades and drainage patterns,
 - (3) test boring results indicating soil types, and depths to bedrock and seasonal high water tables within the proposed area of operation; and
 - (4) existing and/or proposed ground water monitoring well locations, if any.
- (C) All materials shall be removed from the site within twelve months of the cessation or abandonment of operations; and the site shall be restored to a safe, usable condition. Site restoration, including the clean-up and disposal of hazardous materials, shall be subject to all applicable state and federal regulations. A site restoration plan may be required as a condition of approval.

Section 4.17 Telecommunications Facility

- (A) **Purpose.** The purpose of these regulations is to protect the public health, safety, general welfare and scenic character of the Town of Hardwick, while accommodating the communication needs of residents and businesses. The intent of these regulations is to:
- (1) preserve the character and appearance of the town while allowing adequate services and coverage to be developed;
 - (2) protect the scenic, historic, environmental and natural resources of the town;
 - (3) provide standards as requirements for the siting, design, appearance, construction,

operation, and removal of telecommunications facilities;

- (4) minimize tower and antenna proliferation by requiring the co-location and sharing of existing telecommunications facilities wherever feasible and appropriate; and
- (5) facilitate the provision of telecommunications services to residents and businesses in town.

(B) **Federal Limitations.** In accordance with federal law, these regulations shall not have the effect of prohibiting personal wireless services, unreasonably discriminating among providers of functionally equivalent services, nor regulating wireless telecommunications facilities based on emissions which are subject to and in compliance with Federal Communications Commission (FCC) regulations.

(C) **Applicability.** Wireless telecommunications facilities shall include all facilities subject to licensing or regulation by the FCC, including towers, associated accessory structures, buildings and/or equipment, except as specifically exempted under subsection (D). New, modified or expanded wireless telecommunication facilities, except as specified for small scale facilities under subsection (G), may be allowed in designated zoning districts as conditional uses subject to review under Section 5.2 and the requirements of this section. However:

(D) **Exemptions.** The following are specifically exempted from the provisions of this Section:

- (1) A single ground or building mounted satellite dish not exceeding 36 inches in diameter which is intended solely for residential use, and does not, as mounted, exceed 35 feet in height above the lowest grade at ground level.
- (2) An antenna used to transmit, receive, or transmit and receive communications signals on that property owner's premises if the area of the largest face of the antenna is not more than 15 square feet, and if the antenna and any mast support do not extend more than 12 feet above the roof of that portion of the building to which the mast is attached.
- (3) The regulation of a telecommunications facility as defined in 30 V.S.A. §248a, shall be exempt from municipal approval when and to the extent jurisdiction is assumed by the Public Service Board.
- (4) Citizens band radio antennas operated by federally licensed amateur radio operators which do not exceed a height of 50 feet above the grade level, whether free standing or mounted, and which meet all setback requirements for the district in which they are located.
- (5) Replacement of telecommunications facilities operated by public (municipal, state or federal) or not-for-profit emergency service providers (e.g., police, fire, ambulance) in association with their duties.

(E) **Application Requirements.** In addition to application requirements under Section 5.2, applications for new towers shall also include the following:

- (1) The applicant's legal name, address and telephone number. If the applicant is not a natural person, the applicant shall provide the state in which it is incorporated and the name and address of its resident agent.

- (2) The name, title, address and telephone number of the persons to whom correspondence concerning the application should be sent.
- (3) The name, address, and telephone number of the owner or lessee of the property on which the Wireless Telecommunication Facility will be located.
- (4) The names and addresses of all adjoining property owners. Adjoining property owners shall be determined without regard to any public right-of-way.
- (5) A vicinity map showing the entire vicinity within a 1,000 foot radius of the Facility, including the location of any tower, topography, public and private roads and driveways, buildings and structures, utilities, water bodies, wetlands, landscape features, historic sites and necessary wildlife habitats. It shall indicate the property lines of the proposed Facility site parcel and all easements or rights of way needed for access from a public way to the Facility.
- (6) The location of the Facility on a USGS Topographic Map or a GIS-generated map compatible with Vermont Center for Geographic Information (VCGI) standards and encompassing the area within at least a two-mile radius of the proposed tower site.
- (7) Elevations and proposed site plans of the Facility showing all facades and indicating all exterior materials and colors of towers, buildings and equipment, as well as all landscaping, utility wires, guy wires and screening. (All plans shall be drawn at a minimum scale of 1 inch = 50 feet).
- (8) In the case of a site that is forested, the approximate average elevation of the existing vegetation within 50 feet of any tower base.
- (9) Construction sequence and time schedule for completion of each phase of the entire project.
- (10) A report from a qualified engineer that:
 - a. Describes any tower's design and elevation,
 - b. Documents the elevation above grade for all proposed mounting positions for antennas to be collocated on a tower and the minimum distances between antennas,
 - c. Describes a tower's capacity, including the number, elevation and types of antennas that the tower is proposed to accommodate.
 - d. In the case of new Facilities, demonstrates that existing towers and structures within 5 miles of the site cannot reasonably be modified to provide adequate coverage and adequate capacity to the community.
 - e. Describes potential changes or additions to existing structures or towers that would enable them to provide adequate coverage.
 - f. Describes the output frequency, number of channels and the power output per channel for each antenna. In the alternative, a coverage map may be provided.
 - g. Demonstrates the Facility's compliance with the standards set forth in this bylaw or other applicable standards.
 - h. Provides proof that at the proposed Facility site the applicant will be in compliance with all FCC regulations, standards and requirements, and includes a

statement that the applicant commits to continue to maintain compliance with all FCC regulations, standards and requirements for radio frequency radiation (RFR).

i. Includes such other information as determined by the Development Review Board to evaluate the application.

- (11) A letter of intent committing the Facility owner and its successors to permit shared use of any tower if the additional users agree to meet reasonable terms and conditions for shared use, including compliance with all applicable FCC regulations, standards and requirements and the provisions of this Bylaw and all other applicable laws.
- (12) In the case of an application for additional antennas or other equipment to be installed on an existing Facility, a copy of the executed contract with the owner of the existing structure.
- (13) To the extent required by the National Environmental Policy ACT (NEPA) and as administered by the FCC, a complete Environmental Assessment (EA) draft or final report describing the probable impacts of the Facility, or a written statement by the applicant that an EA is not required for the facility.

(F) **Consultants.** Upon submission of an application for a Telecommunication Facility permit, the Development Review Board may require a report by consultants whose services shall be paid for by the applicant. These consultants shall be qualified professionals in telecommunications engineering, structural engineering, monitoring of electromagnetic fields and such other fields as determined by the Development Review Board. The consultant(s) shall work at the Board's direction and shall provide the Board such reports and assistance as the Board deems necessary to review an application.

(G) **Balloon Test.** The Development Review Board may require the applicant to fly a four-foot diameter brightly colored balloon at the location and maximum elevation of any proposed tower. If a balloon test is required, the applicant shall advertise the date, time, and location of this balloon test at least 7 days in advance of the test in a newspaper with a general circulation in the Town. The applicant shall also inform the Development Review Board, in writing of the date, time and location of the test at least 15 days in advance of the test. The balloon shall be flown for at least eight consecutive daylight hours on two days. If visibility and weather conditions are inadequate for observers to be able to clearly see the balloon test, further tests may be required by the Development Review Board.

(H) **Criteria for Approval and Conditions.** An application for a Telecommunication Facility permit shall be approved after a hearing when the Development Review Board finds all the following criteria have been met:

- (1) The Facility will not be built on speculation. If the applicant is not a Telecommunication Service Provider, the Development Review Board may require the applicant to provide a copy of a contract or letter of intent showing that a Wireless Telecommunication Service Provider is legally obligated to locate a Telecommunication Facility on lands owned or leased by the applicant.
- (2) The Facility will not project more than 20 feet above the average elevation of the tree line measured within 50 feet of the highest vertical element of the Telecommunication Facility, unless the proposed elevation is reasonably necessary

to provide adequate Wireless Telecommunication Service capacity or coverage or to facilitate collocation of facilities.

- (3) No wireless telecommunication facility shall be located within 500 feet of an existing residence.
- (4) The minimum distance from the base of any tower to any property line is not less than 100% of the total elevation of the tower, including antenna or equipment, unless otherwise permitted by the Development Review Board in accordance with one of the following:
 - a. if tower design and construction guarantees that, if it collapses, it will collapse inwardly upon itself, and that no liability or risk to adjoining private or public property shall be assumed by the municipality; or
 - b. to allow for the integration of a tower into an existing or proposed structure such as a church steeple, light standard, utility pole, or similar structure, to the extent that no hazard to public health, safety or welfare results.
- (5) The tower including attached antennas does not exceed a height of 180 feet.
- (6) The Facility will not be illuminated by artificial means and will not display any lights or signs except for such lights and signs as required by Federal Aviation Administration, federal or state law, this bylaw, or as needed for the safe operation of the facility.
- (7) The applicant will remove the Facility, should the Facility be abandoned or cease to operate. The Development Review Board may require the applicant to provide a bond, or other form of financial guarantee acceptable to the Development Review Board to cover the cost of removal of the Facility, should the Facility be abandoned or cease to operate.
- (8) The applicant demonstrates that the facility will be in compliance with all FCC standards and requirements regarding radio frequency radiation.
- (9) The applicant will maintain adequate insurance on the Facility.
- (10) The Facility will be properly identified with appropriate warnings indicating the presence of radio frequency radiation. The Development Review Board may condition a permit on the provision of appropriate fencing.
- (11) The proposed equipment cannot be reasonably collocated at an existing Telecommunication Facility. In determining whether the proposed equipment cannot be reasonably collocated at an existing facility, the Development Review Board shall consider the following factors:
 - a. The proposed equipment would exceed the structural or spatial capacity of the existing facility and the existing facility cannot be reinforced, modified or replaced to accommodate planned equipment at a reasonable cost.
 - b. The proposed equipment would materially impact the usefulness of other equipment at the existing facility and such impact cannot be mitigated or prevented at a reasonable cost.
 - c. The proposed equipment, alone or together with existing equipment, would create radio frequency interference and/or radio frequency radiation in violation of

federal standards.

- d. Existing towers and structures cannot accommodate the proposed equipment at an elevation necessary to function reasonably or are too far from the area of needed coverage to function adequately.
- e. Collocation of the equipment upon existing tower would cause an undue aesthetic impact.

(12) The Facility provides reasonable opportunity for collocation of other equipment.

(13) The Facility will not unreasonably interfere with the view from any public park, natural scenic vista, historic building or district, or major view corridor.

(14) The Facility will not have an undue adverse aesthetic impact. In determining whether a facility has an undue adverse aesthetic impact, the Development Review Board shall consider the following factors:

- a. The results of the balloon test, if conducted.
- b. The extent to which the proposed towers and equipment have been designed to blend into the surrounding environment through the use of screening, camouflage, architectural design, and/or imitation of natural features.
- c. The extent to which access roads have been designed to follow the contour of the land and will be constructed within forest or forest fringe areas and not open fields.
- d. The duration and frequency with which the Facility will be viewed on a public highway or from public property.
- e. The degree to which the Facility will be screened by existing vegetation, topography, or existing structures.
- f. Background features in the line of sight to the Facility that obscure or make the Facility more conspicuous.
- g. The distance of the Facility from the point of view and the proportion of the facility that is above the skyline.
- h. The sensitivity or unique value of a particular view affected by the Facility.
- i. Any significant disruption of a view shed that provides context to an important historic or scenic resource.

(15) The Facility will not destroy or significantly imperil necessary wildlife habitat or that all reasonable means of minimizing the destruction or imperilment of such habitat or species will be utilized.

(16) The Facility will not generate undue noise.

(17) The extent to which utility lines (e.g. power) serving telecommunications facilities follow access roads and does not involve extensive clearing; the Development Review Board may require that such utilities be buried where they are likely to otherwise have an adverse visual impact.

(I) **Small Scale and Temporary Facilities.** Notwithstanding the requirements of Section 4.17(G), the following may be permitted in any zoning district by the Zoning

Administrator without conditional use approval:

- (1) Small scale wireless telecommunications equipment, including antennas, microcells or repeaters, which are to be installed on existing towers, utility poles, or other structures; or the installation of ground facilities less than 20 feet in height, provided that:
 - a. no such device is located within 50 feet of an existing residence;
 - b. no changes are made to the height or appearance of such structure except as required for mounting;
 - c. the height of the facility as mounted does not extend the total height of the structure by more than 10 feet;
 - d. no panel antenna shall exceed 72 inches in height or 24 inches in width;
 - e. no dish antenna shall exceed 3 feet in diameter; and
 - f. any accompanying equipment shall be screened from view.
- (2) Wireless communications facilities designed for temporary use, provided that:
 - a. the temporary facility is permitted for the duration of the intended use or event, as specified in the permit, which shall not exceed 60 days, and is removed immediately upon the expiration of the permit,
 - b. the height of the facility does not exceed 50 feet from grade, and
 - c. the facility complies with all other applicable provisions of these regulations.

(J) **Continuing Obligations for Wireless Telecommunication Facilities.** The owner of a Telecommunication Facility shall, at such times as requested by the Development Review Board, file a certificate showing that it is in compliance with all FCC standards and requirements regarding radio frequency radiation, and that adequate insurance has been obtained for the Facility. Failure to file a certificate within the timeframe requested by the Development Review Board, shall mean that the Facility has been abandoned.

(K) **Removal of Abandoned or Unused Facilities.** Unless otherwise approved by the Development Review Board, an abandoned or unused Telecommunication Facility shall be removed within 90 days of abandonment or cessation of use. If the Facility is not removed within 90 days of abandonment or cessation of use, the Development Review Board may cause the Facility to be removed. The costs of removal shall be assessed against the Facility owner.

Unused portions of a Telecommunication Facility shall be removed within 180 days of the time that such portion is no longer used. Replacement of portions of a Facility previously removed shall require a new permit.

Section 4.18 Temporary Structure or Use

(A) **Temporary Structure.** Structures used for temporary office or storage space (e.g., trailers, mobile homes), or for special events requiring a permit under Subsection (B), may be allowed as a temporary accessory structure to a preexisting or permitted use, provided that such structures are not located in flood hazard areas as defined in Section 5.3. Such structures shall be set back a minimum of 5 feet from all property boundaries and shall not be used for dwelling purposes unless specifically approved under Section

4.2. A zoning permit is required for a temporary structure that is located on a parcel for greater than one year. All temporary structures shall be dismantled and/or removed after one year, or the owner shall obtain a zoning permit in accordance with Section 7.1 and all relevant standards contained in these bylaws.

- (B) **Temporary Dwellings.** Temporary dwellings and campers are subject to Section 4.4.
- (C) **Special Events.** Special events (e.g., concerts, festivals, fairs and other cultural events, trade and antique shows), may be allowed as a temporary use, provided that such use occurs for no more than seven days within any twelve month period, and adequate off-street parking and circulation, sanitary and trash collection facilities are provided. Special events may be issued a zoning permit by the Zoning Administrator, for a specified period of time not to exceed one year from the date of issuance, with the provision that the use will be discontinued upon the expiration of the permit. In addition:
 - (1) Family or household events associated with a residential use (e.g., weddings, reunions) are exempt from this provision, and shall not require a zoning permit.
 - (2) Special events with an expected attendance of over 100 people, or extending more than seven days within a twelve month period, shall be subject to conditional use review by the Development Review Board under Section 5.2 prior to the issuance of a zoning permit.
 - (3) No zoning permit shall be issued for any event or use which also requires the approval of the Hardwick Select Board and/or the Hardwick Chief of Police until such approval is issued.

Section 4.19 Private Family Cemeteries

(A) Purpose: To allow private family cemeteries in appropriate zoning districts while ensuring alignment with public health standards, environmental protection, and long-term land use planning.

Formatted: Subsection-indent, Numbered + Level: 1 + Numbering Style: A, B, C, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"

(B) Permit Requirements: A zoning notification is required prior to establishing a private family cemetery. Applications must include:

(1) A site sketch identifying proposed burial location, property lines, existing structures, wells, septic systems, water bodies, and access routes;

Formatted: Sub-Subsection, Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.5" + Indent at: 0.75"

(2) State-issued burial-transit permit or equivalent documentation;

(3) Signed attestation limiting the use to immediate or extended family members;

(4) Documentation of burial site in GPS coordinates or narrative location description for land record filing.

(C) Exemption from Subdivision Review: Private family cemeteries are exempt from subdivision review provided that:

Formatted: Subsection-indent, Numbered + Level: 1 + Numbering Style: A, B, C, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"

(1) No separate parcel is created or conveyed;

(2) The cemetery remains under single ownership with the parent parcel;

(3) There is no commercial activity, sale, or lease of burial plots;

(4) Public access is not offered or implied.

Formatted: Sub-Subsection, Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.5" + Indent at: 0.75"

(D) Environmental Safeguards: All private family cemeteries must comply with the following minimum setbacks and siting restrictions:

(1) Minimum 500 feet from any public or private potable water source (wells, springs);

(2) Outside mapped river corridors, floodplains, and floodways;

(3) Minimum 100 feet from wetlands, streams, or surface water unless reviewed by the Town Health Officer in consultation with the Zoning Administrator.

(4) Minimum burial depth of 3.5 feet in compliance with 18 V.S.A. § 5319 (b).

(E) Long-Term Access and Disclosure: If the parcel containing a private cemetery is subdivided or conveyed, the burial area must be legally described in the deed, and legal access must be maintained. The presence and location of the cemetery must be disclosed to future property owners.

(F) Fencing and Marking: Fencing is not required; however, burial areas shall be demarcated using stones, plantings, signage, or other non-obtrusive means. Headstones are optional.

(G) Recordkeeping: The burial site and documentation shall be filed with the Town Clerk and recorded in the Town Land Records in compliance with 18 V.S.A. § 5311

Formatted: Subsection-indent, Numbered + Level: 1 + Numbering Style: A, B, C, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"

Formatted: Sub-Subsection, Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.5" + Indent at: 0.75"

Formatted: Subsection-indent, Numbered + Level: 1 + Numbering Style: A, B, C, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"

Formatted: Subsection-indent

ARTICLE 5. DEVELOPMENT REVIEW

Section 5.1 Site Plan Review

- (A) **Applicability.** Site plan review standards shall apply to the approval of non-frontage lots, as per Section 3.3 of these bylaws.
- (B) **Application Requirements.** In addition to the application requirements under Section 7.1 for a zoning permit, an application for site plan review by the Development Review Board shall include associated fees, and one original and two complete copies of the following information as applicable to the development:
- (1) Applicant information, including the name and address of the applicant, the property owner of record, and the person or firm preparing the application and supporting materials.
 - (2) The date of the application (to also be shown on all supporting materials).
 - (3) A general location map (on a USGS topographic map or Vermont orthophoto base) showing the location of the proposed development in relation to zoning districts, public highways, drainage and surface waters, and adjoining properties and uses.
 - (4) A site plan, drawn to scale, which shows:
 - a. north arrow, scale, title (project name), date, and the name of the preparer;
 - b. property lines, dimensions and required setback distances;
 - c. the location (footprints) of existing and proposed structures, including all buildings, other structures, signs, and/or walls;
 - d. existing and proposed rights-of-way and easements,
 - e. existing and proposed roads, driveways, parking and loading areas, and pedestrian paths; and
 - f. existing and proposed utility lines, water supply and wastewater disposal areas.

Section 5.2 Conditional Use Review

- (A) **Applicability.** Conditional Use Review standards shall apply to those uses designated as conditional uses in Article 2, or as otherwise specified under Articles 3 (General Regulations) and 4 (Specific Use Standards). Such uses are subject to conditional use review by the Development Review Board.
- (B) **Application Requirements.** In addition to the application requirements under Section 7.1 for a zoning permit, an application for conditional use review by the Development Review Board shall include associated fees, and one original and two complete copies of the following information as applicable to the development:
- (1) Applicant information, including the name and address of the applicant, the property owner of record, and the person or firm preparing the application and supporting materials.
 - (2) The date of the application (to also be shown on all supporting materials).
 - (3) A general location map (on a USGS topographic map or Vermont orthophoto base) showing the location of the proposed development in relation to zoning districts,

public highways, drainage and surface waters, and adjoining properties and uses.

- (4) A site plan, drawn to scale, which shows:
- g. north arrow, scale, title (project name), date, and the name of the preparer;
 - h. property lines, dimensions and required setback distances;
 - i. existing site features, including ridgelines, hill tops and areas of steep slope (greater than 25%); drainage, surface waters, wetlands, and associated setback areas; vegetation and tree lines; historic features (e.g., structures, cellar holes, stone walls), and designated critical habitat, flood hazard and source protection areas;
 - j. the location (footprints) of existing and proposed structures, including all buildings, other structures, signs, and/or walls;
 - k. existing and proposed rights-of-way and easements,
 - l. existing and proposed roads, driveways, parking and loading areas, and pedestrian paths;
 - m. existing and proposed utility lines, water supply and wastewater disposal areas;
 - n. proposed site grading (cut and fill), stormwater management, and erosion control measures; and
 - o. proposed outdoor lighting, landscaping and screening.
- (5) Additional information as may be requested by the Development Review Board to determine conformance with these regulations, including one or more of the following
- a. elevation contours, at intervals to be specified by the Board;
 - b. existing and proposed structural elevations;
 - c. an “elevation certificate” as required under the National Flood Insurance Program for development within flood hazard areas;
 - d. stormwater, erosion control, lighting, landscaping, buffer, forest or wildlife management plans; and/or
 - e. traffic, visual, and fiscal impact assessments.
- (C) **Waivers.** The application will not be considered complete by the Development Review Board until all required materials have been submitted. One or more application requirements may be waived by the Board, at the request of the applicant, should the Board determine that the information is unnecessary for a comprehensive review of the application. Waivers shall be issued by the Board in writing at the time the application is accepted and deemed complete.
- (D) **Technical Review.** To assist in its evaluation of an application, the Board may require the submission of technical analysis of one or more aspects of a proposed development, prepared by a qualified professional, to be funded by the applicant.
- (E) **General Review Standards.** Conditional use approval shall be granted by the Development Review Board upon finding that the proposed development will not result in an undue adverse effect on any of the following:

- (1) **The capacity of existing or planned community facilities and services.** The Board shall consider the demand for community facilities and services that will result from the proposed development in relation to the existing and planned capacity of such facilities and services, and any adopted capital budget and program currently in effect. The Board may request information or testimony from other local officials to help evaluate potential impacts on community facilities and services. To minimize adverse impacts to community facilities and services, the Board may impose conditions as necessary on the provision of facilities, services or related improvements needed to serve the development, and/or the timing and phasing of development in relation to planned municipal capital expenditures or improvements.
 - (2) **Character of the area affected.** The Board shall consider the design, location, scale, and intensity of the proposed development in relation to the character of the neighborhood or area affected by the proposed development, as determined from zoning district purpose statements, municipal plan policies and recommendations, and evidence submitted in hearing. The Board may impose conditions as necessary to eliminate or mitigate adverse impacts to the area, neighboring properties and uses, including conditions on the design, scale, intensity, or operation of the proposed use.
 - (3) **Traffic on roads and highways in the vicinity.** The Board shall consider the potential impact of traffic generated by the proposed development on the function, capacity, safety, efficiency, and maintenance of roads, highways, intersections, bridges, and other transportation infrastructure in the vicinity of the project. The Board may request information or testimony from the Select Board, Road Commissioner or state officials to help evaluate potential impacts on town and state highways in the vicinity of the development. A traffic impact study also may be required to determine potential adverse impacts and appropriate mitigation measures. The Board may impose conditions as necessary to ensure that a proposed development will not result in unsafe conditions for pedestrians or motorists, including the installation of infrastructure improvements or accepted traffic management and control measures as required by the development.
 - (4) **Bylaws in effect.** The Board shall determine whether the proposed development conforms to other applicable municipal bylaws and ordinances currently in effect including, but not limited to, town road, health, and facility (e.g., sewer, water) ordinances. The Board shall not approve proposed development that does not meet the requirements of other municipal regulations in effect at the time of application.
 - (5) **The utilization of renewable energy resources.** The Board shall consider whether the proposed development will interfere with the sustainable use of renewable energy resources either by diminishing their future availability, or by interfering with access to such resources. Conditions may be imposed as necessary to ensure the long-term availability of, and continued access to, renewable energy resources.
- (F) **Specific Review Standards.** In addition to the general standards under Section (E), the Board may also consider and attach specific conditions to conditional use approval as appropriate to avoid, minimize or mitigate the adverse impacts of a proposed development, including:

- (1) **Siting & Dimensional Standards.** All conditional uses shall meet minimum applicable dimensional and density standards as specified for the district in which the use is located (Article 2), the particular use (Article 4), and for the protection of surface waters (Section 3.12). In addition, the Board may specify as a condition of approval lower densities of development, increased frontage or setback distances, increased buffer areas, and/or designated building envelopes that limit the area to be used for structures and parking, as necessary to avoid or minimize adverse impacts to the character of the area, to significant natural and historic resources identified in the town plan or through site investigation, or to adjoining properties and uses.
 - (2) **Performance Standards.** All conditional uses shall meet performance standards as specified in Section 3.11. In determining appropriate performance standards for a particular use, the Board may consult with state regulatory officials and consider accepted industry standards. In addition, the Board may limit the hours of operation so that the proposed use is compatible with the character of the neighborhood and area.
 - (3) **Access & Circulation Standards.** All conditional uses shall meet applicable access management standards as specified in Section 6.6. The Board, in consultation with the Select Board and state, may impose conditions as necessary to ensure the safety of vehicular and pedestrian traffic on and off-site, including but not limited to conditions on the location and number of access and intersection locations, requirements for shared access and/or parking, and provisions for emergency access, parking, service and loading area, snow storage, pedestrian paths and transit facilities (e.g., sheltered bus stops), as appropriate.
 - (4) **Landscaping & Screening Standards.** The Board may require landscaping, fencing, screening or site grading as necessary to maintain the character of the area, or to screen unsightly or incompatible uses from town highways, other public rights-of-way, or adjoining properties. Particular consideration will be given to the preservation of existing vegetation, visibility of the development from public vantage points (including roads), and the adequacy of landscaping and screening materials to meet seasonal weather and soil conditions. A landscaping management plan, and surety for up to three years that is acceptable to the Development Review Board, may be required to ensure that required landscaping and screening is properly installed and maintained.
 - (5) **Stormwater Management & Erosion Control Standards.** All conditional uses shall incorporate accepted stormwater management and erosion control practices as appropriate for the setting, scale and intensity of the existing and planned development. Development shall be sited and designed to minimize stormwater runoff and erosion during all phases of development. The Board may require the submission of a stormwater management and/or erosion control plan, prepared by a qualified professional, that incorporates accepted management practices recommended by the state in the Vermont Stormwater Management Manual and the Vermont Handbook for Soil Erosion and Sediment Control on Construction Sites, as most recently amended.
- (G) **District Standards.** In addition to district standards that pertain to all uses under Article 2, the following standards also shall apply to conditional uses within specified zoning districts:

- (1) **Central Business and Village Center Districts.** Within the Central Business District and the Village Center District, development shall be designed in accordance with the following standards:
 - a. The use of front yards shall be limited to landscaping, pedestrian paths and associated pedestrian amenities (e.g., street furniture, pedestrian scale lighting and signs) and driveways. Outdoor storage, parking and loading areas shall not be located within front yards unless the Board finds that the property is a pre-existing building or that no other practical alternative exists.
 - b. Buildings should be oriented toward and relate to, both functionally and visually, public streets and/or common greens, parks or plazas, and not be oriented toward parking lots. The front facade should include a main entry-way and pedestrian access to the street. Buildings located on corner lots shall either be oriented toward the major street or include a corner entrance. The Board may impose a maximum setback, relative to adjacent buildings, to achieve a consistent streetscape.
 - c. New buildings and additions to existing buildings shall be designed to be compatible with, and not stand in contrast to, historic structures located within the district with regard to building scale, massing, materials, orientation and rhythm of openings.
- (2) **Village Neighborhood District.** Within the Village Neighborhood District development shall be designed in accordance with the following standards:
 - a. The use of front yards shall be limited to landscaping, pedestrian paths and associated pedestrian amenities (e.g., street furniture, pedestrian scale lighting and signs) and driveways. Outdoor storage, parking and loading areas shall not be located within front yards unless the Board finds that the property is a pre-existing building or that no other practical alternative exists.
 - b. Buildings should be oriented toward and relate to, both functionally and visually, public streets and/or common greens, parks or plazas, and not be oriented toward parking lots. The front facade should include a main entry-way and pedestrian access to the street. The Board may impose a maximum setback, relative to adjacent buildings, to achieve a consistent streetscape.
 - c. The scale and massing of new buildings, including height, width, street frontage and roof type, shall be compatible and harmonious with surrounding residential structures. Consideration shall be given to buildings serving special civic, social or cultural functions, including places of worship, that may be designed to serve as prominent focal points within the district.
- (3) **Highway Mixed-Use District.** Within the Highway Mixed Use District, development with frontage on state highways (Route 15, Route 14, Route 16) shall be designed in a manner that meets the following standards:
 - a. Within and contiguous to parking areas, landscaping shall emphasize the use of shade trees to provide a tree canopy, provide separation between parking spaces to avoid large expanses of parking and minimize the visibility of parking areas from off-site. Suitable locations for shade trees include along walkways, in center islands, in between parking spaces and clustered in appropriate locations.

- b. A landscaped strip of at least twenty (20) feet shall be provided parallel to the road, which may be crossed by driveways and sidewalks. Form, location, and composition of the landscaped strip shall be shown on the site plan and approved by the Development Review Board.
- (4) **Rural Residential and Compact Residential Districts.** Within the Rural Residential and Compact Residential Districts, development shall be designed in accordance with the following standards:
- a. Development shall be designed to minimize loss of agricultural land and natural habitat, impact on water quality, and diminishment of the scenic and rural qualities of the site as experienced both on-site and from other vantage points in the Town.
 - b. Access roads, driveways and utility corridors shall be shared to the extent feasible; and, where sites include linear features such as existing roads, tree lines, stone walls, and/or fence lines, shall follow these features to the extent feasible in order to minimize the loss of productive agricultural and forest land, and to avoid physical and visual impacts.
- (5) **Forest Reserve District.** Development within the Forest District should not detract from the site’s scenic qualities, nor obstruct significant views from public vantage points, and should blend in with the existing landscape. Development shall take into consideration existing contours and forest cover to ensure that adequate opportunities exist for the siting and natural screening of development to minimize site disturbance and visual impacts. The Board may require the submission of a visual impact assessment for conditional uses within this district, and/or require additional screening of structures consistent with the natural and built environment.

Section 5.3 Flood Hazard Review [Table 2.9 Flood Hazard Area Overlay District]

- (A) **Applicability.** These regulations shall apply to the Special Flood Hazard Area in and on the most current flood insurance studies and maps published by the Department of Homeland Security, Federal Emergency Management Agency, National Flood Insurance Program, as provided by the Secretary of the Agency of Natural Resources pursuant to 10 V.S.A. Chapter 32 Section 753, which are hereby adopted by reference and declared to be part of these regulations. A permit is required from the Zoning Administrator for all development in all areas in the Special Flood Hazard Area as defined in Table 2.89 of these bylaws. Development that requires conditional use approval, non-conforming use approval, or a variance from the Development Review Board under these regulations must have such approvals prior to the issuance of a permit by the Zoning Administrator. Any development subject to municipal jurisdiction in the designated hazard areas shall meet the criteria of 5.3(G) and 5.3(H). Any permit issued will require that all other necessary permits from State and Federal Agencies have been received before work may begin.
- (B) **Warning of Disclaimer of Liability.** This bylaw does not imply that land outside of the areas covered by this bylaw will be free from flood damages. This regulation shall not create liability on the part of the Town of Hardwick, or any municipal official or employee thereof, for any flood damages that result from reliance on this regulation, or any administrative decision lawfully made hereunder.

- (C) **Permitted Development.** For the purposes of review under these regulations, the following development activities in the Special Flood Hazard Area where meeting the Development Standards in Sections 5.3(G), require only an administrative permit from the Zoning Administrator:
1. Non-substantial improvements to existing structures, outside of the Floodway
 2. Small accessory structures not greater than 500 square feet and outside of the Floodway;
 3. Development related to on-site septic or water supply systems;
 4. Building utilities;
 5. Bridges and culverts
 6. Channel Management
 7. Footbridges
 8. River and floodplain restoration project, outside of the Floodway, including dam removal, that restore natural and beneficial floodplain functions and include written information from the ANR Regional Floodplain Manager that the project is designed to meet the applicable standards in this bylaw.
 9. At-grade parking for existing buildings, outside of the Floodway;
 10. Recreational vehicles (parking of) outside of the Floodway; and
 11. New or replacement storage tanks for existing structures.
- (D) **Conditional Use Review.** Conditional use review and approval by the Development Review Board is required prior to the issuance of a permit by the Zoning Administrator for the following development activities:
1. Accessory structures larger than 500 square feet, outside of the Floodway.
 2. All other new structures, (including Accessory Dwelling Units) outside of the Floodway
 3. Substantial improvement, elevation, relocation, or flood proofing of existing structures;
 4. Non-Substantial improvements to existing structures in the Floodway;
 5. Grading, excavation; or the creation of a pond;
 6. Improvements to existing roads;
 7. Fill to elevate new and existing structures or for primary access.
 8. Public utilities;
 9. River and floodplain restoration projects in the Floodway, including dam removal, which restore natural and beneficial floodplain functions and include written information from the ANR Regional Floodplain Manager that the project is designed to meet the applicable standards in this bylaw.

- (E) **Application.** An application for development shall include:
- (1) Where applicable, a site plan that depicts the proposed development, all water bodies, Special Flood Hazard Areas, floodways, any existing and proposed drainage, any proposed fill, and pre and post development grades, and the elevation of the proposed lowest floor, as referenced to the same vertical datum as the elevation on the current Flood Insurance Rate Maps;
 - (2) A Vermont Agency of Natural Resources Project Review Sheet shall identify all State and Federal agencies from which permit approval is required for the proposal, and shall be filed as a required attachment to the municipal permit application. The identified permits, or letters indicating that such permits are not required, shall be submitted to the Zoning Administrator and attached to the permit before work can begin.
- (F) **Referrals.**
1. Any application regarding New Construction, Substantial Improvement, development in a Floodway, or a Variance shall be submitted by the Zoning Administrator to the State National Flood Insurance Program (NFIP) Coordinator at the Vermont Agency of Natural Resources in accordance with 24 V.S.A. §4424. A permit may be issued only following receipt of comments from the Agency, or the expiration of 30 days from the date the application was mailed to the Agency, whichever is sooner.
 2. If the applicant is seeking a permit for the alteration or relocation of a watercourse, copies of the application shall also be submitted to the adjacent communities, the Stream Alteration Engineer at the Vermont Agency of Natural Resources, and the Army Corps of Engineers. Copies of such notice shall be provided to the State National Flood Insurance Program (NFIP) Coordinator at the Vermont Agency of Natural Resources, Department of Environmental Conservation. A permit may be issued only following receipt of comments from the Vermont Agency of Natural Resources, or the expiration of 30 days from the date the application was mailed to the Vermont Agency of Natural Resources, whichever is sooner. The Board should consider comments from the NFIP Coordinator at ANR.
- (G) **Development Standards – Special Flood Hazard Area.**
- (1) All development below the Design Flood Elevation (DFE), except development that is exempt under Table ~~2-82.9~~ shall be:
 - a. reasonably safe from flooding;
 - b. designed, operated, maintained, modified, and adequately anchored to prevent flotation, collapse, or lateral movement of the structure;
 - c. constructed with materials resistant to flood damage;
 - d. constructed by methods and practices that minimize flood damage;
 - e. constructed with electrical, heating, ventilation, plumbing and air conditioning equipment and other service facilities that are designed and/or located so as to prevent water from entering or accumulating within the components during conditions of flooding;

- f. adequately drained to reduce exposure to flood hazards;
 - g. require any fuel storage tanks and vents to be elevated above the DFE and be securely anchored to prevent flotation. Storage tanks may be placed underground if a qualified professional certifies the installation will be anchored and protected from flood forces.
- (2) In Zones AE, AH, and A1-30, where floodway limits have not been determined, development shall not be permitted unless it is demonstrated that the cumulative effect of the proposed development, when combined with all other existing and anticipated encroachment, will not increase the base flood elevation by more than 1.00 foot at any point within the community. The demonstration must be supported by technical data that conforms to standard hydraulic engineering principles and certified by a registered professional engineer.
 - (3) All new or substantially improved structures in Zones A, A1-30, AE, and AH shall be located such that the lowest floor is, including the basement, elevated to or above the Design Flood Elevation (two feet above base flood elevation). This shall be documented, in the proposed and as-built condition, with a FEMA Elevation Certificate.
 - (4) New or substantially improved non-residential structures shall:
 - a. Meet the standards in 5.3(G)(3); or,
 - b. Have the lowest floor, including basement, together with attendant utility and sanitary facilities, designed so that at least two feet above the base flood elevation of the structure is dry floodproofed, meaning watertight with walls substantially impermeable to the passage of water and with structural components having the capability of resisting hydrostatic and hydrodynamic loads and effects of buoyancy.
 - c. A permit for dry floodproofing shall not be issued until a registered professional engineer or architect has reviewed the structural design, specifications and plans, and has certified that the design and proposed methods of construction are in accordance with accepted standards of practice for meeting the provisions of this subsection.
 - (5) Fully enclosed areas below grade on all sides (including below grade crawlspaces and basements) are prohibited.
 - (6) Fully enclosed areas that are above grade, below the lowest floor, below the Design Flood Elevation, that are subject to flooding shall:
 - a. be solely used for parking of vehicles, storage, or building access, and such condition shall be clearly stated on any permits; and be designed to automatically equalize hydrostatic flood forces on exterior walls by allowing for the entry and exit of floodwaters. Such designs must be certified by a registered engineer or architect; or
 - b. meet or exceed the following minimum criteria: a minimum of two openings on two walls having a total net area of not less than one square inch for every square foot of enclosed area subject to flooding shall be provided. The bottom of all openings shall be no higher than one foot above adjacent grade. Openings may be

equipped with screens, louvers, valves or other cover coverings or devices provided that they permit the automatic entry and exit of floodwaters.

- (7) Recreational Vehicles or job site trailers placed on sites within Zones A1-A30, AH and AE, shall either (1) be on the site for fewer than 180 consecutive days, (2) be fully licensed and ready for highway use, or (3) meet all standards of Section 60.3(b)(1) of the National Flood Insurance Program Regulations and the elevation and anchoring requirements for “manufactured homes” of Section 60.3(c)(6).
- (8) Accessory Structures: A small accessory structure of 500 square feet or less that represents a minimal investment need not be elevated to the base flood elevation if adequate flood openings are provided, the structure is placed on the site so as to offer the minimum resistance to the flow of floodwaters, and the construction meets the criteria of 5.3(G)(6).
- (9) New and replacement water supply and sanitary sewage systems shall be designed to minimize or eliminate the infiltration of flood waters into the systems and discharges from the systems into flood waters.
- (10) On-site waste disposal systems shall be located to avoid impairment to them or contamination from them during flooding.
- (11) The flood carrying and sediment transport capacity within any altered or relocated portion of a watercourse shall be maintained, and any alteration or relocation shall not result in any decrease of stream equilibrium.
- (12) Bridges and culverts and channel management activities, which by their nature must be placed in or over the watercourse, must have a stream alteration permit from the Agency of Natural Resources if applicable.
- (13) Subdivisions and planned unit developments must be accessible by dry land access.
- (14) New and replacement manufactured homes shall be elevated or placed on a permanent foundation so that the lowest floor is elevated to or above the Design Flood Elevation (two feet above a base flood elevation). This shall be documented in the proposed and as-built condition with a FEMA Elevation Certificate.
- (15) Critical Facilities to be substantially improved shall have the lowest floor, including basement, elevated or dry-floodproofed at least one foot above the elevation of the 0.2% annual flood height (500-year floodplain), or three feet above base flood elevation, whichever is higher;
- (16) No net loss of flood storage capacity,
 - a, Except as needed to fill an existing basement or mitigate an existing structure.

(H) Development Standards – Floodway Areas

- (1) Within the Floodway new encroachments are prohibited except for the following, which shall also comply with Section 2 below:
 - a. changes to existing structures where the footprint is proposed to expand horizontally into the Floodway less than 500 square feet;
 - b. new encroachments relating to bridges, culverts, roads, stabilization projects, public utilities, functionally dependent uses, and river and floodplain restoration

Formatted: Font: Bold

Formatted: Subsection-indent

projects;

- c. new encroachments relating to health and safety measures, such as replacement of pre-existing on-site septic and water supply systems, if other practical alternatives are not available.
- (2) Within the Floodway all proposed new encroachments are required to provide a hydraulic analysis, performed by a registered professional engineer, in accordance with standard engineering practice, certifying that the proposed development will:
 - a. not result in any increase in flood levels during the occurrence of the base flood;
 - b. not increase base flood velocities; and,
 - c. not increase any risk to surrounding properties, facilities, or structures from erosion or flooding.
- (3) For development that will not result in any change in grade, the hydrologic and hydraulic analyses may be waived, where the applicant will provide pre- and post-development elevations demonstrating that there will be no change in grade, and that the development will be adequately protected from scour.

(I) **Nonconforming Structures and Uses.**

The Development Review Board may, after public notice and hearing, approve the repair, relocation, replacement, or enlargement of a nonconforming structure within a flood hazard area but outside of the Floodway provided that:

- (1) The proposed development is in compliance with all the Development Standards in Section 5.3(G)-(H) of this bylaw;
- (2) A nonconforming structure that is substantially damaged or destroyed may be reconstructed only in circumstances when the structure cannot be relocated to a less hazardous location on the parcel. The lowest floor of the reconstructed structure must be rebuilt to or above the Design Flood Elevation (two feet above a base flood elevation). This shall be documented in the proposed and as-built condition with a FEMA Elevation Certificate. The structure must otherwise comply with all requirements of the National Flood Insurance Program; and
- (3) An individual manufactured home lot in an existing manufactured home park that is vacated shall not be considered a discontinuance or abandonment of nonconformity. Replacement manufactured homes must be placed so as to meet the development standards in this bylaw.

Formatted: Subsection-indent Char, Font: Not Bold

Section 5.4 River Corridor Protection [Table 2.10 River Corridor Overlay District]

(A) Purpose

River corridors provide rivers and stream channels with the space necessary to maintain or reestablish floodplain access and to reduce erosion hazards through natural physical processes. It is the intent of this bylaw to protect public health and safety by avoiding new encroachments into river corridors and minimizing erosion-related damage to existing structures.

Formatted: Section

Formatted: Font: Bold

Formatted: Font: Bold

A permit is required from the AO for all development that is located within the River Corridor except as provided in Section 5.4 C.1. Where River Corridors and Flood Hazard Areas overlap, the Flood Hazard Area provisions shall also apply.

(B.) River Corridor Boundaries

1. This article applies to the River Corridors in the Town of Hardwick, Vermont, as published by the Agency of Natural Resources (ANR) including refinements to that data which are hereby adopted by reference.
2. On streams with a watershed size greater than half a square mile for which River Corridors are not mapped, the standards shall apply to the area measured as 50 feet from the top of the stream bank or slope.
3. The information presented on any maps, or contained in any studies adopted by reference, is presumed accurate. If uncertainty exists with respect to the boundaries of the River Corridor, the location of the boundary on the property shall be determined by the Administrative Officer (AO).
4. If the applicant disagrees with the determination made by the AO or with the river corridor as mapped, the applicant has the option to either:
 - a. Hire a licensed land surveyor or registered professional engineer to stake out the River Corridor boundary as mapped on the property; or,
 - b. Provide data as needed for ANR to update the river corridor map following the Flood Hazard Area and River Corridor Protection Procedure (“Procedure”); or
 - c. Request a letter of determination from ANR that the proposed development meets the Performance standard in the Procedure.

Formatted: Font: Bold

Formatted: Font: Bold

C. Development Review in River Corridors

1. Exempted Activities

The following activities do not require a permit under this section of the bylaw:

- a. The removal of a building or other improvement in whole or in part, so long as the ground elevations under and adjacent to the removed structure remains unchanged;
- b. Any changes to a structure that will not change the footprint of the structure;
- c. Maintenance of existing sidewalks, roads, parking areas, stormwater drainage, bridges, culverts, and channel stabilization;
- d. Functionally dependent uses that must be placed in or cross over rivers and streams, that are not located in a flood hazard area, and that have coverage under a Stream Alteration Permit, if required, under 10 V.S.A. Chapter 41 and the rules adopted thereunder including the construction, removal, or repair of bridges and culverts, associated transportation and utility networks, dams, and dry hydrants;
- e. Planting projects which do not include any construction or grading;
- f. Subdivision of land that does not involve or authorize development;
- g. Open Space;
- h. Activities exempt from municipal regulation and requiring a permit from ANR

Formatted: Font: Bold

Formatted: Font: Bold

Formatted: Font: Bold

Formatted: Sub-Subsection, Indent: Left: 0"

under the Vermont Flood Hazard Area and River Corridor Rule (CVR 12-030-024) including:

- i. State-owned and operated institutions and facilities;
- ii. Forestry operations or silvicultural (forestry) activities conducted in accordance with the Vermont Department of Forests and Parks Acceptable Management Practices for Maintaining Water Quality on Logging Jobs in Vermont or other accepted silvicultural practices, as defined by the Commissioner of Forests, Parks and Recreation;
- iii. Agricultural activities conducted in accordance with the Vermont Agency of Agriculture, Food and Market's Required Agricultural Practices (RAPs). Prior to the construction of farm structures, the farmer shall notify the AO in writing of the proposed activity. The notice shall contain a sketch of the proposed structure including setbacks;
- iv. Public utilities regulated under 30 V.S.A. § 248;
- v. Telecommunications facilities regulated under 30 V.S.A. § 248a;

Formatted: Indent: First line: 0.5"

Formatted: Indent: Left: 1.5"

2. Prohibited Development in the River Corridor

- a. Cemeteries
- b. Critical Facilities
- c. Fill for any purpose other than elevating structures or primary access
- d. Natural Burial Ground
- e. Private Family Cemetery
- f. Salvage Yards
- g. Storage Facilities

Formatted: Indent: First line: 0.38"

Formatted: Font: Bold

Formatted: Indent: Left: 0.38", First line: 0.5"

3. Permitted by Administrative Review

The following development activities meeting the Development Standards in the River Corridor in Section 5.4 D1 or 2, may be permitted directly by the AO:

- a. Small accessory structures not greater than 500 square feet;
- b. Improvements to existing structures that will change the footprint of the structure.
- c. Building Utilities;
- d. Parking, at grade
- e. Recreational vehicles, (parking of)
- f. Replacement of water supply or septic systems
- g. An attached deck or patio to an existing structure that is 200 square feet or less and is located no less than 100 feet from the top of bank;
- h. Unimproved trails on native grades and soils that will be relocated as needed to accommodate channel adjustments and avoid degradation to bank stability and riparian habitat;
- i. River or floodplain restoration projects that do not involve fill, structures, utilities, or other improvements, and which have written confirmation from the ANR Regional Floodplain Manager that the project is designed to meet or exceed the applicable standards in this bylaw;

Formatted: Font: Bold

Formatted: Sub-Subsection, Indent: First line: 0.38"

Formatted: Sub-Subsection

Formatted: List Paragraph, Numbered + Level: 1 + Numbering Style: a, b, c, ... + Start at: 1 + Alignment: Left + Aligned at: 0.88" + Indent at: 1.13"

Formatted: Indent: Left: 0.88"

4. Conditional Use Review

Conditional use review and approval by the DRB in accordance with 24 V.S.A. § 4461 is

Formatted: Indent: First line: 0.5"

Formatted: Font: Bold

Formatted: Indent: Left: 0.5"

required prior to the issuance of a permit by the AO for any activity in the River Corridor that is not exempt, prohibited, or eligible for administrative review. In particular,

- a. Accessory Structures larger than 500 square feet
- b. All other new structures (including Accessory Dwelling Units)
- c. Storage (See Definition)
- d. Grading, excavation, or the creation of a pond
- e. Road Improvements

Formatted: List Paragraph, Numbered + Level: 1 + Numbering Style: a, b, c, ... + Start at: 1 + Alignment: Left + Aligned at: 0.81" + Indent at: 1.06"


D. Development Standards within the River Corridor

Formatted: Font: Bold

These are the minimum standards for development in the River Corridor. Where more than one district is involved, the most restrictive standard shall take precedence.

Formatted: Subsection-indent

1. In-Fill: Development must be located no closer to the top of bank than the existing primary structures, within a gap that is no more than 300 feet (see Figure 1), or



Formatted: Sub-Subsection Char, Font: Not Bold, Check spelling and grammar

Formatted: List Paragraph, Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"

2. Down River Shadow: An addition to an existing habitable structure, or an accessory structure that is adjacent to an existing structure, shall be located in the shadow area directly behind and further from the channel than the existing structure, or within 50 feet to the downstream side and no closer to the top of bank. Below-ground utilities may also be placed within the same shadow dimensions of an existing below-ground system (see Figure 2). Only primary structures existing before this bylaw may be considered for shadowing other development.


Formatted: Sub-Subsection Char, Font: Not Bold

Formatted: Indent: Left: 0.25"

Formatted: Font: Bold

Formatted: List Paragraph, Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"

Figure 1: In-fill Development Standard



Formatted: Indent: Left: 0.5", No bullets or numbering

Formatted: List Paragraph

Formatted: Indent: First line: 0.25"

Formatted: Indent: Left: 0.25"

3. River Corridor Performance Standard

Proposals that do not meet the infill or shadowing criteria in section D. 1 or 2 must demonstrate, and the DRB must find, that the proposed development will:

- a. not be placed on land with a history of fluvial erosion damage or threatened by fluvial erosion; and,
- b. not cause the river reach to depart from or further depart from the channel width, depth, meander pattern, and slope associated with natural stream processes and equilibrium conditions; and,
- c. not result in a need for bank armoring or stream channelization as a result of the proposed development, that would increase flood elevations and velocities, or alter the

Formatted: List Paragraph, Indent: Left:

sediment regime triggering channel adjustments and erosion in adjacent and downstream locations.

4. The DRB may request or consider additional information to determine if the proposal meets the River Corridor Performance Standard, including data and analysis from a consultant qualified in the evaluation of river dynamics and erosion hazards; and comments provided by the DEC Regional Floodplain Manager on whether the proposal meets the River Corridor Performance Standard.

Formatted: Indent: Left: 0.25"

5. New paths or alterations to paths that provide access to the water for the public, and promote the public trust uses of the water, shall not necessitate bank armoring, and must be relocated when the channel adjusts toward the path.

Formatted: List Paragraph

Formatted: Indent: Left: 0.5", First line: 0"

Section 5.54 Planned Unit Development

- (A) **Applicability.** Planned Unit Development (PUD) review procedures and standards may be applied by the Development Review Board at the request of the applicant for any parcel which meets the minimum lot size for the district within which it is located.
- (B) **Purpose.** In accordance with the Act §4417, PUDs are permitted in all zoning districts to allow for innovative and flexible design and development that will promote the most appropriate use of land, and specifically achieve one or more of the following objectives:
- (1) increase density, reduce lot size and/or facilitate the adequate and economical provision of streets and utilities to provide housing in a cost-effective manner;
 - (2) cluster residential development to preserve and maintain open space;
 - (3) protect significant natural, cultural or scenic features as identified in the Hardwick Town Plan, or through site investigation; and/or,
 - (4) allow for creative design and layout of development, an efficient use of land, and to provide for the integrated mix of housing types.
- (C) **Review Procedure.**
- (1) A proposed PUD that requires a subdivision of land shall be reviewed as a Major Subdivision Review as set forth in Section 6.3. Nevertheless, review and approval of a PUD involving the development of one or more conditional uses under this Section shall not exempt the proposed development from review under Section 5.2. The Development Review Board may review and approve one or more conditional uses concurrently with granting PUD approval, or may require the submission of a conditional use application subsequent to PUD approval.
 - (2) A proposed PUD that requires no subdivision of land shall be reviewed as a conditional use, as set forth in Section 5.2.
 - (3) In addition to the application requirements specified under Section 6.3 or 5.2, an application for PUD approval shall include a statement describing all proposed modifications, changes or supplements to existing bylaw requirements. Modifications of these bylaws approved by the Development Review Board shall be noted in writing and appended to a plat depicting the project to be filed in the Hardwick Land Records. All other provisions of these bylaws not specifically

modified shall remain in effect and be applicable to the project.

(D) **General Standards.** The modification of zoning regulations by the Development Review Board may be permitted in accordance with the following standards:

- (1) The PUD shall be consistent with the Hardwick Town Plan and all other applicable municipal regulations and ordinances currently in effect. The PUD shall also meet all local and state regulations for sewage disposal and the protection of water quality.
- (2) The PUD shall represent an effective and unified treatment of the development site, including provisions as appropriate for the preservation or protection of surface and ground waters; wetland, stream bank, floodplain and lake shore areas; significant topographic features, including hilltops and ridgelines; areas of steep slope or shallow soil; significant resource lands, including agricultural and forest land; historic or archaeological sites and structures; natural and critical habitat areas; and open spaces, including scenic views and vistas.
- (3) The Development Review Board may allow for a greater concentration or intensity of development within some section(s) of the development than in others, on individual lots which are smaller than the minimum lot size for the district within which the PUD is located, provided that there is an offset by a lesser concentration in other sections, including the reservation of no less than 50% of the remaining land as open space.
- (4) The minimum front, side and rear yard setbacks at the periphery of the PUD shall be as dictated for the particular district unless otherwise specified by the Development Review Board. The Board may allow other setback standards, such as zero setbacks from lot lines, as part of PUD approval.
- (5) Provision shall be made for the preservation of open space. Preserved open space shall be dedicated, either in fee or through a conservation easement to the Town, a community association comprising all of the present and future owners of lots or dwellings in the project, or a non-profit land conservation organization. The Development Review Board shall approve such easement. Preserved open space may remain in single ownership, subject to easement conditions and appropriate land management (e.g., forestry, agriculture). Land held in common shall be subject to appropriate deed restrictions stipulating the permitted and restricted use of such lot, and establishing the person or entity responsible for maintenance and long term stewardship. The Board shall approve the location, size and shape of lands set aside to be preserved for open space in accordance with the following:
 - a. Open space land shall provide for the protection of identified resources, including farmland, productive forest, wildlife habitat, natural areas, aquifer protection areas, surface waters, stream banks, historic and archaeological sites, and scenic views and vistas;
 - b. Designated open space may include the portion of a single lot which is characterized by one or more of the above referenced features, or may encompass the contiguous boundaries of the above referenced feature located on multiple lots;
 - c. The location, shape, size and character of the open space shall be suitable for its

intended use. Generally, open space shall be at least 50% of the total area for projects involving a parcel(s) of twenty-five (25) acres or more. For smaller parcels, open space should be in proportion to the size and scope of the project, and its intended use;

- d. Open space shall be suitably improved and/or maintained for its intended use, except for open space containing natural or cultural resources worthy of preservation that may be required to be left unimproved. Provisions shall be made to enable lands designated for agriculture and forestry to be used for these purposes. The Board as appropriate may require management plans for forests and/or wildlife habitat;
- e. Open space land shall be located so as to conform with and extend existing and potential open space lands on adjacent parcels; and
- f. Sewage disposal areas and utility and road rights-of-way or easements, access and parking areas shall not be counted as open space areas, except where the applicant can prove, to the satisfaction of the Board, that they will in no way disrupt or detract from the values for which the open space is to be protected.

(6) The total number of dwelling units shall not exceed that which would be permitted in the Development Review Board's judgment if the parcel were subdivided into buildable lots in conformance with the district minimum lot area required for single ~~unit family~~ dwellings. However, the number of dwelling units allowed in a PUD may, at the discretion of the Development Review Board, be increased in accordance with the following:

- a. The Board may grant a density increase of up to 25% of the allowable number of units in instances in which a significant portion (50% or greater) of the site is preserved as open space and/or the Board determines that the PUD reflects an exceptional site design that will result in the preservation of important natural resources and the creation such amenities as pedestrian paths, parkland and/or playgrounds; or
- b. The Board may grant a density increase of up to 50% of the allowable number of units in instances in which not less than 50% of the total number of dwelling units created are affordable housing units, as defined in Article 8.

(7) Where a district boundary line divides a parcel, the Development Review Board may allow the development of a single PUD with a total density based on the combined allowable density of each district.

(8) Two (2) or more contiguous parcels under the ownership or control of the applicant may be combined for review as a PUD. The permitted density on one parcel may be increased as long as the overall density for the combined parcels does not exceed that which could be permitted, in the Development Review Board's judgment, if the land were subdivided into lots in conformance with district regulations.

(9) A PUD shall include only residential uses and associated accessory structures and uses allowed within the district in which the PUD is located. The dwelling units permitted may, at the discretion of the Development Review Board, be of varied types, including single-~~unitfamily~~, two-~~unitfamily~~, or multi-~~unitfamily~~ construction, and may be attached or detached.

- (E) **District Standards.** Within the Rural Residential and Forest Reserve Districts, dwellings may be comprised of one or more state licensed residential care home serving not more than 6 persons who are developmentally disabled or handicapped, and such dwellings may be clustered so that they are located within 1,000 feet of each other in accordance with the standards set forth in this Section and the approval of the Development Review Board under Section 5.2.

Section 5.5 — Local Act 250 Review

- ~~(A) — **Applicability.** In according with 24 V.S.A. §4420, the Development Review Board is hereby authorized to undertake local Act 250 review of municipal impacts of all Act 250 permits in the Town of Hardwick unless ALL of the following conditions apply:~~
- ~~(1) — The applicant can establish to the satisfaction of the Development Review Board that the applicant relied on a determination by the Natural Resource's Board local district coordinator that Act 250 jurisdiction did not apply to the development in question and, based on that reliance, the applicant obtained local permits without complying with the requirement for local Act 250 review.~~
 - ~~(2) — The Natural Resource Board's local district coordinator's jurisdictional ruling was later reconsidered or overturned on appeal, with the result that Act 250 jurisdiction does apply to development in question.~~
 - ~~(3) — The Development Review Board waives its local Act 250 review jurisdiction in the interest of fairness to the applicant. Determination by the Development Review Board to waive local Act 250 review jurisdiction shall not be subject to review.~~
- ~~(B) — **MAPA.** The Development Review Board shall hear applications for local Act 250 review of municipal impacts at a public hearing warned in accordance with Section 7.6(C) and pursuant to the procedures established under 24 V.S.A. Chapter 36 (the Municipal Administrative Procedures Act).~~
- ~~(C) — **Review Criteria.** At the Development Review Board's local Act 250 hearing, the applicant shall provide, at the minimum, all of the information related to Act 250 Criteria 6, 7, and 10, and shall demonstrate to the satisfaction of the DRB that the proposed development:~~
- ~~(1) — will not cause an unreasonable burden on the ability of the Town of Hardwick to provide educational services (criterion 6);~~
 - ~~(2) — will not cause an unreasonable burden on the ability of the Town of Hardwick to provide municipal or governmental services (criterion 7); and~~
 - ~~(3) — is in conformance with the duly adopted Town Plan (criterion 10).~~

Section 5.6_ Review Procedures

At the time an application is deemed complete, the Development Review Board shall schedule a public hearing, warned in accordance with Section 7.6(C). The Board may recess the hearing (adjourn to a time and date) as needed to allow for the submission of testimony and evidence by the applicant or other interested parties. The Board shall act to approve, approve with conditions, or deny an application within 45 days of the date of adjournment of the final public hearing. The written decision shall include findings, any conditions of approval or reasons for denial, and provisions for appeal to the Environmental Court. The failure of the Board to act within this 45 day period shall be deemed and shall be effective on the 46th day.

ARTICLE 6. SUBDIVISION REVIEW

Section 6.1 Applicability

(A) Whenever any subdivision of land is proposed, subdivision review and approval is required prior to:

- conveying or leasing of a subdivided parcel,
- grading, clearing, construction or installation of subdivision site improvements,
- applying for a zoning permit for the development of any subdivided parcel, or
- filing a subdivision plat in the land records of the town.

Subdivision of Land: The division of any parcel of land into two or more parcels for the purpose of sale, transfer, lease or development. The term includes the resubdivision of a previously subdivided parcel, and the development of a parcel as a planned residential development.

Formatted: Font: Not Bold

Such approval shall be granted by the Zoning Administrator or Development Review Board in accordance with the procedures and standards set forth below.

(B) **Exemptions.** The following are specifically exempted from subdivision review under this article:

- (1) parcels leased for agricultural or forestry purposes where no permanent roads or structures are established,
- (2) rights-of-way or easements which do not result in the subdivision of land, and
- (3) boundary adjustments between existing parcels which do not create new or nonconforming lots.

(C) **Minor & Major Subdivisions.** For the purposes of these regulations, subdivisions of land are defined as “minor” or “major” subdivisions, as follows:

- (1) **Minor subdivisions**, to be reviewed by the Zoning Administrator under Section 6.2 include:
 - a. the subdivision of land, or the resubdivision of a previously subdivided parcel, which results in the creation of a total of three or fewer lots within any five year period, regardless of any change in ownership; or
 - b. an amendment to an approved subdivision which does not substantially alter the subdivision, nor result in the creation of a major subdivision.
- (2) **Major subdivisions**, to be reviewed by the Development Review Board under Section 6.3 include:
 - a. the subdivision of land, or the resubdivision of a previously subdivided parcel (e.g., a minor subdivision) which results in the creation of a total of four or more lots within any five year period and/or involves the construction of a new road;
 - b. an amendment to an approved subdivision which substantially alters the subdivision or conditions of approval, or which results in the creation of a major subdivision or a new road;

- c. a planned unit development; and
- d. the creation of a lot which does not meet minimum frontage or access requirements, which is subject to approval under Section 3.3.

(D) **Coordination with Planned Unit Development Review.** Applications for planned unit developments (PUDs) shall be reviewed concurrently by the Development Review Board as major subdivisions in accordance with Section 6.3 and associated PUD requirements under Article ~~5.55-4~~.

Section 6.2 Minor Subdivision Review

- (A) **Zoning Permit Requirement.** A zoning permit issued by the Zoning Administrator in accordance with Section 7.1 is required for all minor subdivisions. The zoning permit issued for a minor subdivision under these regulations shall be separate from the zoning permit issued for the subsequent development of a subdivided parcel, and shall be identified as such; however zoning permits may be issued by the Zoning Administrator concurrently for the minor subdivision of land, and for the subsequent development of a subdivided parcel. Development Review Board
- (B) **Review Criteria.** The zoning permit application for a minor subdivision shall include information required for sketch plans, as specified in Table 6.1. The Zoning Administrator shall review the sketch plan to determine whether all proposed lots, including any retained lot, comply with applicable lot size, setback, and access requirements under these regulations.

TABLE 6.1 SUBDIVISION APPLICATION REQUIREMENTS

| (A) Application Information | Sketch | Final |
|---|--------------------------|--------------------------------------|
| Application Form [number of copies] | One [original] | Three [2 copies] |
| Application Fee [to be set by Select Board] | | Y |
| Name of project, if any | Y | Y |
| Name, address of applicant [landowner and/or subdivider] | Y | Y |
| Written description of proposed development plans, including: Number and size of lots, intended use, general timing of development | Y | Y |
| Waiver request, in writing [optional] | Y | |
| (B) Plan/Plat Mapping Requirements | Sketch | Final Plat |
| Material | Paper | Mylar |
| Preparer Information, Certifications | | Y |
| Scale | To scale noted | Min. 1" = 100' |
| Date, North Arrow, Legend | Y | Y |
| Project boundaries and property lines; | Drawn | Surveyed |
| Existing and proposed lot lines, dimensions | Drawn | Surveyed |
| Adjoining land uses, roads and drainage | Y | Y |
| Zoning district designations and boundaries | Y | Y |
| The location of natural and physical features located on the site, including buildings; roads, driveways and parking areas; fences and walls; watercourses; wetlands; areas of slope in excess of 20%; and a general indication of land cover, including forested areas and land in current or recent (prior 3 years) agricultural production | Y [General Locations] | Y [Specifically Delineated Areas] |
| Existing and proposed elevations, contour lines within 50 feet of any proposed excavation/grading | | 5' interval |
| Existing and proposed roads, paths, common or shared parking areas, associated rights-of-way or easements | Drawn | Surveyed |
| Proposed building envelopes (if required) | | Y |
| Proposed utilities, water and wastewater systems and associated rights-of-way or easements | Y | Y |
| Road profiles; road, intersection and parking area geometry and construction schematics | | Y |
| Proposed landscaping and screening | | Y |
| Proposed conservation buffer and/or open space easement areas | | Y |
| Monument locations | | Y |
| (C) Supporting Information & Documentation | Sketch | Final |
| Site location map showing proposed subdivision in relation to major roads, drainage ways, and adjoining properties | Y | Y |
| Statement of compliance with town plan and applicable local regulations | Y | Y |

| | | |
|--|-------------|---|
| Engineering reports (water and wastewater systems) | Y | Y |
| Existing and proposed traffic generation rates, volumes | | Documented |
| Off-site easements (e.g., for water, wastewater, access) | Description | Final |
| Proposed phasing schedule | Description | Final |
| Proposed covenants and/or deed restrictions | Description | Final |
| Proposed homeowner or tenant association or agreements | Description | Final |
| Proposed performance bond or surety | | Final |
| (D) As may be required by the Development Review Board | | |
| Stormwater and erosion control plan | | As required under sketch plan or preliminary approval |
| Grading plan (showing proposed areas of cut and fill) | | |
| Open space management plan | | |
| Site reclamation plan (for subdivisions involving extraction) | | |
| Traffic impact analysis (current and proposed traffic volumes, capacities, levels of service, proposed improvements) | | |
| Fiscal impact analysis (analysis of fiscal costs and benefits to the town) | | |
| Historic or archeological assessment | | |
| Environmental impact assessment (analysis of potential environmental impacts, proposed mitigation measures) | | |
| Other | | |

Section 6.3 Major Subdivision Review

- (A) **Subdivision Approval Requirement.** The Development Review Board shall review all major subdivisions. Subdivision approval, rather than a zoning permit, shall be required for a major subdivision. An application for subdivision approval shall be made on forms provided by the Board and filed with the Development Review Board Secretary.
- (B) **Waiver Authority.** Pursuant to the Act [§4418] the Development Review Board may waive application requirements as specified in Table 6.1, or subdivision standards under Sections 6.5, 6.6 and/or 6.7 which, in its judgment:
 - (1) are not requisite in the interest of public health, safety, and general welfare;
 - (2) are inappropriate due to the inadequacy or lack of connecting facilities adjacent to or in proximity to the subdivision; or
 - (3) would unnecessarily add to the cost of an affordable housing development as defined in Article 8.2.

The request for a waiver shall be submitted in writing by the applicant with the subdivision application. It shall be the responsibility of the applicant to provide sufficient information to justify the waiver or variance, and enable the Development Review Board to reach a decision. In granting waivers, the Board may require such conditions that will, in its judgment, substantially meet the objectives of the requirements so waived or varied. No such waiver may be granted if it would have the effect of nullifying the intent and purpose of these regulations or other municipal ordinances or regulations currently in effect.

- (C) **Sketch Plan Review.** Prior to the submission of an application for major subdivision review, the applicant may submit a sketch plan to the Development Review Board

Secretary for consideration by the Board at a regularly scheduled Board meeting. Sketch plan review is strongly recommended for all planned unit developments.

- (1) **Purpose.** The purpose of sketch plan review is to acquaint the Development Review Board with the proposed subdivision at an early stage in the design process, prior to the applicant incurring significant expense. Sketch plan review is intended to allow for an informal exchange of ideas, in which the applicant explores with the Board subdivision design options that best meet the needs of the applicant and the requirements of these regulations.
 - (2) **Submission Requirements.** One original and seven copies of the sketch plan, to include information specified in Table 6.1, should be submitted to the Development Review Board at least 15 days prior to a regularly scheduled commission meeting.
 - (3) **Effect.** The Development Review Board may offer comments and recommendations at the meeting or, within 30 days of the date of the meeting, provide comments and recommendations to the applicant in writing. Such comments are advisory and as such shall not constitute an appealable decision or action of the Development Review Board, and shall not be binding on subsequent subdivision review.
- (D) **Subdivision Review [Required].** The application for major subdivision review shall include one original and seven copies of the information for subdivision plan approval specified in Table 6.1, and any required fees. The application must also include, in writing, any requested waivers to be considered under Subsection (B) and the reasons for such waivers. The Development Review Board shall consider the application in accordance with the following:
- (1) **Public Hearing.** As required by the Act [§4463] within 45 days of the date submission of a complete application for major subdivision approval, the Development Review Board shall hold a public hearing on the application, warned in accordance with Section 7.6. In the event that the subdivision is located within 500 feet of a municipal boundary, copies of the hearing notice also shall be sent, at least 15 days prior to the hearing date, to the clerk of an adjacent municipality. After the hearing is convened the Development Review Board may continue the hearing as needed to request and allow for the submission of additional information or studies to determine conformance with these regulations.
 - (2) **Final Approval.** As required by the Act [§4463], within 45 days of the date of adjournment of the public hearing, the Development Review Board shall approve, approve with conditions or disapprove the subdivision plan and associated plat, based on a determination of the subdivision's conformance with review standards under Sections 6.5, 6.6 and 6.7.
 - (3) **Performance Bonding.** For any subdivision that includes the construction of roads or other physical improvements, the Development Review Board may require the subdivider to post a performance bond or other comparable surety to ensure completion of the improvements in accordance with approved specifications. In accordance with the Act [§4464(b)(6)], the term of a performance bond shall be fixed by the Development Review Board for a period not to exceed three years, unless with the consent of the owner it is extended for an additional period not to exceed three years. If any required improvements have not been installed or

maintained as provided, the bond shall be forfeited to the municipality which shall then use the proceeds to install and maintain covered improvements.

- (4) **Effect.** Approval of the Development Review Board of a major subdivision shall not be construed to constitute acceptance by the town of any street, easement, utility, park, recreation area or other open space shown on the final plat. Such acceptance may be accomplished only by an act of the Hardwick Select Board, in accordance with state law for the laying out of public rights-of-way.

(E) **Recording & Amendment Requirements.**

- (1) In accordance with the Act [§4463], within 180 days of the date of receipt of final subdivision approval under Subsection (D)(2), the subdivider shall file three copies of plan and final plat (one Mylar, two paper), signed by an authorized representative of the Development Review Board, for recording in the land records of the town in conformance with the requirements of 27 V.S.A. Chapter 17. Approval of subdivision plats not filed within 180 days shall expire.
- (2) Notwithstanding (1) above, the Zoning Administrator may extend the deadline for filing the plat by 90 days, if the subdivider can demonstrate that final local or state permits or approvals are still pending.
- (3) The municipality shall meet all recording requirements for subdivision approvals as specified for municipal land use permits under Section 7.6.
- (4) No changes, modifications, or other revisions that alter the final plat or the conditions attached to subdivision approval shall be made unless the proposed revisions are first submitted for review by the Zoning Administrator under Section 6.2 as a minor subdivision amendment, or the Development Review Board under 6.3 as major subdivision amendment. In the event that revisions are recorded without complying with this requirement, the revisions shall constitute a violation of these regulations, and be considered null and void.

Section 6.4 Application of Subdivision Standards

- (A) The Development Review Board shall evaluate major subdivisions under the standards set forth in this article. The Development Review Board, to assist in its evaluation, may require:
- (1) that the subdivider identify the intended use of land to be subdivided, including a general indication of subsequent development plans for retained land when only a portion of an existing parcel is to be subdivided;
 - (2) an independent technical review of the proposed subdivision under one or more standards, prepared by a qualified professional and paid for by the subdivider; and
 - (3) the modification of the subdivision design, the phasing of development, and/or additional measures to avoid or mitigate any adverse impacts likely to result from the proposed subdivision.

Section 6.5 General Standards [applicable to all Major Subdivision]

- (A) **Development Suitability.** All land to be subdivided shall be suitable for the intended use and proposed density of development, and not result in undue adverse impacts to public health and safety, natural resources identified in the Hardwick Town Plan, or the character of the surrounding neighborhood in which it is located. Subdivisions shall set

aside, or exclude from subsequent development, land that is characterized by periodic flooding, poor drainage, steep slopes, or other hazardous conditions, or that is inadequate to support structures or infrastructure.

- (B) **Hardwick Town Plan & Regulations.** Subdivisions shall conform to the Hardwick Town Plan, other provisions of these regulations, capital budget and programs, and all other municipal bylaws, ordinances and regulations in effect at the time of application.
- (C) **District Settlement Patterns.** A subdivision shall be designed to achieve the purpose, objectives and desired settlement patterns of the zoning district(s) in which it is located, as defined in Article 2. To the extent feasible, new subdivisions of land shall:
 - (1) maintain and extend desired settlement patterns, including lot areas and configurations, building locations, and road networks;
 - (2) maintain contiguous tracts of open land with adjoining parcels; and
 - (3) connect and extend existing road, sidewalk, path, and utility corridors.
- (D) **Lot Layout.** Lot layouts shall:
 - (1) be consistent with the suitability of land for development, as defined under Subsection (A);
 - (2) conform to desired district settlement patterns, as required under Subsection (C);
 - (3) meet zoning district minimum lot size and density requirements under Article 2, except as modified for planned unit developments under Article ~~5.55.4~~;
 - (4) conform to lot and yard requirements under Section 3.8; and
 - (5) avoid irregularly shaped lots (e.g., with curves, jogs, dog-legs, etc.), unless warranted due to topographic constraints, or to minimize the fragmentation of natural, scenic or cultural features.
- (E) **Survey Monuments.** The locations of all proposed permanent surveying monuments and corner markers, as required under the Rules of the Board of Land Surveyors, shall be identified on the final subdivision plat.
- (F) **Building Envelopes.** The Development Review Board may require the designation of building envelopes to limit the location of structures, parking areas, and associated site improvements to one or more portions of a lot. The size and shape of each building envelope shall be established in accordance with these regulations. The Development Review Board also may require the identification of specific building footprints if, in its judgment, such information is needed to determine conformance with these regulations.
- (G) **Natural, Scenic & Historic Resource Protection.** Subdivision boundaries, lot lines, and building envelopes shall be located and configured to avoid adverse impacts to significant natural, historic and scenic features identified in the Hardwick Town Plan or through site investigation. For purposes of these regulations, these shall include wetlands, surface waters, and associated buffer areas (Section 3.12); flood hazard areas (Section 5.3); prominent ridgelines and hilltops, rock outcroppings, and slopes in excess of 25% (Section 3.15); critical wildlife habitat areas; and historic sites, structures and features (e.g., buildings, cellar holes, stone walls). Accordingly:
 - (1) lot lines shall be configured to avoid the fragmentation of significant natural or

cultural features, including designated buffer areas;

- (2) building envelopes shall be located and sized to exclude such features;
- (3) roads, driveways and utility corridors, to the extent feasible, shall be shared, located to follow existing linear features (e.g., farm roads, stone walls, tree and fence lines), and to avoid significant natural and cultural features;
- (4) lot lines and building envelopes shall be located to ensure that no buildings are placed on steep slopes, or extend above the height of land (highest point) of any prominent ridgeline or hilltop;
- (5) historic sites and structures shall be incorporated in subdivision design and layout;
- (6) subdividers may be required to incorporate buffers, landscaping or screening in subdivision design, and/or submit management plans to protect significant natural, scenic and historic resources.

(H) **Stormwater Management & Erosion Control.** Subdivisions shall incorporate temporary and permanent stormwater management and erosion control practices appropriate for the type and density of proposed development. Accordingly:

- (1) All stormwater management systems shall be designed to:
 - a. use natural drainage systems to the extent feasible, and minimize the need for maintenance,
 - b. maximize on-site infiltration and treatment of stormwater, and minimize surface runoff,
 - c. accommodate anticipated storm events,
 - d. provide storage areas and treatment to manage flow and protect water quality, and
 - e. avoid damage to adjoining or downstream properties.
- (2) The Development Review Board may require the submission of stormwater management and erosion control plans, prepared by a licensed professional. Such plans shall incorporate acceptable stormwater treatment practices and sizing criteria set forth in the Vermont Stormwater Management Manual as most recently amended.
- (3) The Development Review Board may require the phasing of site development or construction to limit the extent of disturbed area during each phase of the subdivision.
- (4) The Development Review Board also may require an evaluation of the effect of the subdivision on existing downstream drainage capacity outside the area of subdivision. Where the Board finds that increased runoff from the subdivision will exceed the capacity of downstream storage, drainage or treatment systems, it may request that the subdivider delay construction until such capacity exists, or to install necessary off-site improvements as needed to increase capacity.

(I) **Landscaping & Screening.** The preservation, planting and maintenance of trees, ground cover, or other vegetation, of a size and type deemed appropriate by the Development Review Board, may be required to:

- (1) preserve existing trees, tree lines, wooded areas of particular natural or aesthetic

value to the site, or critical wildlife habitat areas;

- (2) provide an undisturbed vegetated buffer between developed and undeveloped portions of the site to protect water quality, or other natural or scenic features.
 - (3) provide screening to increase privacy, reduce noise or glare, or establish a barrier between incompatible land uses; and/or to
 - (4) establish a tree canopy along roads or pedestrian walkways where the Development Review Board deems it appropriate.
- (J) **Energy Conservation.** Subdivision design and layout, to the extent feasible, will encourage energy efficiency through:
- (1) the siting and orientation of development (e.g., building envelopes), to take advantage of southern exposures and natural vegetative or topographic buffers;
 - (2) the clustering of development (e.g., lots, building envelopes) to minimize road and utility line extensions and reduce travel distances; and
 - (3) the effective use of landscaping to provide wind barriers and shading, and to reduce heat loss.

Section 6.6 Transportation Facilities & Infrastructure

- (A) **Access.** Access to the subdivision and to individual lots shall be provided in accordance with the requirements of Section 3.3. All access onto town highways shall be subject to the approval of the Hardwick Select Board, or for state routes, the Vermont Agency of Transportation. Such approval shall be required prior to final subdivision plan approval. To better manage traffic flow and safety, to avoid congestion, and to preserve the capacity of local roads, the Development Review Board may also:
- (1) limit the number of access points onto public highways;
 - (2) require shared access, driveways, and/or roads to serve multiple lots;
 - (3) require access from secondary roads, if a proposed subdivision has frontage on both primary and secondary roads;
 - (4) require rights-of-way for future road extensions to connect to adjoining parcels; and/or
 - (5) prohibit the creation of reserved strips adjacent to a proposed road which would deny access from adjacent properties.
- (B) **Driveways.** Driveways serving three or fewer lots, shall meet standards for driveways included in the Town of Hardwick Policy for Transportation Construction and Improvements as most recently amended. For the purposes of these regulations, driveways serving four or more lots shall be considered roads subject to the requirements of Subsection (C).
- (C) **Roads.** The following road standards shall apply to all public roads, and to private roads serving four or more lots.
- (1) **Capacity.** Traffic to be generated by the proposed subdivision shall not result in unreasonable traffic congestion on public highways, or exceed the functional capacity of roads, intersections and related infrastructure in the vicinity of the subdivision. The Development Review Board may require the submission of a

traffic impact study to identify impacts and necessary mitigation measures to ensure road safety and efficiency, the cost of which shall be borne by the applicant. The subdivider, as a condition of approval, also may be required to install needed traffic control measures and road improvements, and/or reserve land to accommodate future improvements, as needed to serve the subdivision.

- (2) **Layout.** Roads shall be laid out to:
 - a. minimize the amount of cut and fill required,
 - b. maintain reasonable grades and safe intersections,
 - c. produce useable lots,
 - d. allow for access by emergency vehicles,
 - e. avoid adverse impacts to natural, scenic and historic features,
 - f. follow existing linear features (e.g., field edges, utility corridors, tree and fence lines, stone walls),
 - g. avoid dead-end streets and cul-de-sacs, particularly in village areas, and
 - h. allow for future road extensions, identified as proposed easements on the subdivision plat, to serve adjoining parcels.
 - (3) **Design & Construction.** All roads serving the proposed subdivision shall be designed according to the dimensional and geometric design standards for streets and roads contained in the *Vermont State Standards for the Design of Transportation Construction, Reconstruction and Rehabilitation on Freeways, Roads, and Streets* as most recently amended; and constructed in accordance with the *Town of Hardwick Policy for Transportation Construction and Improvements*.
 - (4) **Maintenance.** The maintenance of all roads not designated as Class III town highways or higher shall be the responsibility of the subdivider and subsequent property owners. The subdivider shall provide evidence and assurance that such roads will be adequately maintained by the subdivider and/or an owners' association. In instances involving proposed lots requiring access onto Class IV town highways, a road maintenance agreement approved by the Hardwick Select **B**oard shall be required prior to final subdivision approval.
 - (5) **Names & Signs.** Road names shall be approved by the Hardwick Select **B**oard, in accordance with road naming ordinances and policies currently in effect. Approved road names shall be clearly depicted on the final plat, and identified on signs approved by the Select **B**oard.
- (E) **Parking Facilities.** Common or shared parking areas shall be identified on the subdivision plat, and designed in accordance with Section 3.10. Parking areas for individual lots shall be included within designated building envelopes.
 - (F) **Transit Facilities.** The Development Review Board may require that subdivisions located on existing or proposed transit routes, including school bus routes, include a sheltered transit stop for use by residents of the subdivision.
 - (G) **Pedestrian Access.** To facilitate pedestrian access from the subdivision to adjoining parcels and roads, or to nearby public schools, playgrounds, or public lands, the

Development Review Board may require one or more of the following:

- (1) sidewalks and curbing to connect to existing sidewalks on adjoining properties;
- (2) sidewalks and curbing along internal subdivision roads within the Central Business and Village Neighborhood Districts.
- (3) the installation of pedestrian crosswalks at designated intersections,
- (4) unobstructed easements at least 10 feet in width for pedestrian or recreation paths, as indicated on the final plat.

Section 6.7 Facilities & Utilities

- (A) **Public Facilities.** The Development Review Board shall find that the proposed subdivision does not create an undue burden on existing and planned public facilities. The Development Review Board may consult with appropriate municipal and school officials to determine whether adequate capacity exists to serve the subdivision. The Development Review Board also may require a fiscal impact analysis, to be paid for by the subdivider, and/or the phasing of development in accordance with a duly adopted municipal or school capital budget and program.
- (B) **Fire Protection.** The Development Review Board, in consultation with the Hardwick Fire Department, may require that the subdivider provide adequate water storage and distribution facilities for fire protection. The subdivider shall install fire hydrants, dry hydrants, or fire ponds as required by the Board.
- (C) **Water Systems.** The subdivider shall demonstrate to the satisfaction of the Development Review Board that adequate potable water supplies exist on and/or off site to serve the subdivision. In addition:
 - (1) Subdivisions within the designated municipal water system service areas for Hardwick and East Hardwick shall be connected to such systems in accordance with municipal water system ordinances currently in effect; and the location of water lines shall be shown on the final subdivision plat.
 - (2) On-site systems, including individual or community water supply systems, shall be designed in accordance with all applicable state and municipal regulations. The Development Review Board may require that all water sources be identified on the final subdivision plat.
 - (3) Where applicable, designated source protection areas (SPAs) for municipal and community water supplies also shall be identified on the final subdivision plat; and shall be managed in accordance with a state approved source protection plan.
 - (4) The location of structures and in-ground wastewater disposal systems will be reviewed to ensure such locations do not encroach upon existing water supply isolation distances, as defined by applicable state regulations.
- (D) **Wastewater Systems.** All subdivisions within the Hardwick municipal sewer service area shall be designed and connected to the municipal system in accordance with the municipal sewer ordinance. Sewer lines shall be shown on the final plat. All other on-site systems, including individual and community (clustered) systems, shall be designed in accordance with applicable state and municipal regulations. The Development Review Board may require that sewage disposal areas be identified on the final plat.

- (E) **Utilities.** All existing and proposed utilities, including but not limited to electric, telephone, and cable television utilities, shall be shown on the final plat. In addition:
- (1) All utilities within the subdivision shall be located underground, unless the Development Review Board determines that burial is not necessary to preserve the scenic character of the area, or that it is prohibitively expensive.
 - (2) The subdivider shall coordinate subdivision design with utility companies, including the Hardwick Electric Company, to ensure that suitable areas are available for above ground or underground installation, within and adjacent to the proposed subdivision. Utility easements of sufficient width shall be provided to serve both the proposed subdivision, and future service extensions to adjoining properties. Such easements shall be identified on the final plat.
 - (3) Utility corridors shall be shared with other utility and/or transportation corridors where feasible, and be located to minimize site disturbance, adverse impacts to significant natural, cultural and scenic features, and to public health.

Section 6.8 Legal Requirements

- (A) Land reserved for the protection of significant natural, cultural or scenic features, or other open space areas, may be held in common, or in separate ownership from contiguous parcels. Such land may be dedicated, either in fee or through a conservation easement approved by the Development Review Board, to the municipality, an owners' association comprised of all present or future owners of subdivided lots, and/or a nonprofit conservation organization. At minimum, land designated for protection shall be indicated with appropriate notation on the final subdivision plat.
- (B) The subdivider shall provide documentation and assurances that all required improvements, associated rights-of-way and easements, and other common lands or facilities will be adequately maintained either by the subdivider, an owners' association, or through other legal means acceptable to the Development Review Board. Such documentation, as approved by the Development Review Board, shall be filed in the Hardwick land records.
- (C) All required improvements shall be constructed to approved specifications in accordance with a construction schedule approved by the Development Review Board. The Board may require that all such improvements be completed prior to the issuance of a zoning permit for the subsequent development of subdivided lots. A performance bond or comparable surety acceptable to the Hardwick Select Board may be required to ensure that all improvements are completed to specification.

ARTICLE 7. ADMINISTRATION & ENFORCEMENT

Section 7.1 Permit & Application Requirements

- (A) **Zoning Permit Requirements.** No land development may commence, and no structure may be erected, substantially improved, moved, or changed in use, unless a zoning permit has been issued by the Zoning Administrator, or the development is specifically exempted from the provisions of these bylaws under Section 7.2. Other municipal permits or approvals, such as curb-cut or sewer connection approval, also may be required under separate ordinances.
- (B) **Application Requirements.** Applications for zoning permits shall be submitted to the Zoning Administrator on forms provided by the Town, along with any application fees as established by the Select **B**oard. In addition, the following will be required as applicable:
- (1) **Permitted Uses.** Applications for permitted uses shall include a statement of the existing and intended use of land and structures, and be accompanied by a sketch plan, drawn to scale, that includes the following:
 - a. the dimensions of the lot, including existing and proposed property boundaries;
 - b. the location, footprint, and height of existing and proposed structures and additions;
 - c. the location of existing and proposed easements, rights-of-way and utilities;
 - d. setbacks from property boundaries, rights-of-way, surface waters, and wetlands;
 - e. a surveyor's plot plan, if available; and
 - f. additional information as requested to determine conformance with the provisions of these bylaws.
 - (2) **Conditional Uses.** Uses that require conditional use review must include a development plan prepared and submitted in accordance with Section 5.2.
 - (3) **Flood Hazard Area Review.** Uses within the flood hazard overlay district that require flood hazard review must include a flood hazard development plan prepared and submitted in accordance with Section 5.3.
- (C) **Issuance of Zoning Permits.** The Zoning Administrator shall issue zoning permits in accordance with the following:
- (1) No zoning permit shall be issued by the Zoning Administrator for any use or structure which requires approval of the Development Review Board, until such approval has been obtained.
 - (2) Within 30 days of receipt of a complete application, including all application materials, fees and approvals, the Zoning Administrator shall either issue, deny or refer a permit in writing to the Development Review Board. An application for a zoning permit will not be considered complete until all approvals Development Review Board as required by these bylaws have been obtained. Denials shall include a statement describing the reasons for denial and the time in which appeals may be made under Section 7.3. If the Zoning Administrator fails to act within the 30 day period, a permit shall be deemed issued on the 31st day.

- (3) Within 3 days of issuance, the Zoning Administrator shall deliver a copy of the permit to the Listers, and post a copy at the Town Office for a period of 15 days from issuance.
 - (4) A notice of permit, on a form prescribed by the municipality, must be posted by the applicant within view from the public right-of-way most nearly adjacent to the subject property until the time for appeal has passed.
- (D) **Effective Dates.** No zoning permit shall take effect until the time for appeal under Section 7.3 has passed, or in the event that a notice of appeal is properly filed, until final adjudication of the appeal. Permits and associated conditions will run with the land and be binding upon the landowner's future heirs and assigns. A permit will, however, expire and become null and void within 2 years from the date of issuance if the permitted development has not substantially commenced. Prior to the expiration of the permit, the Zoning Administrator may issue an extension for one additional year.
- (E) **Certificate of Compliance.**
- (1) **Special Flood Hazard Area.** It shall be unlawful to use or occupy, or permit the use or occupancy of any land or structure, or part thereof, created, erected, changed, converted, or wholly or partly altered or enlarged in its use or structure within Special Flood Hazard Area until a Certificate of Compliance is issued by the Zoning Administrator stating that the proposed use of the structure or land conforms to the requirements of these bylaws. A Certificate of Compliance shall not be required for structures that were built in compliance with the bylaws at the time of construction and have not been improved since the adoption of this bylaw.
 - (2) **Other Development.** The Development Review Board may require, as a condition of subdivision or conditional use approval for development outside of the Special Flood Hazard Area, that a Certificate of Compliance be obtained to ensure that all work has been completed in conformance with the zoning permit and associated approvals, including all applicable permit conditions.
 - (3) The application for a Certificate of Compliance shall be submitted to the Zoning Administrator with as-built plans drawn to scale which show the location of all monuments, utilities, structures, roadways, easements, parking areas, signs, landscaping and other improvements as constructed.
 - (4) Within 14 days of receipt of the application for a certificate of compliance, the Zoning Administrator will inspect the premises to ensure that all work has been completed in conformance with the conditions of approval. If the Zoning Administrator fails to either grant or deny the certificate of compliance within 14 days of the submission of an application, the certificate shall be deemed issued on the 15th day.
 - (5) If a Certificate of Compliance cannot be issued, notice will be sent to the owner. In the case of development within the Special Flood Hazard Area, notice will be copied to the lender.

Section 7.2 Exemptions

- (A) No zoning permit shall be required for the following:
 - (1) Repair, remodeling or interior alteration of an existing structure outside of the

Special Flood Hazard Area that does not result in any change to the footprint or height dimensions, or any expansion in the total area, of the structure, or a change in use.

- (2) Normal maintenance of an existing structure that does not result in any change to the footprint or height dimensions, or any expansion in the total area of the structure, or a change in use.
- (4) Residential entry stairs (excluding deck or porch areas), handicap ramps, walkways, and fences or walls less than 8 feet in height which do not extend into or obstruct public rights-of-way, interfere with corner visibility or sight distances for vehicular traffic, or encroach into the Special Flood Hazard Area.
- (5) Accessory structures, such as a shed, tree house, doghouse, child's play house, or similar structure with a floor area of not more than 100 square feet (each) and a height of not more than ten (10) feet which is located at least 10 feet from all property lines, and outside the Special Flood Hazard Area and the River Corridor, and set back 75 feet from all perennial streams and rivers in accordance with Section 3.12. A zoning permit is required for all other accessory structures.
- (6) Prefabricated, temporary carports and storage covers assembled out of metal structural supports and fabric, provided they are located outside of the Special Flood Hazard Area and the River Corridor, and such covers are not affixed to a permanent foundation, do not exceed 240 square feet of covered space and meet all setback standards for the district in which they are located.
- (7) The ordinary use of a small room of a dwelling for personal office use and/or

Interested Person. In accordance with the Act [§4465 (b)], the definition of an interested person includes the following:

- a person owning title to property, or a municipality or solid waste management district empowered to condemn it or an interest in it, affected by a bylaw, who alleges that the bylaw imposes on the property unreasonable or inappropriate restrictions of present or potential use under the particular circumstances of the case.
- The Town of Hardwick or any municipality that adjoins it.
- a person owning or occupying property in the immediate neighborhood of a property that is the subject of any decision or act taken under this chapter, who can demonstrate a physical or environmental impact on the person's interest under the criteria reviewed, and who alleges that the decision or act, if confirmed, will not be in accord with the policies, purposes, or terms of the plan or bylaw of that municipality.
- any ten persons who may be any combination of voters or real property owners within a municipality listed above who, by signed petition to the appropriate municipal panel of a municipality, the plan or a bylaw of which is at issue in any appeal brought under this title, allege that any relief requested by a person under this title, if granted, will not be in accord with the policies, purposes or terms of the plan or bylaw of that municipality. This petition to the appropriate municipal panel must designate one person to serve as the representative of the petitioners regarding all matters related to the appeal.
- any department and administrative subdivision of this state owning property or any interest in property within a municipality listed above, and the agency of commerce and community development of this state.

paperwork for business activity carried on elsewhere, in accordance with Section 4.8.

- (8) Noncommercial outdoor recreation that outside of the Special Flood Hazard Area does not involve the development or use of structures or site improvement. Examples of site improvement include the construction of parking area at a trail head, pavilion, or bridge.
 - (9) Minor grading and excavation associated with road and driveway maintenance (including culvert replacement and re-surfacing) and yard improvements associated with accessory uses to existing principle uses (contouring yards, establishing garden and landscape areas), providing they do not alter or impact a perennial stream or alter the flood carrying capacity of any watercourse within the Special Flood Hazard Area or the River Corridor.
 - (10) Garage sales, yard sales and auctions not exceeding 3 consecutive days, nor more than 12 days per calendar year, which do not cause unsafe traffic conditions or parking problems.
 - (11) Fuel storage as an accessory structure to an allowed use, provided such storage is outside the Special Flood Hazard Area and the River Corridor and meets the requirements of Section 3.15.
 - (12) Accepted management practices (AMPs) for silviculture as defined by the Commissioner of Forests, Parks, and Recreation, pursuant to the Act [§4413(d)].
 - (13) The removal of a building or other structure in whole or in part from the Special Flood Hazard Area or the River Corridor.
- (B) In accordance with the Act [§4413(d)], required agricultural practices (RAPs), including farm structures, as defined by the Commissioner of Agriculture, Food and Markets, also are also exempted from the permit requirements under Section 7.1. However, written notification, including a sketch plan of the structure showing setback distances from road rights-of-way, property lines, and surface waters shall be made to the Zoning Administrator prior to any construction as required under the RAPs.

Section 7.3 Appeals

- (A) **Decisions of the Zoning Administrator.** In accordance with the Act [§§4465, 4472], the applicant or any interested person may appeal a decision or act of the Zoning Administrator by filing a notice of appeal with the Secretary of the Development Review Board, or the Town Clerk if no Secretary has been elected, within 15 days of the date of such decision or act.
- (1) The Development Review Board shall hold a public hearing on a notice of appeal within 60 days of the filing of the appeal. The Board shall give public notice of the hearing as required under Section 7.6, and mail a copy of the hearing notice to the appellant at least 15 days prior to the hearing date.
 - (2) The Development Review Board shall render a decision on appeal, to include written findings of fact, within 45 days after close of hearing as required by the Act [§4464]. The Board may reject an appeal without hearing, and render a decision within 10 days of the filing of a notice of appeal, if the Board determines that the issues raised by the appellant have been decided in an earlier appeal, or are based

on substantially or materially the same facts, by or on behalf of the appellant. Copies of the decision shall be mailed to the appellant and hearing participants, and filed with the Zoning Administrator and Town Clerk in accordance with the Act.

- (B) **Decisions of the Development Review Board.** The applicant or any interested person who has participated in the proceeding may appeal a decision of the Development Review Board within 30 days of such decision to the Vermont Environmental Court, in accordance with the Act [§§4471, 4472]. Notice of appeal shall be sent to every interested person appearing and having been heard at the hearing before the Board.
- (C) **Notice of Appeal.** A notice of appeal shall be in writing and include:
- (1) the name and address of the appellant;
 - (2) a brief description of the property with respect to which the appeal is taken;
 - (3) a reference to applicable bylaw provisions;
 - (4) the relief requested by the appellant, including any request for a variance from one or more provisions of these bylaws;
 - (5) the alleged grounds why such relief is believed proper under the circumstances; and
 - (6) any request for a stay of enforcement which may be granted or denied by the Vermont Environmental Court in accordance with the Act [§4449(a)(3)].

Section 7.4 Variances

- (A) The Development Review Board shall hear and decide upon requests for variances pursuant to the Act [§4469] and appeal procedures under Section 7.3. The Board may grant a variance, and render a decision in favor of the appellant, only if all of the following facts are found, and the findings are specified in its written decision:
- (1) that there are unique physical circumstances or conditions, including irregularity, narrowness, or shallowness of lot size or shape, or exceptional topographical or other physical conditions peculiar to the particular property, and that unnecessary hardship is due to such conditions and not the circumstances or conditions generally created by the provisions of the zoning regulation in the neighborhood or district in which the property is located;
 - (2) that because of such physical circumstances and conditions, there is no possibility that the property can be developed in strict conformity with the provisions of the zoning regulation and that the authorization of a variance is necessary to enable the reasonable use of the property;
 - (3) that the unnecessary hardship has not been created by the appellant;
 - (4) that the variance, if authorized, will not alter the essential character of the neighborhood or district in which the property is located, substantially or permanently impair the appropriate use or development of adjacent property, reduce access to renewable energy resources, nor be detrimental to the public welfare; and
 - (5) that the variance, if authorized, will represent the minimum that will afford relief and will represent the least deviation possible from the zoning regulation and from the plan.
- (B) (B) In granting a variance, the Development Review Board may impose conditions it

deems necessary and appropriate under the circumstances to implement the purposes of these bylaws and the municipal plan currently in effect. In no case shall the Development Review Board grant a variance for a use which is not permitted or conditionally permitted within the zoning district, or which results in an increase in allowable density.

- (C) Variances within the Flood Hazard Area Overlay District shall be granted by the Development Review Board only:
- (1) in accordance with the Act [§4469, §4424] and in accordance with the criteria for granting variances found in 44 CFR, Section 60.6, of the National Flood Insurance Program regulations;
 - (2) upon a determination that during the base flood discharge the variance will not result in increased flood levels; and
 - (3) upon a determination that the structure or other development is protected by methods that minimize flood damages during the base flood and create no additional threats to public safety.
 - (4) Any variance issued in the Special Flood Hazard Area will inform the applicant in writing over the signature of the Zoning Administrator that the issuance of a variance to construct a structure below the base flood elevation increases risk to life and property and will result in increased flood insurance premiums up to amounts as high as \$25 for \$100 of coverage. Such notification shall be maintained with a record of all variance actions.

Section 7.5 Violations & Enforcement

- (A) **Violations.** The commencement or continuation of any land development or use which is not in conformance with the provisions of these bylaws shall constitute a violation. The Zoning Administrator shall take appropriate action in the name of the Town to enforce the provisions of these bylaws in accordance with the Act [§§4451, 4452]. All fines imposed and collected for violations of these bylaws shall be paid over to the Town.
- (B) **Notice of Violation.** No action may be brought under this Section unless the alleged offender has had at least seven days' notice by certified mail that a violation exists. The warning notice shall state that a violation exists, the nature of that violation, that the alleged offender has an opportunity to cure the violation within the seven days and that the alleged offender will not be entitled to an additional warning notice for the violation occurring after the seven days. Action may be brought without notice and opportunity to cure if the alleged offender repeats the violation of the bylaw after the seven-day notice period and within the next succeeding 12 months.
- (C) **Limitations on Enforcement.** The Town shall observe any limitations on enforcement proceedings relating to municipal permits and approvals. Enforcement proceedings must be instituted within 15 years from the date the violation first occurred. The burden of proving the date that the alleged violation first occurred shall be on the person against whom the enforcement action is instituted.
- (D) **Violations in the Flood Hazard Overlay.** Notwithstanding 7.5(C) above, a violation in the Flood Hazard Overlay shall remain a violation until such violation is cured.
- (1) A copy of the notice of violation will be mailed to the State National Flood Insurance Program Coordinator.

- (2) If any appeals have been resolved, but the violation remains, the Zoning Administrator shall submit a declaration to the Administrator of the National Flood Insurance Program requesting a denial of flood insurance to the property pursuant to Section 1316 of the National Flood Insurance Act of 1968, as amended.
- (3) Violations of Required Agricultural Practices shall be enforced under this Section as violations of this bylaw. Such violations shall also be immediately reported to the Secretary of Agriculture for enforcement under 6 V.S.A. Section 4812.

Section 7.6 Municipal Administrative Requirements

- (A) Appointments. The following appointments shall be made in association with the administration and enforcement of these bylaws as provided for in the Act:
- (1) **Zoning Administrator.** The Zoning Administrator shall be nominated by the Planning Commission and appointed by the Select ~~B~~board for a term of 3 years in accordance with the Act [§4448]. In the absence of the Zoning Administrator, the Planning Commission may nominate and the Select ~~B~~board appoint an Acting Zoning Administrator. The Zoning Administrator shall administer these bylaws literally, and shall not have the power to permit any development that is not in conformance with it.
 - (2) **Development Review Board.** Members of the Development Review Board, which may consist of the members of the Planning Commission, shall be appointed by the Select ~~B~~board [§4460]. One or more alternates also may be appointed by the Select ~~B~~board to serve for members in the event of an absence or conflict of interest. The Board shall adopt rules of procedure to guide its official conduct in accordance with the requirements of the Act [§4461] and Vermont’s Open Meeting Law [1 V.S.A., §310-314]; and shall have quasi-judicial powers and duties as set forth in the Act to administer the provisions of these bylaws, including but not limited to the power to hear and decide:
 - requests for access approval under Section 3.3;
 - applications for conditional use approval under Section 5.2, ~~and~~ Section 5.3, and 5.4;
 - applications for planned residential and planned unit developments under Section 5.4.5.5;
 - requests for subdivision approval under Section 6.1 and
 - appeals from any decision, act or failure to act by the Zoning Administrator under Section 7.3; and
 - variance requests under Section 7.4.
 - (3) **Planning Commission.** The Planning Commission shall be appointed by the Select ~~B~~board. The Commission shall adopt rules of procedure to guide its official conduct in accordance with the requirements of the Act [§4323] and Vermont’s Open Meeting Law [1 V.S.A. 310-314]; and shall have legislative powers and duties as set forth in the Act [§4325], including but not limited to the power to hear and decide requests and petitions for bylaw amendments.
- (B) **Fee Schedule.** The Select ~~B~~board shall establish a schedule of fees to be charged in

administering these regulations, with the intent of covering the town's administrative costs.

(C) **Hearing Notice Requirements.** Any public notice required for public hearing under these bylaws shall be given by the publication of the date, place and purpose of such a hearing in a newspaper of general circulation in the Town, and the posting of such notice in three or more public places within the Town including posting by the applicant of a notice of hearing within view from the public right-of-way most nearly adjacent to the property for which an application is made, not less than 15 days prior to the hearing date. Failure by the applicant to comply with this requirement may result in the denial of the application. Written notification of the hearing shall be sent by mail to the applicant and to all adjoining property owners. The applicant will be required to provide a list of adjoining property owners to the Administrator for notification purposes.

(D) **Permit Recording Requirements.** As required by the Act [§4443(c)], within 30 days after a municipal land use permit, including but not limited to a zoning permit and associated approvals, has become final, or within 30 days of the issuance of a notice of violation, the Zoning Administrator shall deliver the notice of violation, or memorandum or notice of recording, to the Town Clerk for recording as provided in 24 V.S.A. subsections 1154(a) or (b). The applicant shall be charged the cost of recording fees.

Municipal Land Use Permit: a zoning, subdivision, site plan or building permit or approval, any of which relate to land development as defined in statute, which has received final approval from the applicable board, commission, or officer of the municipality [24 V.S.A. §4303(11)].

(E) **Flood Hazard Overlay Recording Requirements.** For development within the Flood Hazard Overlay, the Zoning Administrator shall also maintain a record of:

- (1) All permits issued in areas covered by this bylaw;
- (2) Elevation Certificates with the as-built elevation (consistent with the datum of the elevation on the current Flood Insurance Rate Maps for the community) of the lowest floor, including basement, of all new or substantially improved buildings (not including accessory buildings) in the Special Flood Hazard Area;
- (3) All flood proofing and other certifications required under this regulation; and,
- (4) All decisions of the Development Review Board (including variances and violations) and all supporting findings of fact, conclusions and conditions.

ARTICLE 8. DEFINITIONS

Section 8.1 Terms & Use

- (A) Except where specifically defined here or in the Act, or unless otherwise clearly required by the context, all words, phrases and terms in these regulations shall have their usual, customary meanings.
- (B) In the interpretation of words and terms used, defined, or further described here, the following shall apply:
- (1) the specific controls the general;
 - (2) the present tense includes the future tense;
 - (3) the singular includes the plural;
 - (4) the word "shall" is mandatory; the word "may" is permissive;
 - (5) the word "structure" includes "building; "
 - (6) the word "road" includes "street" and "highway; "
 - (7) the word "lot" includes "parcel; "
 - (8) the word "person" includes an individual, partnership, association, corporation, company or organization; and
 - (9) the word "occupied" or "used" shall be considered as though followed by "or intended, arranged or designed to be used or occupied. "
- (C) Any interpretation of words, phrases or terms by the Zoning Administrator may be appealed to the Development Review Board under Section 7.3. In such cases, the Board shall base its decision upon the following definitions, state statute, and the need for reasonable and effective implementation of these regulations. The Board shall publish and update from time to time such written interpretation, to ensure consistent and uniform application of the provisions of these regulations.

Section 8.2 Definitions

Abutting Property: Two or more parcels which share a common parcel boundary or point. For the purposes of these regulations, abutting property shall also include facing properties across road rights-of-way. See also *Contiguous Land*.

Accepted Management Practices (AMPs): Accepted silvicultural (forestry) practices as currently defined by the Commissioner of the Vermont Department of Forests, Parks and Recreation in accordance with the Act [§4413(d)].

Accessory Dwelling: A secondary dwelling unit established in conjunction with and clearly subordinate to a single unit family dwelling which is retained in common ownership, is located on the same parcel as the primary structure, and which otherwise meets applicable criteria of

these regulations (see Section 4.2). This definition encompasses accessory apartments as required under the Act [§4412(1)]. See also *Caretakers Apartment*.

Accessory Structure: A structure which is: 1) detached from and clearly incidental and subordinate to the principal use of or structure on a lot, 2) located on the same lot as the principal structure or use, and 3) clearly and customarily related to the principal structure or use. For residential uses these include, but may not be limited to garages, garden and tool sheds, playhouses, and in-ground swimming pools which are incidental to the residential use of the premises and not operated for gain. For other than residential uses these are sheds and storage buildings which are incidental to the approved conditional use of the premises. See also *Accessory Use*.

Accessory Use: A use which is customarily incidental and subordinate to the principal use of a lot or parcel of land, is located on the same lot as the primary use, and is clearly related to the principal use.

Access: A defined area of vehicular ingress and/or egress between property and an abutting road right-of-way.

Act: 24 V.S.A., Chapter 117, the Vermont Municipal and Regional Planning and Development Act as amended.

Adaptive Reuse: The rehabilitation or renovation of an historic structure for another allowed use, as specified in these regulations (see Section 4.3).

Affordable Housing: In accordance with the Act [§4303(1)], housing that is either: (1) owned by its inhabitants, whose gross annual household income does not exceed 80 percent of the state median income, as defined by the United States Department of Housing and Urban Development, and the total annual cost of the housing, including principal, interest, taxes and insurance, is not more than 30 percent of the household's gross annual income; or (2) rented by its inhabitants whose gross annual household income does not exceed 80 percent of the state median income, as defined by the United States Department of Housing and Urban Development, and the total annual cost of the housing, including rent, utilities, and condominium association fees, is not more than 30 percent of the household's gross annual income.

Affordable Housing Development: In accordance with the Act [§4303(2)], a housing development of which at least 20 percent of the units or a minimum of 5 units, whichever is greater, are affordable housing units.

Agriculture: Land or structures primarily used for cultivating soils, producing crops, or raising livestock; orchards and maple sugar production; the storage, processing or sale of products raised on the premises; or as otherwise defined by the Commissioner of Agriculture, Food and Markets. Structures which are customarily accessory to agricultural uses and are located on the same parcel as an agricultural use, with the exception of residential dwellings, shall be included in this definition. See also Farm Structure, Required Agricultural Practices.

Agricultural and Forest Processing: The offsite processing and/or packaging of agricultural and forestry products, excluding slaughter houses and saw mills. Examples include but are not limited to: the making of compost products, herbal products, food products, wreaths, woolen products, cheese, and candles. See Section 4.11.

Alteration: Structural change, change of location, or addition to a building or structure, excluding normal maintenance and repair. Alterations shall include any construction that changes the number of dwelling units, or increases the size of a building or structure in terms of its

height, length, width, footprint, or gross floor area. See also ***Improvement, Substantial Improvement.***

Antenna Height: The vertical distance measured from the base of the antenna support structure at grade to the highest point of the structure. If the support structure is on a sloped grade, then the average between the highest and lowest grades shall be used in calculating the antenna height.

Applicant: The owner of land or property proposed to be developed in accordance with these regulations, and/or his or her duly authorized representative. Any party with a legal interest in land development may apply in cooperation with the owner of the property.

Approval: A written decision issued by the Development Review Board within the statutory time limit, or in the event of the Board's failure to act within the specified time limit, a certification of such failure to act issued by the Town Clerk, as attached to the permit application and recorded in the land records of the town.

Area of Shallow Flooding: A designated AO or AH Zone on the Flood Insurance Rate Map (FIRM) having a one percent or greater annual chance of flooding to an average depth of one to three feet where a clearly defined channel does not exist, where the path of flooding is unpredictable, and where the velocity flow may be evident. Such flooding is characterized by ponding or sheet flow.

Area of Special Flood Hazard: is synonymous in meaning with the phrase "special flood hazard area" for the purposes of these regulations. **Bar:** See ***Restaurant.***

Associated transportation and utility networks: Those transportation and utility networks connected to a bridge, culvert, or utility for the purpose of crossing a river or stream and do not include transportation or utility networks within the river corridor that merely run parallel to a river or stream

Formatted: Font: Bold

Bank: See ***Financial Institution.***

Banner: A temporary sign composed of lightweight, flexible, non-rigid material either enclosed or not enclosed in a rigid frame.

Base Flood: The flood having a one percent chance of being equaled or exceeded in any given year (commonly referred to as the "100-year flood").

Base Flood Elevation (BFE): The elevation of the water surface elevation resulting from a flood that has a 1 percent chance of equaling or exceeding that level in any given year. On the Flood Insurance Rate Map, the elevation is usually in feet, in relation to the National Geodetic Vertical Datum of 1929, the North American Vertical Datum of 1988, or other datum referenced in the Flood Insurance Study report, or the average depth of the base flood, usually in feet, above the ground surface.

Basement: Any area of a building having its floor at subgrade (below ground level) on all sides including crawl spaces

Bed & Breakfast (B&B): A single ~~unit family~~ dwelling occupied by the owner or operator, in which not more than six double occupancy rooms within the dwelling and/or in an accessory structure located on the same lot, are rented out to provide overnight accommodations to transient travelers. Individual cooking and eating facilities shall not be provided; breakfasts shall be the only meals served and shall be limited to overnight guests. The bed and breakfast shall function as a private home with house guests. See also ***Hotel/Motel.***

Board: The Hardwick Development Review Board, as established under the Act, unless otherwise specified.

Buffer: Any space between adjoining land uses or between a land use and a natural feature, which is intended and designed to reduce the impact of one use on the other use or feature. Buffers may include open space, woodland, landscaped areas, undisturbed vegetated areas, or other types of physical, visual or sound barriers.

Building: (1) A structure used for the shelter or accommodation of persons, animals, goods, chattel or equipment, which has a roof supported by columns or walls; (2) for development within the flood hazard area overlay district, this definition also includes a gas or liquid storage tank that is principally above ground. See also Structure.

Building Envelope: A specific area delineated on a lot within which all structures are to be located, and outside of which no structures are to be located.

Building Face: The exterior surface of any side of a building, minus windows and doors.

Building Height: The distance measured vertically from the average (of the highest and lowest) finished grade at the base or foundation to the highest point on top of the building (or structure), excluding any noted structural exemptions from height requirements under Section 3.7.

Building Line: The line parallel to the lot line transecting that point in the principal or accessory dwelling face which is closest to the lot line, including porches, whether enclosed or unenclosed, but excluding steps. See also Lot Line, Street Line.

Building Orientation: The location on a lot of a building or other structure in relation to roads, rights-of-way, parks, and building or street lines.

Camp: See Seasonal Dwelling.

Camper: See Recreational Vehicle.

Campground: A parcel of land upon which two or more campsites are located for occupancy by a tent, cabin, lean-to, or similar structure as temporary living quarters for recreation, education, or vacation purposes. "Primitive" campgrounds are further characterized as campgrounds which are limited to substantially unimproved camp sites intended for tenting use only (see Section 4.5).

Caretakers Apartment: A secondary dwelling unit established in conjunction with and clearly subordinate to a principal use other than a single unit family dwelling, which is retained in common ownership, is located on the same parcel as the primary structure, and which otherwise meets applicable criteria of these regulations. See Accessory Apartment. (see Section 4.2).

Cemetery: Land used or dedicated to the burial of the dead, which includes as accessory structures, mausoleums, columbariums, and maintenance facilities, but specifically excludes crematoriums. An individual or family burial plot on private land, registered with the Hardwick Town Clerk in accordance with state law, is exempted from this definition. See also Natural Burial Ground.

Change of Use: Any use which differs substantially from an established use based on the type, intensity, or magnitude of use. For example, this may include a change from one type of use to another (e.g., from a residential to commercial use), or from an accessory to a principal use, or from seasonal to year-round use (see Section 3.4).

Channel: An area that contains continuously or periodic flowing water that is confined by banks

and a streambed.

Church: See Place of Worship.

Commercial Use: An enterprise that is carried on for profit by the owner, lessee or licensee.

Common Land: Land within a development or subdivision that is not individually owned or dedicated for public use, but which is intended to be held in common, for use, enjoyment, management and maintenance by the residents of the development or subdivision. Such land may include but not be limited to open space areas, parking lots, pedestrian walkways, utility and road rights-of way.

Common Plan of Development: Where a structure will be refurbished over a period of time. Such work might be planned unit by unit.

Community Care Facility: A residential care facility licensed by the state which provides 24-hour supervision, personal care services, and limited medical services to seven or more individuals who are in need of care, protection and/or assistance to sustain the activities of daily living. See also Group Home.

Community Center: A building owned by a public or nonprofit entity, or a homeowners or similar community association, which is used for recreational and social activities and is intended primarily to serve the population of the community in which it is located.

Community System: Any water or wastewater disposal system other than a municipally-owned system which provides potable water to or disposes of wastewater from two or more domestic, commercial, industrial, or institutional uses. Such systems shall include related collection, distribution and treatment facilities.

Compensatory Storage: A volume not previously used for flood storage and which shall be incrementally equal to or exceed the theoretical volume of flood water at each elevation, up to and including the base flood elevation, which would be displaced by the proposed project. Such compensatory volume shall have an unrestricted hydraulic connection to the same waterway or water body. Further, with respect to waterways, such compensatory volume shall be provided within the same reach of the river, stream, or creek.

Contiguous Land: (1) A parcel of land contained within a single, unbroken parcel boundary (a division of land by a town or private road right-of-way shall not render such land noncontiguous); or (2) two or more parcels which share a common parcel boundary or point.

Contractor's Yard: A parcel of land with or without buildings thereon to be used for the storage of equipment, materials, and/or vehicles used in the operation of construction and related trades.

Critical facility: Includes police stations, fire and rescue facilities, hospitals, shelters, schools, nursing homes, water supply and waste treatment facilities, and other structures the community identifies as essential to the health and welfare of the population and that are especially important following a disaster. For example, the type and location of a business may raise its status to a Critical Facility, such as a grocery or gas station.

Cul-de-Sac: A road intersecting another road at one end, and terminated at the other end by some form of vehicular turnaround.

Cultural Facility: A museum, theater, concert hall, botanical or zoological garden, or other establishment which offers programs, performances or exhibits of cultural, educational,

historical, or scientific interest, and is not operated as a commercial use. See also Commercial Use, Recreation, Indoor.

~~**Critical facility:** Includes police stations, fire and rescue facilities, hospitals, shelters, schools, nursing homes, water supply and waste treatment facilities, and other structures the community identifies as essential to the health and welfare of the population and that are especially important following a disaster. For example, the type and location of a business may raise its status to a Critical Facility, such as a grocery or gas station.~~

Day Care Facility: All state registered or licensed day care facilities which do not meet the definition of "home child care," including nonresidential child and adult day care facilities, and home-based child care facilities that serve more than six children on a full-time basis. See also Home Child Care, Residential Care Facility.

Degree of Nonconformity: The extent which the nonconforming feature/element of a structure extends beyond that point which constitutes the greatest pre-existing encroachment.

Density: The number of dwelling units, principal uses or structures permitted per area of land, excluding land area within designated road rights-of-way.

Design Flood Elevation (DFE): The Base Flood Elevation plus two feet (in the Town of Hardwick).

Development in the Flood Hazard Area Overlay: any human-made change to improved or unimproved real estate, including but not limited to buildings or other structures, mining, dredging, filling, grading, paving, excavation or drilling operations, or storage of equipment or materials.

Drive-through: A business establishment which includes a driveway approach or parking spaces for motor vehicles to serve patrons while in the motor vehicle rather than within a building or structure.

Driveway: A minor, private travel way, serving up to three adjoining parcels, which provides vehicular access from an adjoining road to a parking space, garage or other structure. See also Road.

Duplex: Per 24 V.S.A. [§4303(39)], means a residential building that has two dwelling units in the same building and neither unit is an accessory dwelling unit. See also Two-~~Unit~~Family Dwelling, Accessory Dwelling, Dwelling Unit.

~~**Dwelling Unit:** A space consisting of one or more rooms designed, occupied or intended for occupancy as a separate living quarters, with cooking, sleeping, and sanitary facilities provided within that space for the exclusive use of a single family or individual maintaining a household. See also Family, Accessory Apartment, and Seasonal, Single Family, Two Family, and Multi-Family Dwelling. A single unit providing complete, independent living facilities for one or more persons, including permanent provisions for living, sleeping, eating, cooking and sanitation.~~

Easement: The legal authorization given by a property owner to another person or party for the use of any designated part of his or her property for a specified purpose.

Educational Facility: See School.

Elderly Housing: A multiple dwelling in one or more buildings, each unit of which is specifically designed and intended for occupancy by at least one person who is 55 years of age or older. Such housing may include, as accessory structures or uses, congregate dining and

recreational facilities, and assisted living services. See also Community Care Facility.

Emergency Shelter: In accordance with 24 V.S.A. [§4303(40)], any facility, the primary purpose of which is to provide a temporary shelter for people experiencing homelessness in general or for a specific population of people experiencing homelessness, and which does not require occupants to sign leases or occupancy agreements.

Encroachment: Fill or development that reduces the functional river corridor (impairs the equilibrium condition) or increases flood levels.

Erosion Control: Measures to prevent the detachment and movement of soil or rock fragments or the wearing away of the land surface by water, wind, ice and gravity.

Equilibrium Condition: The width, depth, meander pattern, and longitudinal slope of a stream channel that occurs when water flow, sediment, and woody debris are transported by the stream in such a manner that it generally maintains dimensions, pattern, and slope without unnaturally aggrading or degrading the channel bed elevation.

Extraction of Earth Resources: A use involving the on-site removal of surface and subsurface materials, including soil, sand, gravel, stone or organic substances other than vegetation, from land or water. Customary extraction operations include sand and gravel pits, and accessory operations such as the crushing, screening, and temporary storage of materials on-site (see Section 4.8). Specifically excluded from this definition are the grading and removal of dirt which is associated with and incidental to an approved site plan or subdivision, or an excavation associated with an accepted agricultural practice. See also Quarrying.

Family: A group of two or more persons living together as a household, or a single person maintaining a household.

Farm Structure: In accordance with the Act [§4495], a building for housing livestock, raising horticultural or agronomic plants, or carrying out other practices associated with agricultural or farming practices, as "farming" is defined in 10. V.S.A. §6001(22). This definition includes such farm structures as barns, silos, fences and manure pits, but specifically excludes a dwelling for human habitation. See also Accessory Dwelling, Agriculture, Accepted Agricultural Practices.

Farming: See Agriculture.

Fill: Any placed material that changes the natural grade, increases the elevation, redirects the movement of flood water, or diminishes the flood storage capacity at the site. Temporary storage of material for less than 180 days is not considered fill.

Final Plat: The final drawings on which the subdivision is presented to the Planning Commission for approval and which, if approved, shall be filed for record with the Town Clerk.

Financial Institution: A bank, savings and loan, finance, mortgage or investment company that is open to the public.

FIRM: See Flood Insurance Rate Map.

Flood: (a) A general and temporary condition of partial or complete inundation of normally dry land areas from: the overflow of inland or tidal waters; the unusual and rapid accumulation or runoff of surface waters from any source; and mudslides which are proximately caused by flooding and are akin to a river of liquid and flowing mud on the surfaces of normally dry land areas, as when earth is carried by a current of water and deposited along the path of the current. (b) The collapse or subsidence of land along the shore of a lake or other body of water as a result

of erosion or undermining caused by waves or currents of water exceeding anticipated cyclical levels or suddenly caused by an unusually high water level in a natural body of water, accompanied by a severe storm, or by an unanticipated force of nature, such as flash flood or abnormal tidal surge, or by some similarly unusual and unforeseeable event which results in flooding.

Flood Hazard: Those hazards related to damage from flood-related inundation or erosion.

Flood Insurance Rate Map (FIRM): An official map of a community, on which the Federal Insurance Administrator has delineated both the special flood hazard areas and the risk premium zones applicable to the community.

Flood Insurance Study (FIS): An examination, evaluation, and determination of flood hazards and, if appropriate, corresponding water surface elevations or an examination, evaluation, and determination of a mudslide and/or flood-related erosion hazards.

Floodplain or flood-prone area: Any land area susceptible to being inundated by water from any source (See Flood.)

Floodproofing: Any combination of structural and nonstructural additions, changes or adjustments to structures which reduce or eliminate flood damage to real estate or improve real property, water and sanitary facilities, structures, and their contents.

Floodway: The channel of a river or other watercourse and the adjacent land areas that must be reserved in order to discharge the base flood without cumulatively increasing the water surface elevation more than one foot at any point. Please note that Special Flood Hazard Areas and floodways may be shown on separate map panels.

Floodway, Regulatory in the Town of Hardwick: The channel of a river or other watercourse and the adjacent land areas that must be reserved in order to discharge the base flood without cumulatively increasing the water surface elevation more than one foot at any point.

Fluvial Erosion: Erosion or scouring of riverbeds and banks during high flow conditions of a river. Fluvial erosion is most likely to occur within the river corridor.

Forestry: The use and management of woodlands for purposes of timber production, harvesting, and management for commercial, wildlife and/or conservation purposes. This definition specifically excludes permanent sawmills, lumber yards and other similar facilities used for the processing and/or manufacturing of wood and wood products; but may include, as accessory uses, portable sawmills and equipment used on-site in association with timber harvesting activities. See also Accepted Management Practices, Sawmill.

Frontage: The width of a lot abutting a road as measured at the street line.

Functionally Dependent Use: A use which cannot perform its intended purpose unless it is located or carried out in close proximity to water.

Gasoline Station: An establishment principally used for the sale of automobile or motor vehicle fuels, lubricants, and related motor vehicles products, and/or which has facilities for fueling motor vehicles. This definition specifically excludes automobile and motor vehicle repair services and sales, and the sale of food and unrelated convenience or grocery items. See also Motor Vehicle Service, Mixed Use.

Grading: The movement or replacement of topsoil or other material originating on the site and within the hazard area. Grading results in minor or no changes in topographic elevations. If new

material is brought from outside the hazard area and such new material is not offset with an equal or greater removal of material from the portion of the site within the hazard area, the new material shall be considered “fill” and shall not be considered grading.

Greenhouse/Nursery: The use of land, buildings and/or structures for the purpose of selling lawn and garden equipment, furnishings and supplies. This definition specifically does not include nurseries and greenhouses that are defined by the state as "Agriculture" or "Accepted Agricultural Practices" and are therefore exempted from these regulations. See also Agriculture, Accepted Agricultural Practices.

Group Home: A residential care home to be operated under state licensing or registration, serving not more than eight persons who have a handicap or disability as defined in 9 V.S.A. §4501. (See Section 4.7.)

Health Clinic: A building or part thereof used for the medical, dental, surgical, or therapeutic treatment of human beings, but does not include a public or private hospital or a professional office of a doctor located in his or her residence. See also Home Occupation, Office.

Height: see Building Height.

Historic Structure: Any structure that is: (a) listed individually in the National Register of Historic Places (a listing maintained by the Department of the Interior) or preliminarily determined by the Secretary of the Interior as meeting the requirements for individual listing on the National Register; (b) certified or preliminarily determined by the Secretary of the Interior as contributing to the historical significance of a registered historic district or a district preliminarily determined by the Secretary to qualify as a registered historic district; (c) individually listed on a state inventory of historic places in states with historic preservation programs which have been approved by the Secretary of the Interior; or (d) individually listed on a local inventory of historic places in communities with historic preservation programs that have been certified either: (i) by an approved state program as determined by the Secretary of the Interior or (ii) directly by the Secretary of the Interior in states without approved programs.

Home Child Care: In accordance with the Act [§4412(5)], a state registered or licensed child care home serving 6 or fewer children on a full-time basis, and up to 4 additional children on a part-time basis, which is conducted within a single unit family dwelling by a resident of that dwelling. (See Section 4.6.) See also Day Care Facility, Home Occupation.

Home Industry: A home-based business other than a home occupation which is conducted by the resident(s) of a single unit family dwelling, which is carried on within the principal dwelling and/or an accessory structure, and which meets all applicable requirements of these regulations (see Section 4.9). See also Home Occupation.

Home Occupation: A use conducted entirely within a minor portion of a single unit family dwelling which is conducted by resident unit family members, which is clearly incidental and secondary to the use of the dwelling for dwelling purposes, which does not have an undue adverse effect upon the residential character of the neighborhood, and which meets the requirements of these regulations (see Section 4.9). See also Bed & Breakfast, Home Child Care, Home Industry.

Hospital: An institution authorized by the state to provide primary and emergency health services and medical or surgical care to persons, primarily inpatients, suffering from illness, disease, injury, or other physical or mental conditions; and including, as an integral part of the institution, related facilities such as laboratories, outpatient facilities, training facilities, medical

offices, central service facilities, and staff residences. See also Health Clinic.

Hotel/Motel: A building containing bedrooms and other facilities rented out to provide overnight accommodations to transient travelers, and having a management entity operating the building(s) and providing such services as maid service, a central switchboard, or dining facilities to occupants of the lodging facility. See also Bed & Breakfast.

Industry, Light: A use providing for the manufacturing of goods predominately from previously prepared materials of finished products or parts, including processing, fabrication, assembly, treatment, packaging, incidental storage, sales and distribution of such products or components, but excludes basic industrial processing; and meets the specific standards in Section 4.10. See Also Industry, Heavy.

Industry, Heavy: The processing, treatment and/or conversion of raw or semi-finished materials into a different form or state. This definition does not include the processing of agricultural goods raised on the premises, which falls under the definition of agriculture, nor does it include agricultural and forest processing. See also Industry, Light.

Junk Yard: See Salvage Yard.

Kennel: The boarding, breeding, raising, grooming, or training of four or more dogs, cats, or other household pets of any age for a commercial use and/or which are not owned by the owner or occupant of the premises. See also Veterinary Clinic.

Land Development: In accordance with the Act [§4303(10)], the division of a parcel into two or more parcels, the construction, reconstruction, conversion, structural alteration, relocation or enlargement of any building or other structure, or any human-made change to improved or unimproved real estate, including but not limited to paving, mining, excavation, landfill, dredging, grading, or drilling, or storage of equipment or materials, or any changes in the use of any building or other structure or land or extension of use of land. For projects in the Special Flood Hazard Area, refer to the definition of **Development in the Flood Hazard Area Overlay**.

Letter of Map Amendment (LOMA): A letter issued by the Federal Emergency Management Agency officially removing a structure or lot from the flood hazard zone based on information provided by a certified engineer or surveyor. This is used where structures or lots are located above the base flood elevation and have been inadvertently included in the mapped special flood hazard area.

Level of Service: (1) A measure of the relationship between public service and facility capacity and the demand for public services and facilities; (2) for traffic, the operating conditions that a driver will experience while traveling on a particular street or highway, including frequency of stops, operating speed, travel time, traffic density and vehicle operating costs.

Loading Space: An off-street space that is at least twelve feet wide, thirty-five feet long, and fourteen feet high, not including the access driveway, and has direct access onto a road, which is used for the temporary parking of one licensed motor vehicle.

Lot: (1) Land occupied or to be occupied by a principal structure or use and its accessory structures and/or uses, together with required open spaces, having not less than the minimum area, width or depth required for a lot in the district in which such land is situated, and having frontage on a road, or other means of access as may be approved by the Board; (2) a portion of land in a subdivision or plat that is separated from other portions by a property line (see also Contiguous Land). A separate deed description for a parcel of land does not necessarily constitute a lot for zoning and development purposes.

Lot Area: The total land area within the property (boundary) lines of a lot, excluding any area within the boundaries of an existing or proposed road right-of-way.

Lot, Corner: Lot at the intersection of two roads (streets) which has an interior angle of less than 135 degrees. A lot abutting a curved street shall be considered a corner lot if the tangents to the curve at the points of intersection of the side lot lines intersect at an interior angle of less than 135 degrees.

Lot Depth: The mean horizontal distance from the street line of the lot to its opposite rear line measured at right angles to the building front line.

Lot Frontage: See Frontage.

Lot Line: Property line bounding a lot (parcel).

Lot Size: See Lot Area.

Lot Width: The width of a lot as measured at right angles to lot depth, at the required building front line.

Lowest Floor: The lowest floor of the lowest enclosed area (including basement). An unfinished floor or flood resistant enclosure, used solely for parking vehicles, building access, or storage in an area other than a basement area is not considered a building's lowest floor, provided that such enclosure is not built so as to render the structure in violation of applicable federal (44 CFR Section 60.3) non-elevation design requirements.

Maintenance: Periodic actions required to keep up a condition and that do not significantly change the materials or extent of an existing condition in the hazard area.

Manufactured Home: See Mobile Home.

Mean Sea Level: The standard datum to which base flood elevations shown on Flood Insurance Rate Maps, and typical contour elevations, are referenced.

Mixed Use: A building or parcel containing two or more uses which are otherwise allowed as permitted or conditional uses within the district in which the building or parcel is located (see Section 4.12). See also Accessory Use, Principal Use.

Mobile Home (or Manufactured Home): A structure, transportable in one or more sections, which is built on a permanent chassis and is designed for use with or without a permanent foundation when attached to the required utilities. The term "manufactured home" does not include a "recreational vehicle."

Mobile Home Park: A parcel of land under single or common ownership or control which contains, or is designed, laid out or adapted to accommodate three or more mobile homes.

Motor Vehicle Sales: A building, lot or portion thereof used for the sale and/or rental of automobiles, trucks, motorcycles, or other motor vehicles. This definition specifically excludes motor vehicle service, which may be allowed in designated zoning districts subject to review as a Mixed Use. See also Mixed Use, Motor Vehicle Service.

Motor Vehicle Service: An establishment whose principal purpose is the repair of motor vehicles, including body shops, general vehicle and engine repair shops, and rebuilding and/or reconditioning shops. Gasoline stations are specifically excluded from this definition. See also Gasoline Station, Motor Vehicle Sales.

Multi-Family-Unit Dwelling: As defined in the Act [§4303(41)], a building that contains three

or more dwelling units in the same building, including apartments or attached town houses. See also Dwelling Unit.

Municipal Land Use Permit: As defined in the Act [§4303(11)] to include, as issued by the municipality: (1) final zoning, subdivision, site plan or building permits or approvals relating to subdivision and land development; (2) septic or sewage system permits; (3) final official minutes of meetings which relate to permits or approvals, which serve as the sole evidence of such permits or approvals; (4) certificates of occupancy, compliance or similar certificates; and (5) any amendments to the previously listed, permits, approvals and/or certificates.

Natural Burial Ground: A cemetery maintained using ecological land management practices and without the use of vaults for the burial of unembalmed human remains or human remains embalmed using nontoxic embalming fluids and that rest in either no burial container or in a nontoxic, nonhazardous, plant-derived burial container or shroud. See also Cemetery.

New Construction: Structures or subsequent improvements to existing structures that were either a) Issued a permit by the Zoning Administrator after the effective date of these bylaws; or b) Structures or subsequent improvements to existing structures, not exempt from these bylaws, that occurred after the effective date of these bylaws. For purposes of these bylaws, “occur” shall mean: a) Substantial commencement of any development outside of the Special Flood Hazard Area; or b) Start of construction of any development within the Special Flood Hazard Area.

Nonconforming Structure: A structure or part of a structure that does not conform to the present bylaws but was in conformance with all applicable laws, ordinances, and regulations prior to the enactment of the present bylaws, including a structure improperly authorized as a result of error by the administrative officer.

Nonconforming Use: The use of land that does not conform to the present bylaws but did conform to all applicable laws ordinances, and regulations prior to the enactment of the present bylaws, including a use improperly authorized as a result of error by the administrative officer.

Non-residential: Includes, but is not limited to: small business concerns, churches, schools, nursing homes, farm buildings (including grain bins and silos), pool houses, clubhouses, recreational buildings, government buildings, mercantile structures, agricultural and industrial structures, and warehouses.

Office: A room, suite of rooms or building principally used for conducting the affairs of a business, profession, or service industry. This definition specifically excludes office space which is associated with home occupations, or is clearly accessory to another allowed principal use. It also specifically excludes the on-premise retail sale of goods and services. See also Home Occupation.

Open Space: Land not occupied by structures, buildings, roads, drive-ways, rights-of-way, recreational facilities, and parking lots. Open space may or may not be held in common.

Parking Space: An on- or off-street area, other than a loading or service area, which is to be used exclusively as a temporary storage space for one licensed private motor vehicle (see Section 3.13). A parking space shall be at least nine feet wide, and eighteen feet long, not including associated access and maneuvering space, and shall have access onto a public or private road.

Parking Facility: A separate, off-street parking area, garage or similar structure that is the principal use of a lot.

Perennial Stream: A watercourse or portion, segment, or reach of a watercourse, generally

exceeding 0.5 square miles in watershed size, in which surface flows are not frequently or constantly interrupted during normal seasonal low flow periods. Perennial streams that begin flowing subsurface during low flow periods, due to natural geologic conditions, remain defined as perennial. All other streams, or stream segments of significant length, shall be termed intermittent. A perennial stream shall not include the standing waters in wetlands, lakes, and ponds.

Person: Any individual, partnership, corporation, association, unincorporated organization, trust, or any other legal or commercial entity, including a joint venture or affiliated ownership which owns or controls land or other property to be subdivided and/or developed under the provisions of these regulations. The word "person" shall also include any municipality or other government agency.

Personal Service: A business which provides services of a personal nature, including but not limited to: laundry and dry cleaning, beauty and barber shops, shore repair, funeral services, and photographic studios.

Phasing: Development undertaken in a logical time and geographical sequence, typically to ensure that development is coordinated with the provision of services and facilities and will not result in adverse environmental impacts (e.g., erosion).

Place of Worship: A building used solely for purposes of assembly and worship by a legally established and recognized religious institution. This definition also includes such customary accessory structures such as parish houses.

Planned Unit Development (PUD): An area of land, controlled by a landowner, to be developed as a single entity for a number of dwelling units; the plan for which does not correspond in lot size, bulk, or type of dwelling, density, lot coverage, or required open space under these regulations except as a planned unit development. See also Subdivision, Major.

Planning Commission: The Hardwick Planning Commission, as created under the Act.

Plot Plan or Plat: A map or representation on paper, Mylar or other accepted material, of a piece of land subdivided into lots and roads, drawn to scale.

Pre-existing: A use or structure that was legally in existence as of the effective date of these regulations.

Principal Structure: A building or structure within which the main or principal use of the lot on which the building is located is conducted. See also Accessory Structure, Structure.

Private Club: A corporation, organization, or association or group of individuals existing for fraternal, social, recreational, or educational purposes, for cultural enrichment or to further the purposes of agriculture, which owns, occupies, or uses certain specified premises, which is not organized or operated for profit, and the benefits of which are available primarily to members only.

Private Family Cemetery: A burial ground located on private property used solely for the interment of immediate or extended family members, and not operated as a public, commercial, or religious cemetery. Private family cemeteries may include home burials as defined in 18 V.S.A. § 5319 (a). See Section 4.19.

Public Property: Owned, leased, held, used, and/or controlled exclusively for public purposes by the Town of Hardwick, or any other department or branch of government, or publicly-regulated utility.

Public Assembly Use: See Cultural Facility, Public Facility.

Public Improvement: Any improvement which shall be owned and/or maintained by the Town of Hardwick or other department or branch of state or federal government.

Public Facility/Utility: A building, utility or other facility owned, leased, held, used, and/or controlled exclusively for public purposes by a municipal, state or federal government, regulated utility or railroad. Such facilities include, but may not be limited to: municipal buildings and garages, water and wastewater facilities, power generation and transmission facilities, reservoirs, solid and hazardous waste management facilities, institutional facilities, and telephone, cable and electrical distribution lines. Public facilities and utilities, including distribution and service lines to individual uses, are allowed within all zoning districts unless otherwise specified, or specifically excluded, under district standards (see Section 4.13). See also Public Improvement, School, Telecommunications Facility.

Public Road: A road (street, highway) which is constructed within the boundaries of an officially deeded and municipally accepted public right-of-way (town highway), or a designated state road. See also Road.

Quarrying: The removal of rock by means of open excavation to supply material for construction, industrial or manufacturing purposes, and related operations such as blasting, crushing and the temporary storage of materials on site (see Section 4.7). See also Extraction of Earth Resources.

Reconstruct: To replace or rebuild a building or structure which has been substantially destroyed or demolished without regard to cause.

Recreation/Indoor: A building or structure designed, equipped and used for sports, leisure time, and other recreational activities, except for such facilities which are accessory to an approved educational facility or a residential use. This includes, but may not be limited to bowling alleys, movie theaters, pool halls, skating rinks, gymnasiums, and indoor swimming pools. See also Community Center, Cultural Facility.

Recreation/Outdoor: A facility for outdoor recreation, including but not limited to a stadium, tennis courts, golf courses, athletic fields, swimming pools, and trails for hiking, horseback riding, bicycling, snowmobiling, and cross-country skiing; except for such facilities which are accessory to an approved educational facility or a residential use.

Recreational Vehicle: A vehicle which is: (a) Built on a single chassis; (b) 400 square feet or less when measured at the largest horizontal projection; (c) Designed to be self-propelled or permanently towable by a light duty truck; and (d) Designed primarily not for use as a permanent dwelling but as a temporary living quarters for recreational, camping, travel, or seasonal use.

Replacement Structure: A new building placed in the same footprint as the pre-existing building and does not include a change in use.

Required Agricultural Practices (RAPs): Required practices for agriculture, including farm structures other than dwellings, as currently defined by the Commissioner of Vermont Department of Agriculture, Food and Markets in accordance with the Act [§4413(d)]. Also see *Agriculture*.

Residential Care Facility: A facility licensed by the state which provides primarily non-medical residential care services to seven or more individuals in need of personal assistance essential for sustaining the activities of daily living, or for the protection of the individual, on a 24-hour a day

basis. See also Day Care Facility, Group Home.

Residential Use: The use of a structure principally for dwelling purposes, and associated customary accessory uses such as a child care home or home occupation as defined under these regulations. For the purposes of these regulations, group homes shall also be considered a residential use of a single ~~unit~~~~family~~ dwelling.

Restaurant: Premises where food and drink are prepared, served and consumed primarily within the principal building.

Retail Store: Establishment where goods or merchandise are offered for retail sale or short term rental to the general public for personal, business or household consumption and services incidental to the sale of such goods are provided. This definition specifically excludes motor vehicle sales, motor vehicle service and gasoline stations, and the retail sale of gasoline in association with other retail uses.

Retreat Center: A facility used for professional, education or religious conclaves, meetings, or seminars and which may provide meals, housing and recreation for program participants. Such facilities shall not be open to the general public for meals or lodging. Kitchen and dining facilities shall be located in a single, centrally located building.

Ridgeline: The uppermost points on a profile of a ridge, hill, cliff, slope or face. It may coincide with the top (highest elevation) of a rock cliff or, where the bedrock is not exposed, the most obvious break in slope associated with the underlying bedrock. The term does not include intermediate terraces, steps, or elevations along the face of a slope.

River: The full length and width, including the bed and banks, of any watercourse, including rivers, streams, creeks, brooks, and branches which experience perennial flow. "River" does not mean constructed drainageways, including water bars, swales, and roadside ditches.

River Corridor: The land area adjacent to a river that is required to accommodate the dimensions, slope, planform, and buffer of the naturally stable channel and that is necessary for the natural maintenance or natural restoration of a dynamic equilibrium condition and for minimization of fluvial erosion hazards, as delineated by the Vermont Agency of Natural Resources in accordance with river corridor protection procedures (10 V.S.A. §1422).

Road: A right-of-way that provides access to four or more parcels. The word "road" shall mean the entire right-of-way, unless otherwise specified under these regulations. See also Driveway,




Figure 34-River Corridor Diagram showing room for river channel adjustments to minimize slope and erosive power.

Formatted: Font: Bold

Formatted: Font: Bold

Public Road.

Road Grade: Officially established grade (slope) of the road upon which a lot fronts. If there is no officially established grade, the existing grade of the road shall be taken as the road grade.

Salvage Yard: Any place of outdoor storage or deposit for storing, keeping, processing, buying, or selling junk or as a scrap metal processing facility as defined in 24 V.S.A. § 2241(12). “Salvage yard” also means any outdoor area used for operation of an automobile graveyard as defined in 24 V.S.A. § 2241. It does not mean a garage where wrecked or disabled motor vehicles are stored for less than 90 days for inspection or repairs, or a private transfer station or sanitary landfill which is licensed in compliance with the Vermont Statutes Annotated.

Sawmill: A facility where logs are temporarily stored, and sawn, split, shaved, stripped, chipped or otherwise processed to produce lumber or other wood products. Portable chippers, sawmills, or other equipment used on a temporary basis to process wood on the site of an active logging operation are excluded from this definition. See also Forestry.

School: A public, private or parochial institution licensed by the State of Vermont to provide educational instruction to students. Such facilities may also include accessory recreational and dining facilities, and be used as officially designated, temporary emergency shelters.

Screening: The use of planted vegetation, fencing, walls, natural topography or earthen berms to visually shield or obscure a structure or use from neighboring structures, properties, rights-of-way, and/or designated public vantage points.

Seasonal Camp: A detached dwelling unit which is not the primary residence of the owner or occupant and/or is occupied only on a part-time or seasonal basis, such as a hunting or summer camp. This definition shall include, but may not be limited to: a dwelling which lacks one or more of the basic amenities, services or utilities required for year-round or all weather occupancy, including but not limited to a winterized plumbing system, insulated walls and roof, heating source, or adequate water or wastewater disposal systems. In districts in which single ~~family-unit~~ dwellings are an allowed use, a seasonal camp may be permitted as a single ~~unit-family~~ dwelling.

Served by Water and Sewer: Any parcel that currently has Town water and sewer connections or is within the limits of the Urban Compact of Hardwick. The map of this area is available for viewing in the municipal office or online from the VTrans Online Map Center: <https://vtransmaps.vermont.gov>.

Service Area: An area designated on-site to accommodate customary accessory services to a principal use or structure, including but not limited to recycling and waste disposal facilities, snow storage, cart and bicycle storage, emergency service areas (e.g., fire lanes), and transit services.

Setback: The horizontal distance from a road, lot line, boundary or other delineated feature (e.g., a stream bank, shoreline, or wetland area), to the nearest structural element of a building, structure, or parking area on the premises. In the case of a road, the distance shall be measured starting 25 feet from the road centerline.

Sign: Any structure, display, device, or representation, which is designed or used to advertise, direct to, or call attention to anything, person, business activity or place, and is visible from any public highway or other public vantage point. This definition does not include the flag, pennant, or insignia of any nation, state, or municipality (see Section 3.14).

Sign Area: The total area that encompasses all sign faces and supporting structures, except for legs of supporting posts, and knobs of supporting posts that extend beyond the highest point of the sign face of freestanding signs.

Sign Face: The portion of the sign that contains a message, an image, or lettering.

Silviculture: See Forestry.

Single (One) ~~Family Unit~~ Dwelling: A building housing one principal dwelling unit designed and intended for year-round use. See also Accessory Dwelling, Dwelling Unit, Group Home, Mobile Home, Manufactured Home, Seasonal Dwelling.

Slope: The deviation of a surface from the horizontal, usually expressed in percent or degrees.

Special Flood Hazard Area: The floodplain within a community subject to a 1 percent or greater chance of flooding in any given year. For purposes of these regulations, the term “area of special flood hazard” is synonymous in meaning with the phrase “special flood hazard area”. This area is usually labeled Zone A, AO, AH, AE, or A1-30 in the most current flood insurance studies and on the maps published by the Federal Emergency Management Agency. Maps of this area are available for viewing in the municipal office or online from the FEMA Map Service Center: <http://msc.fema.gov> Base flood elevations have not been determined in Zone A where the flood risk has been mapped by approximate methods. Base flood elevations are shown at selected intervals on maps of Special Flood Hazard Areas that are determined by detailed methods. Please note, where floodways have been determined they may be shown on separate map panels from the Flood Insurance Rate Maps.

Start of Construction: Exclusively used for the purpose of a) determining the Flood Insurance Rate Map in effect at the time of construction, as well as the bylaw in effect, and b) identifying the total cost of substantial improvements to structures in the Special Flood Hazard Area. “Start of Construction” means the date the building permit was issued, provided the actual start of construction, repair, reconstruction, rehabilitation, addition placement, or other improvement occurred within 180 days of the permit date. The actual start means either the first placement of permanent construction of a structure on a site, such as the pouring of slab or footings, the installation of piles, the construction of columns, or any work beyond the stage of excavation; or the placement of a manufactured home on a foundation. Permanent construction does not include land preparation, such as clearing, grading and filling; nor does it include the installation of streets and/or walkways; nor does it include excavation for basement, footing, piers, or foundations or the erection of temporary forms; nor does it include the installation on the property of accessory structures, such as garages or sheds not occupied as dwelling units or not part of the main structure. For a substantial improvement, the actual start of construction means the first alteration of any wall, ceiling, floor, or other structural part of a building, regardless of whether that alteration affects the external dimensions of the building. (Note: This term is not synonymous with “Substantially Commenced” which is more broadly defined, and is used to track the expiration date of any zoning permit issued in the Town of Hardwick.)

Storage: The aggregation of materials, items, or objects whether natural or human-made; that is kept as a stockpile, collection, or inventory; where individual materials from the stockpile, collection, or inventory may change, but where the general footprint of the stored materials continues to be used for the same purpose; whether set upon the land or within a container, structure, or facility; and that would not otherwise be in compliance with these development standards.

Formatted: Font: Bold

Storage Facility(enclosed): One or more structures used for the storage of goods and materials, and not as a primary location or outlet for business or retail uses.

Stormwater Management: The collecting, conveyance, channeling, holding, retaining, detaining, infiltrating, diverting, treating or filtering of surface water and/or runoff, together with applicable nonstructural management techniques.

Story: Part of a building which is between one floor level and the next higher floor level, or ceiling above it.

Stream: Any surface water course in the Town of Hardwick as depicted by the U.S. Geological Survey on topographic maps or as identified through site investigation; excluding artificially created irrigation and drainage channels (see also Stream Channel).

Stream Channel: A defined area that demonstrates clear evidence of the permanent or intermittent passage of water and includes, but may not be limited to bedrock channels, gravel beds, sand and silt beds, and swales. A stream bank may define the usual boundaries, but not the flood boundaries, of a stream channel. Artificially created water courses such as irrigation and drainage ditches are specifically excluded from this definition. See also Stream.

Street: See Road.

Street Line: The boundary of an existing or proposed road (street) right-of-way. Where the width of a public road is not established, the street line shall be considered to be twenty-five feet from the center of the road.

Structure: A walled and roofed building, as well as a manufactured home, and any related built systems, including gas or liquid storage tanks. See also Building.

Subdivider: Any person who shall lay out for the purpose of transfer of ownership or right to use any subdivision or part thereof. The term shall include an applicant for subdivision approval.

Subdivision: The division of any parcel of land into two or more parcels for the purposes of immediate or future sale, conveyance, or development. The term "subdivision" includes resubdivisions, amended subdivisions, lot line (boundary) adjustments, and the division of land held in common among several owners. See also Parcel; Subdivision, Major; Subdivision, Minor.

Subdivision, Major: All subdivisions other than minor subdivisions, including but not limited to a subdivision and/or subsequent resubdivision of a parcel(s) to create four or more lots, and all planned residential and planned unit developments. See also Subdivision; Subdivision, Minor.

Subdivision, Minor: (1) Lot line or boundary adjustments between pre-existing lots which do not create additional or nonconforming lots, (2) the subdivision of land into three or fewer lots, each of which meets the frontage requirements for the zoning district in which it is located, within a five year period; or (3) amendments to an approved subdivision (including a the resubdivision of a subdivided parcel) which do not substantially alter the nature of the approved subdivision, result in the creation of a total of more than three lots, or violate the original conditions of approval. See also Subdivision; Subdivision, Major.


Substantial Damage: For purposes of floodplain management, includes damage of any origin sustained by a structure whereby the cost of restoring the structure to its before-damaged conditions would equal or exceed 50 percent of the market value of the structure before damage occurred.

Substantial Improvement: For purposes of floodplain management, includes any reconstruction, rehabilitation, addition, or other improvement of a structure after the date of adoption of this bylaw, the cost of which, over one year, or over a period of a “common plan of development,” cumulatively equals or exceeds fifty percent of the market value of the structure before the “start of construction” of the improvement. The term includes structures which have incurred “substantial damage,” regardless of the actual repair work performed. The term does not, however, include either: a) Any project for improvement of a structure to address violations of state or local health, sanitary, or safety code specifications, which have been identified by the local code enforcement official and which are the minimum necessary to assure safe living conditions; or b) Any alteration of a “historic structure,” provided that the alteration will not preclude the structure’s continued designation as a “historic structure.”

Substantially commenced: For purposes of all aspects of this bylaw, except for floodplain management, includes visible signs of activity on new construction of a new structure or repair of a damaged structure, including the commitment of resources and materials to a project, such as the pouring of a foundation, the completion of a frame, or the delivery of required building materials to the construction site.

Substantially Completed: The completion of a permitted building or structure to the extent that it may be safely occupied for its intended use.

Telecommunications Facility: A tower or other support structure, including antennae, that will extend 20 or more feet vertically, and related equipment, and base structures to be used primarily for communication or broadcast purposes to transmit or receive communication or broadcast signals.



Top of Bank: The point along a streambank where an abrupt change in slope is evident, and where the stream is generally able to overflow the banks and enter the adjacent floodplain during flows at or exceeding the average annual high water stage.

Formatted: Font: Bold

Top of Slope: A break in slopes adjacent to steep-banked streams that have little or no floodplain; or a break in slope where the side slopes adjacent to an incised, or deeply cut, channel meet floodplains that have been abandoned or are undergoing abandonment.

Formatted: Font: Bold

Tourist Home: See Bed & Breakfast.

Tower: A vertical structure for antenna(s) and associated equipment that provide telecommunication services.

Figure 5-4 Diagram showing the Top of Bank where stream flows onto a floodplain and Top of Slope where floodplain access is not present.

Town Plan: The Hardwick Town Plan as most recently adopted.

Town Highway: See Public Road.

Trailer: See Camper.

| **Two-Family-Unit Dwelling:** Per 24 V.S.A. [§4303(39)], means a residential building that has two dwelling units in the same building and neither unit is an accessory dwelling unit. See also Duplex, Accessory Dwelling, and Dwelling Unit.

Use: The purpose for which a building, structure, or parcel of land is designed, intended, occupied or used.

Variance: As set forth in the Act [§4469], permission to depart from the literal requirements of these regulations. Such permission is limited to departures from zoning requirements relating to frontage, setback, yard, coverage and height requirements (see Section 7.4). See also Degree of Nonconformity, Nonconforming Structure, and Nonconforming Use.

Veterinary Clinic: A building or premises used for the medical or surgical treatment and temporary boarding of domestic animals and pets receiving medical or surgical treatment. See also Kennel.

Violation: The failure of a structure or other development to be fully compliant with this bylaw. A structure or other development without the elevation certificate, other certifications, or other evidence of compliance required in 44 CFR 60.3 is presumed to be in violation until such time as that documentation is provided.

Warehouse: See Storage Facility (enclosed).

Wireless Telecommunication Service: Any commercial mobile service, wireless service, common carrier wireless exchange service, cellular service, personal communication service (PCS), specialized mobile radio service, paging service, wireless data service or public or private radio dispatch service.

Yard: The area on a lot, defined by front, side or rear setback distances, which is not occupied by a building or structure. See also Setback.

Yard Sale: The casual sale of personal property open to the general public and generally denoted by the terms "garage sale, " "attic sale, " "lawn sale, " "flea market, " "barn sale" or similar phrase.

Zoning Administrator: The Hardwick Administrative Officer.